

FENCE DETAILS

Proposed School Hall Extension
'The William Older School Hall', Arundel Road, Angmering, West Sussex,
BN16 4LP



Fig 01 - View of post & rail security fence around existing William Older School Charity owned playgroup building.

Specification:

Posts & Rails to be sawn & treated timber with green chainlink fence fixed externally.

Posts - 75 x 125mm x 1275 high @ 2.7 metre cts.

Intermediate posts - 38 x 100mm high @ 2.7 metre cts.

Top Rail - 38 x 100mm (Top of which is 1200mm above d).

Intermediate Rail 30 x 100mm

Bottom Rail - 38 x 100mm (Bottom of which is 225mm above g.l.)



Fig 02 – View of post & rail fence separating the parking area & William Older School Charity owned adjoining agricultural use land