506900m.E

507000m.E

104500m.N

104400m.N

STATION SCHEDULE

Station	Easting(m)	Northing(m)	Level(m)
1	506933.323	104468.956	5.71
2	506941.587	104444.475	5.94
3	506955.414	104486.201	5.60
4	506970.991	104483.578	6.19
5	506958.052	104414.470	5.80
6	506961.932	104406.335	5.75
7	506928.587	104390.676	5.77
8	506923.341	104382.963	6.79
9	506905.566	104384.081	6.02
10	506926.167	104377.053	7.52
11	506887.013	104391.961	5.48
12	506913.536	104393.653	6.08
13	506872.622	104409.870	5.58
14	506904.157	104439.886	5.48
15	506911.184	104421.244	5.73
16	506926.742	104405.155	6.16

QLS Chartered Surveyors

Offington Land Surveys
29 Offington Drive
Worthing
West Sussex BN14 9PW
Tel/fax 01903 267614

Job

CHANDLERS BMW SITE ANGMERING

Plot Scale: 1:200
Sheet size: A0 Portrait

Copyright © August 2012

Drawing No.

10410812 Site Plan

STANDARD REFERENCE

Datum Used Newlyn

Locall survey translated to Newlyn and OSGB36 by direct acquisition of control stations using RTK GPS to accuracy +/-25mm RMS

Survey Station Shown Thus:

Foul Water Drainage

Storm Water Drainage

Water Mains

Gas Mains

Electricity Cable

British Telecom Cable

True north direction shown is indicative only

The details shown hereon relating to all underground services are as obtained by normal survey observation and methods and also by reference to available records. Although all reasonable efforts have been made no guarantee can be given for the completeness or accuracy of this information

ABBREVIATIONS

BT British Telecom IC Inspection Chamber
CATV Television Cable Pit IL Invert Level
CE Cleaning Eye LP Lamp post
CL Cover Level MH Manhole
CM Cable Marker RG Road Gully
CP Catch Pit RWP Rain Water Pipe
ECP Electricity Cable Pit SC Stop Cock
EP Electricity Pole SV Stop Valve
FA Fire Alarm SVP Soil & Vent Pipe
FH Fire Hydrant TP Telegraph Pole
FL Floor Level VP Vent Pipe
G Gully WM Water Meter
WO Water Wash Out

FENCES

FCB Close Boarded FPan Panel
FCP Chestnut Paling FPR Post & Rail
FIR Iron Railings FPW Post & Wire
FPal Metal Palisade FTr Trellis