



NOTES



Permeable storage area

150mm thickness of Type 3 stone.

Permeable geotextile.

150mm thickness 6F2 granular material.



Tarmac access

30mm thickness of 10mm size close graded surface course.

55mm thickness of 20mm size dense base course.

250mm thickness of DTP Type 1 granular material.

A	First Issue.			
REV	DESCRIPTION	SIG	CHK	DATE

SCALE WHEN PLOTTED AT A1 1:125			DRAWING STATUS PRELIMINARY	
DRAWN MW	CHECKED SJE	DATE 13-04-17	DRAWING NUMBER 43413/001	REV A