



- Roads, footways and parking bays which form part of the highway to be adopted under Section 38 of the Highways Act 1980 shall comply with the requirements of the Adopting Authority.
- Sewers to be adopted under Section 104 of the Water Industries Act 1991 shall comply with the Water Industry Act 1991 and the Sewerage Byelaws as amended, together with any amendments specified by the Adopting Water Authority.
- All pipes to be laid in adoptable sewerage shall be either cast-iron to BS EN 268 or concrete to BS EN 1916 and BS 5911. Part 1 with Class S bedding unless otherwise stated. With approval of the Adopting Authority, reinforced concrete or reinforced PVC pipes complying with the relevant provisions of BS EN 13476 may be used.
- Where cover to a pipe is more than 1200mm under adoptable highway the trench shall be filled to form the carriageway with well compacted D7 type 1 material.
- Where cover to a pipe is less than 1200mm under adoptable carriageway it shall be provided with concrete to BS EN 1916 and BS 5911. Part 1 with Class S bedding unless otherwise stated. The back fill of the trench shall be compacted D7 type 1 material. Where concrete bed and surround is specified, flexibility of joints to be maintained by using compressible bitumen impregnated fibreglass at each pipe joint.
- All existing drainage invert levels, diameters and locations are to be checked by the Contractor prior to the commencement of any proposed drainage works. Any difference between actual and drawn details is to be reported to the Engineering Services immediately.
- All drainage works to be undertaken prior to the start of any proposed works.
- Positions of existing 'sewerage infrastructure' undertaken appears adequate or to crossing proposed sewers to be checked by the Contractor prior to starting work.