

Street lighting to be in accordance with the design approved by West Sussex County Council.

Column

6.0m straight shaft (no outreach bracket),
Coating Amercoat

71P/PSX 700 polysiloxane and Amercoat
4560 GF epoxy glass flake

Colour as specified by the Authority

Luminaire

Philips/WRTL "Mini Lumia" post top mounted,
12-20 LED, 1.4klm

upwards (other lumens outputs may be
required for other options).

Cool White
wired for Dali control and fitted with
Mayflower six pin NEMA socket,
post-top mounted, maximum tilt 5
degrees. Luminaire to be supplied
with manufacturers 25 year warranty.

Switch Controls

Mayflower Complete Lighting Control Dali
internal Luminaire on an in ground
lantern. Switching to 35/18 per night
(12-5:30 off or Dimmed to 60%
light output)



		A5 40 49 48 45 A6 40 49 48 45 21 41 45 48 45	
<h1>PRELIMINARY</h1>			
REV. No.	DATE	DESCRIPTION	INITIALS
Client			
		Monarch House, Barton Lane, Abingdon, Oxon, OX14 3NB Tel: 01235 555171 Fax: 01235 523226	
Project West End Nursery, Amgering			
Title	Scale	Date	Drawing No.
Street Lighting Plan Sheet 3	1:200@A0	Nov 17	5356:62
	Checked JTG	Drawn JS	