


To register to receive notification of planning applications in your area please go to
<https://www1.arun.gov.uk/planning-application-finder>

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF
www.arun.gov.uk

Sign up to our newsletter [here](#)



From: Laura Gibbons <laura.Gibbons@arun.gov.uk>
Sent: 02 November 2021 15:23
To: Simon Davis <Simon.Davis@arun.gov.uk>
Subject: RE: Planning Consultation on: A/212/21/DOC

Hi Simon,

Quick response as I am on leave next week. The diffusers should not be located at the base of the permeable paving, the strategy was to drain hard surfaces via infiltration but to provide these with overflows to the network.

I believe the drainage has been constructed on site, it may be we need to go out and have a look at what they have constructed. Which may require a bit of taking up of surfaces in locations of our choosing.

Thanks,

Laura Gibbons

Drainage Engineer

Engineering Services

Please note that I work Tuesdays 08:00-16:00 for Arun only.



T: 01903 221374

E: laura.gibbons@arun.gov.uk

Arun District Council, Civic Centre, Maltravers Rd, Littlehampton, West Sussex, BN17 5LF

From: Glenn Gasson
Sent: 02 November 2021 15:18
To: Simon Davis <Simon.Davis@arun.gov.uk>
Cc: Laura Gibbons <Laura.Gibbons@arun.gov.uk>
Subject: RE: Planning Consultation on: A/212/21/DOC

CAUTION: This email originated from outside of the organisation. You should take extra care when clicking links or opening attachments - if you are unsure the content is safe contact the IT Helpdesk before clicking or opening.


Hi Simon

Thanks for your prompt response, please note the following:

- It appears that there are some errors with the levels stated, please can the applicant review to ensure any typos are corrected to ensure that diffusers are located above formation level and a gravity connection from paving areas to the surface water drainage network can be achieved. The construction detail drawing implies that diffusers are the inlets to the permeable paving and that fin drains are proposed as outlets. However the arrangement of the diffusers and the levels stated on the layouts imply that the diffusers are actually being used as collectors at the base of permeable paving. My understanding is that the permeable paving is meant to infiltrate with high level overflow to the network, therefore levels should be revised so that the diffusers/ collectors are not set at the very base of the sub-base - I've revised the details to include the diffuser unit which is the Formpave diffuser unit detail used on site.
- Please can the applicant confirm whether any further changes beyond surface type and the use of diffusers are included within the latest proposals. -- I can confirm that there are no further changes other than the change in driveway material and the diffusers are included in the latest proposals.

Kind regards


Glenn Gasson
Technical Manager



Woodmans Arms, Hammerpot, Angmering, West Sussex, BN16 4EU

Website: www.gdhomes.co.uk

GD Concepts Limited Company Registration: 11683803



This email and any files transmitted with it are confidential and intended solely for the use of the individual or entity to whom they are addressed. If you received this email in error, please notify the system manager.

Recipient should check this mail and any attachments for the presence of viruses. The company accepts no liability for damage or loss of revenue caused by any virus or gateway transmitted by this mail.