

Trees						
Number	Abbreviation	Species	Height	Girth	Pot Size	Density
2	ACECAM	Acer campestre	min. 550cm	35-40cm	10L	Semi-Mature :Clear Stem min. 200 :RB Counted
148	Ac	Acer campestre	300-350cm	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB Counted
48	AcE	Acer campestre 'Elsrijk'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
88	AcR	Acer campestre 'Red Shine'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
14	ACWC	Acer campestre 'William Caldwell'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
4	Agl	Alnus glutinosa	min. 450cm	30-35cm		Semi-Mature :Clear Stem min. 200 :RB Counted
12	AMEBA	Amelanchier 'Ballerina'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
32	AMLAN	Amelanchier lamarckii	300-350cm			Multi-Stemmed :Bushy :3 Stems :3x :RB Counted
10	ARBUN	Arbutus unedo	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
252	BETPE	Betula pendula	400-450cm	16-18cm		Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB Counted
30	BETPE	Betula pendula	350-400cm	14-16cm		Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB Counted
30	BTUM	Betula utilis 'Moonbeam'	350-400cm	14-16cm		Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB Counted
24	BETJACA	Betula utilis jacquemontii	250-300cm			Multi-Stemmed :3 Stems :RB Counted
10	CARBET	Carpinus betulus	min. 450cm	16-18cm		Extra Heavy Standard :Clear Stem min. 200 :5 brks :3x :RB Counted
48	CARBET	Carpinus betulus	350 min.	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB Counted
6	Cbe	Carpinus betulus	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB Counted
37	CbC	Carpinus betulus 'Columnaris'	400-450cm	14-16cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
94	CbFF	Carpinus betulus 'Frans Fontaine'	350-400cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
2	Cej	Cercidiphyllum japonicum	min. 400cm	30-35cm		Semi-Mature :Clear Stem min. 200 :RB Counted
22	COREWW	Cornus 'Eddie's White Wonder'	200-250cm			Multi-Stemmed :Bushy :3 Stems :3x :RB Counted
12	Corm	Cornus mas	2.5-3.0m			Multi-Stemmed :3/5 brks :RB Counted
68	Ccol	Corylus columna	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
4	CYDOB	Cydonia oblonga	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
2	FAGSY	Fagus sylvatica	min. 450cm	30-35cm		Semi-Mature :Clear Stem min. 200 :RB Counted
60	la	Ilex aquifolium	300-350cm	12-14cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB Counted
6	la	Ilex aquifolium	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
2	Jr	Juglans regia	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB Counted
2	LIRTU	Liriodendron tulipifera	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB Counted
4	MAGKO	Magnolia kobus	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
7	MAGST	Magnolia stellata	1.5-1.8m			Multi-Stemmed :C Counted
22	MALSN	Malus 'Snowcloud'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
118	MALSY	Malus sylvestris	450-500cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
10	MALTRI	Malus trilobata	300-350cm	14-16cm		Heavy Standard :Clear Stem min. 200 :3x :RB Counted
40	MORNI	Morus nigra	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
52	PRUBOUA	Prunus 'Sunset Boulevard'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
4	Pav	Prunus avium	350-400cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
82	Pav	Prunus avium	300-350cm	12-14cm		Advanced Nursery Stock :3x :RB Counted
30	PaP	Prunus avium 'Plena'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
36	Ppa	Prunus padus	400-450cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
24	PRSA	Prunus sargentii	350-400cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
1	PRUSU	Prunus subhirtella	400-450cm	12-14cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
6	PRUROSA	Prunus subhirtella 'Autumnalis Rosea'	min. 400cm	16-18cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
12	PRSU	Prunus subhirtella 'Autumnalis'	350-400cm	14-16cm		Heavy Standard :Clear Stem min. 200 :3x :RB Counted
40	PcC	Pyrus calleryana 'Chanticleer'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
30	PcC	Pyrus calleryana 'Chanticleer'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
4	PYCB	Pyrus communis 'Beech Hill'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
18	QUERO	Quercus robur	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB Counted
24	Qr	Quercus robur	350-400cm	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB Counted
30	ROBPSUN	Robinia pseudoacacia 'Unifoliola'	250-300cm			Heavy Standard :Clear Stem 175-200 :3x :RB Counted
70	Sar	Sorbus aria	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
54	SaLu	Sorbus aria 'Lutescens'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
6	Sau	Sorbus aucuparia	350-425cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
16	Sinc	Sorbus incana	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB Counted
58	SORTO	Sorbus torminalis	400-450cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted
12	Tc	Tilia cordata	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB Counted
174	TilcorG	Tilia cordata 'Greenspire'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB Counted

Specimen Shrubs

Number	Species	Height	Pot Size	Specification	Density
4	Cotinus coggygria 'Royal Purple'	100-125cm	10L	Bushy :5/7 brks :C	Counted
3	Hydrangea arborescens 'Annabelle'	80-100cm	10L	Bushy :6/9 brks :C	Counted
12	Rhus glabra	100-125cm	10L	Multi stem :C	Counted

Hedges

Number	Species	Height	Pot Size	Specification	Density	Length
12	Carpinus betulus	1.2-1.5 m		Feather :2 Stems :2x :B	0Ctr	5m
534	Carpinus betulus	1.2-1.5 m		Feather :2 Stems :2x :B	1Ctr	261m
66	Escallonia 'Apple Blossom'	40-60cm	3L	Bushy :4 brks :C	1Ctr	33m
90	Ilex aquifolium	80-100cm	10-12L	Leader With Laterals :C	0Ctr	40m
418	Lonicera nitida	60-80cm	3L	Bushy :3/5 brks :C	0Ctr	182m
71	Rosa 'Kent'	40cm	3L	Bushy :5 brks :C :Bushy :3 brks :C	0Ctr	28m
25	Willow tunnel				1/m	24m

Climbers

Number	Species	Height	Pot Size	Specification	Density
9	Clematis montana 'Elizabeth'		2L	Several Shoots :Caned	Counted
20	Hedera colchica 'Sulphur Heart'		2L	Several Shoots :Caned	Counted
18	Jasminum nudiflorum		3L	Several Shoots :Caned	Counted
26	Parthenocissus tricuspidata 'Veitchii'				Counted
4	Schizophragma hydrangeoides		3L	Several Shoots :Caned	Counted

- Notes:
- All contractors must visit the site and be responsible for taking and checking dimensions.
 - All construction information should be taken from figured dimensions only.
 - Any discrepancies between drawings, specifications and site conditions must be brought to the attention of the supervising officer.
 - This drawing and the works depicted are the copyright of HBA.

-					
Rev.	Date	By	Description	Ckd	Aprd
Drawing Status: PLANNING					



landscape architecture ■ urban design
expert witness ■ environmental planning

Huskinson Brown is the trading name of David Huskinson Associates Limited
17 Upper Grosvenor Road Tunbridge Wells Kent TN11 2DU
tel: 01892 527628 email:office@huskinsonbrown.co.uk www.huskinsonbrown.co.uk

All dimensions to be checked on site

Client
CALA (South Home Counties) Ltd/ Bellway Homes Ltd

Project
Land north of Water Lane, Angmering

Drawing
Planting Schedule

Sheet 1 of 4	Scale: NTS
Date 18:05:22	Rev. -
Drawing No. HBA-875-235	
File location: P:\875 Water Lane\Drawings\HBA\Current Drawings\Detail Design	

Dormouse Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
206	Acer campestre	60-80cm	10%		1 + 1 :BR	2Ctr
43	Betula pendula	250-300cm	2%		Multi-Stemmed :RB	2Ctr
64	Betula pendula	125-150cm	3%		Feather :3 brks :BR	2Ctr
511	Corylus avellana	60-80cm	25%		1 + 1 :BR	2Ctr
105	Crataegus monogyna	40-60cm	5%		1 + 1 :BR	2Ctr
43	Ligustrum vulgare	60-80cm	2%		0/1 :Branched :BR	2Ctr
23	Malus sylvestris	250-300cm	1%		Standard :RB	2Ctr
43	Malus sylvestris	60-80cm	2%		1 + 1 :BR	2Ctr
511	Quercus robur	60-80cm	25%		1 + 1 :BR	2Ctr
511	Quercus robur	150-175cm	25%		Feather :3 brks :BR	2Ctr

Hedgerow Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
265	Acer campestre	125-150cm	5%		Feather :3 brks :BR	4/m
521	Acer campestre	60-80cm	10%		1 + 1 :BR	4/m
2575	Crataegus monogyna	40-60cm	50%		1 + 1 :BR	4/m
59	Ilex aquifolium	60-80cm	1%	3L	Bushy :C	4/m
111	Ligustrum vulgare	60-80cm	2%		0/1 :Branched :BR	4/m
59	Malus sylvestris	60-80cm	1%		1 + 1 :BR	4/m
111	Prunus avium	125-150cm	2%		Feather :3 brks :BR	4/m
111	Prunus padus	60-80cm	2%		1 + 1 :BR	4/m
1292	Prunus spinosa	60-80cm	25%		1 + 1 :BR	4/m
111	Viburnum opulus	60-80cm	2%		1 + 1 :BR	4/m

Thorny Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
3249	Crataegus monogyna	40-60cm	45%		1 + 1 :BR	3/m²
1231	Ilex aquifolium	60-80cm	17%	3L	Bushy :C	3/m²
222	Ligustrum vulgare	60-80cm	3%		0/1 :Branched :BR	3/m²
1085	Prunus spinosa	60-80cm	15%		1 + 1 :BR	3/m²
725	Rosa canina	60-80cm	10%		1 + 1 :BR	3/m²
725	Ulex europaeus	40-60cm	10%		1 + 1 :BR	3/m²

Woodland Buffer Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
55	Acer campestre	60-80cm	5%		1 + 1 :Transplant :BR	2Ctr
106	Acer campestre	125-150cm	10%		3 brks :Feather :BR	2Ctr
498	Crataegus monogyna	40-60cm	48%		1 + 1: Transplant :BR	2Ctr
13	Ilex aquifolium	60-80cm	1%	3L	Bushy :C	2Ctr
23	Ligustrum vulgare	60-80cm	2%		0/1 :Branched :BR	2Ctr
23	Lonicera periclymenum	20-40cm	2%	2L	Branched: Cutting :C	2Ctr
13	Malus sylvestris	60-80cm	1%		1 + 1 :Transplant :BR	2Ctr
23	Prunus avium	250-300cm	2%		Standard :RB	2Ctr
23	Prunus padus	125-150cm	2%		Feather :3 brks :BR	2Ctr
261	Prunus spinosa	60-80cm	25%		1 + 1: Transplant :BR	2Ctr
23	Viburnum opulus	60-80cm	2%		1 + 1: Transplant :BR	2Ctr

Woodland Edge Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
81	Acer campestre	60-80cm	5%		1 + 1 :BR	2Ctr
160	Acer campestre	125-150cm	10%		Feather :3 brks :BR	2Ctr
704	Crataegus monogyna	40-60cm	45%		1 + 1 :BR	2Ctr
18	Ilex aquifolium	60-80cm	1%	3L	Bushy :C	2Ctr
35	Ligustrum vulgare	60-80cm	2%		0/1 :Branched :BR	2Ctr
35	Lonicera periclymenum	20-40cm	2%	2L	Branched :CG	2Ctr
18	Malus sylvestris	60-80cm	1%		1 + 1 :BR	2Ctr
35	Prunus avium	250-300cm	2%		Standard :RB	2Ctr
35	Prunus padus	125-150cm	2%		Feather :3 brks :BR	2Ctr
363	Prunus spinosa	60-80cm	23%		1 + 1 :BR	2Ctr
81	Quercus robur	150-175cm	5%		Feather :3 brks :BR	2Ctr
35	Viburnum opulus	60-80cm	2%		1 + 1 :BR	2Ctr

Amenity Mix 1

Number	Species	Height	Mix %	Pot Size	Specification	Density
134	Cornus alba 'Sibirica'	60-80cm	35%	5L	Branched: 4 brks :C	3/m²
59	Corylus avellana	80-100cm	15%		1 + 2: Transplant - seed raised: Branched: 4 brks :BR	3/m²
59	Ilex aquifolium 'Golden van Tol'	60-80cm	15%	5L	Branched :3/6 brks :C	3/m²
134	Rubus cockburnianus	60-80cm	35%	5L	Branched :3/6 brks :C	3/m²

Amenity Mix 2

Number	Species	Height	Mix %	Pot Size	Specification	Density
175	Cornus stolonifera 'Flaviramea'	60-80cm	20%	5L	Branched :5/6 brks :C	4/m²
175	Cotoneaster 'Coral Beauty'	30-40cm	20%	3L	Branched :3/4 brks :C	4/m²
175	Epimedium x perralchicum 'Frohnleiten'		20%	2L	Full Pot :C	4/m²
175	Hypericum 'Hidcote'	40-60cm	20%	3L	Branched :5/6 brks :C	4/m²
175	Polystichum aculeatum		20%	2L	Full Pot	4/m²

Amenity Mix 3

Number	Species	Height	Mix %	Pot Size	Specification	Density
402	Anemanthele lessoniana		20%	3L	Full Pot	4/m²
500	Crocsmia 'Spitfire'		25%	2L	Full Pot :C	4/m²
597	Mahonia nitens 'Cabaret'	30-40cm	30%	3L	Branched :3/4 brks :C	4/m²
500	Miscanthus sinensis 'Gracillimus'		25%	5L	Full Pot	4/m²

Amenity Mix 4

Number	Species	Height	Mix %	Pot Size	Specification	Density
224	Cotoneaster 'Coral Beauty'	30-40cm	25%	3L	Branched :3/4 brks :C	4/m²
224	Euonymus alatus	40-60cm	25%	3L	Branched :5/6 brks :C	4/m²
224	Euonymus fortunei 'Emerald Gaiety'	20-30cm	25%	3L	Bushy :3/4 brks :C	4/m²
224	Spiraea japonica 'Goldflame'	30-40cm	25%	3L	Branched :5/6 brks :C	4/m²

Amenity Mix 5

Number	Species	Height	Mix %	Pot Size	Specification	Density
255	Bergenia 'Perfect'		30%	2L	Full Pot	5/m²
338	Brachyglottis 'Sunshine'	40-60cm	40%	3L	Bushy :3/5 brks :C	5/m²
255	Vinca minor 'Burgundy'	30-40cm	30%	3L	Branched :3/6 brks :C	5/m²

Amenity Mix 7

Number	Species	Height	Mix %	Pot Size	Specification	Density
96	Allium schoenoprasum		20%	2L	Full Pot :C	4/m²
96	Bergenia 'Bressingham White'		20%	2L	Full Pot :C	4/m²
142	Osmanthus burkwoodii	60-80cm	30%	5L	Branched :3/5 brks :C	4/m²
142	Polystichum setiferum		30%	3L	Full Pot	4/m²

Amenity Mix 8

Number	Species	Height	Mix %	Pot Size	Specification	Density
140	Bergenia 'Bressingham White'		20%	3L	Full Pot :C	5/m²
174	Geranium phaeum 'Album'		25%	2L	Full Pot	5/m²
140	Liriope muscari 'Monroe'		20%	2L	Full Pot	5/m²
243	Sarcococca humilis	40-60cm	35%	3L	Bushy :3 brks :C	5/m²

Amenity Mix 9

Number	Species	Height	Mix %	Pot Size	Specification	Density
93	Hedera colchica 'Sulphur Heart'	80-100cm	50%	3L	3/5 brks :Caned	3/m²
93	Skimmia japonica 'Kew White'	60-80cm	50%	3L	Bushy :5/6 brks :C	3/m²

Amenity Mix 10

Number	Species	Height	Mix %	Pot Size	Specification	Density
117	Bergenia 'Bressingham White'		30%	3L	Full Pot :C	4/m²
117	Hebe 'Green Globe'	40-60cm	30%	3L	Bushy :5 brks :C	4/m²
78	Sarcococca humilis	40-60cm	20%	3L	Bushy :3 brks :C	4/m²
78	Skimmia confusa 'Kew Green'	40-60cm	20%	3L	Bushy :3 brks :C	4/m²

Amenity Mix 11

Number	Species	Height	Mix %	Pot Size	Specification	Density
26	Anemanthele lessoniana		25%	3L	Full Pot	3/m²
26	Miscanthus sinensis 'Gracillimus'		25%	5L	Full Pot	3/m²
51	Photinia fraseri 'Red Robin'	80-100cm	50%	5-7.5L	Bushy :5/6 brks :C	3/m²

Amenity Mix 12

Number	Species	Height	Mix %	Pot Size	Specification	Density
47	Cornus alba 'Sibirica'	60-80cm	25%	5L	Branched: 4 brks :C	2/m²
29	Ilex aquifolium 'Golden van Tol'	60-80cm	15%	5L	Branched :3/6 brks :C	2/m²
29	Pachysandra terminalis 'Green Carpet'	20-30cm	15%	3L	Bushy :3/5 brks :C	2/m²
38	Rosa rugosa 'Alba'	30-40cm	20%	3L	Branched :Bushy :3/4 brks :C	2/m²
47	Rubus cockburnianus	60-80cm	25%	5L	Branched :3/6 brks :C	2/m²

Notes:

- All contractors must visit the site and be responsible for taking and checking dimensions.
- All construction information should be taken from figured dimensions only.
- Any discrepancies between drawings, specifications and site conditions must be brought to the attention of the supervising officer.
- This drawing and the works depicted are the copyright of HBA.

-					
Rev.	Date	By	Description	Ckd	Aprd
Drawing Status:					
PLANNING					



landscape architecture ■ urban design
expert witness ■ environmental planning

Huskinson Brown is the trading name of David Huskinson Associates Limited
17 Upper Grosvenor Road Tunbridge Wells Kent TN11 2DU
tel: 01892 527629 email:office@huskinsonbrown.co.uk www.huskinsonbrown.co.uk

All dimensions to be checked on site

Client

CALA (South Home Counties) Ltd/ Bellway Homes Ltd

Project

Land north of Water Lane, Angmering

Drawing

Planting Schedule

Sheet	Scale:
2 of 4	NTS
Date	Drawing No.
18:05:22	HBA-875-236
Rev.	-

File location:
P:\875 Water Lane\Drawings\HBA\Current Drawings\Detail Design

Amenity Mix 13

Number	Species	Height	Mix %	Pot Size	Specification	Density
232	Astrantia major 'Rubra'		15%	2L	Full Pot :C	5/m ²
232	Bergenia 'Sunningdale'		15%	2L	Full Pot :C	5/m ²
232	Geranium oxonianum 'Wargrave Pink'		15%	2L	Full Pot :C	5/m ²
304	Hebe 'Green Globe'		20%	3L	Bushy :5 brks	5/m ²
304	Liriope muscari 'Big Blue'		20%		Full Pot :C	5/m ²
232	Miscanthus sinensis 'Zebrinus'		15%	5L	Full Pot	5/m ²

Amenity Mix 14

Number	Species	Height	Mix %	Pot Size	Specification	Density
238	Bergenia 'Sunningdale'		20%	2L	Full Pot :C	5/m ²
238	Hebe albicans		20%	3L	Bushy :5 brks	5/m ²
238	Mahonia aquifolium 'Apollo'		20%	3L	Bushy :3/5 brks :C	5/m ²
238	Sedum 'Ruby Glow'		20%	2L	Full Pot :C	5/m ²
238	Vinca major	20-30cm	20%	2L	Bushy :3/4 brks :C	5/m ²

Amenity Mix 15

Number	Species	Height	Mix %	Pot Size	Specification	Density
104	Mahonia aquifolium 'Apollo'		25%	3L	Bushy :3/5 brks :C	5/m ²
104	Potentilla fruticosa 'Primrose Beauty'	30-40cm	25%	3L	Bushy :3/5 brks :C	5/m ²
104	Sedum 'Ruby Glow'		25%	2L	Full Pot :C	5/m ²
104	Vinca major	20-30cm	25%	2L	Bushy :3/4 brks :C	5/m ²

Amenity Mix 16

Number	Species	Height	Mix %	Pot Size	Specification	Density
375	Brachyglottis 'Sunshine'	30-40cm	25%	3L	Bushy :3 brks :C	4/m ²
375	Hebe 'Silver Queen'	30-40cm	25%	3L	Bushy :3 brks :C	4/m ²
375	Pachysandra terminalis	30-40cm	25%	3L	Branched :3/4 brks :C	4/m ²
375	Sarcococca humilis	40-60cm	25%	3L	Bushy :3 brks :C	4/m ²

Amenity Mix 17

Number	Species	Height	Mix %	Pot Size	Specification	Density
119	Brachyglottis 'Sunshine'	30-40cm	25%	3L	Bushy :3 brks :C	4/m ²
119	Euonymus jap. 'Micro. Albovariegatus'	40-60cm	25%	3L	Bushy :3 brks :C	4/m ²
119	Pachysandra terminalis	30-40cm	25%	3L	Branched :3/4 brks :C	4/m ²
119	Viburnum davidii	40-60cm	25%	5L	Bushy :3/5 brks :C	4/m ²

Amenity Mix 18

Number	Species	Height	Mix %	Pot Size	Specification	Density
6	Ceanothus thyrsiflorus 'Skylark'	40-60cm	10%	5L	Bushy :4/6 brks :C	4/m ²
14	Choisya 'Aztec Pearl'	30-40cm	25%	5L	Bushy :4/6 brks :C	4/m ²
11	Fatsia japonica	60-80cm	20%	5L	Bushy :4/6 brks :C	4/m ²
11	Photinia fraseri 'Red Robin'	60-80cm	20%	5L	Bushy :5/6 brks :C	4/m ²
14	Polystichum setiferum		25%	3L	Full Pot	4/m ²

Amenity Mix 19

Number	Species	Height	Mix %	Pot Size	Specification	Density
196	Choisya 'Aztec Pearl'	30-40cm	30%	5L	Bushy :4/6 brks :C	4/m ²
260	Hamamelis mollis 'Pallida'	80-100cm	40%	5L	Bushy :4/6 brks :C	4/m ²
196	Polystichum setiferum		30%	3L	Full Pot	4/m ²

Amenity Mix 20

Number	Species	Height	Mix %	Pot Size	Specification	Density
60	Brachyglottis 'Sunshine'	30-40cm	40%	3L	Bushy :4/6 brks :C	5/m ²
45	Choisya 'Aztec Pearl'	30-40cm	30%	5L	Bushy :4/6 brks :C	5/m ²
45	Polystichum setiferum		30%	3L	Full Pot	5/m ²

Amenity Mix 22

Number	Species	Height	Mix %	Pot Size	Specification	Density
54	Bergenia 'Abendglut'		20%	2L	Full Pot :C	4/m ²
54	Kniphofia 'Coral Flame'		20%	3L	Full Pot :C	4/m ²
54	Mahonia aquifolium 'Apollo'		20%	3L	Bushy :3/5 brks :C	4/m ²
54	Polystichum aculeatum		20%	3L	Full Pot	4/m ²
54	Sarcococca confusa	30-40cm	20%	3L	Bushy :3/4 brks :C	4/m ²

Play Mix 1

Number	Species	Height	Mix %	Pot Size	Specification	Density
183	Briza media		40%	10L		3/m ²
160	Helictotrichon sempervirens		35%	5L		3/m ²
115	Miscanthus sinensis 'Morning Light'		25%	10L		3/m ²

Play Mix 2

Number	Species	Height	Mix %	Pot Size	Specification	Density
21	Achillea 'Coronation Gold'		4%	5L		5/m ²
21	Agapanthus 'White Heaven'		4%	5L		5/m ²
26	Allium caeruleum		5%	3L		5/m ²
101	Briza media		20%	10L		5/m ²
21	Campanula 'Azure Beauty'		4%	3L		5/m ²
26	Centranthus ruber 'Albus'		5%	5L		5/m ²
26	Chaerophyllum hirsutum 'Roseum'		5%	3L		5/m ²
16	Echinops bannaticus 'Taplow Blue'		3%	3L		5/m ²
26	Eryngium 'Jos Eijking'		5%	3L		5/m ²
101	Helictotrichon sempervirens		20%	5L		5/m ²
76	Miscanthus sinensis 'Morning Light'		15%	10L		5/m ²
26	Rudbeckia triloba		5%	2L		5/m ²
26	Veronica longifolia 'Marietta'		5%	2L		5/m ²

Play Mix 3

Number	Species	Height	Mix %	Pot Size	Specification	Density
244	Cornus sanguinea 'Midwinter Fire'	60-80cm	25%	5L	Branched: 4 brks: C	3/m ²
148	Corylus avellana	80-100cm	15%		1 + 2: Transplant - seed raised: Branched: 4 brks: BR	3/m ²
340	Deschampsia cespitosa 'Goldtau'		35%			3/m ²
244	Miscanthus sinensis 'Zebrinus'		25%	5L	Full Pot: C	3/m ²

Play Mix 4

Number	Species	Height	Mix %	Pot Size	Specification	Density
17	Rubus fruticosus 'Waldo'		50%	3L	Branched :3/5 brks :C	3/m ²
17	Rubus fruticosus x ideaus 'Buckingham'		50%	3L	Branched :3/5 brks :C	3/m ²

Play Mix 5

Number	Species	Height	Mix %	Pot Size	Specification	Density
427	Cornus sanguinea 'Midwinter Fire'	60-80cm	25%	5L	Branched: 4 brks: C	3/m ²
427	Cornus sericea 'Flaviramea'	60-80cm	25%	5L	Branched :5/6 brks :C	3/m ²
257	Corylus avellana	80-100cm	15%		1 + 2: Transplant - seed raised: Branched: 4 brks: BR	3/m ²
427	Miscanthus sinensis 'Zebrinus'		25%	5L	Full Pot: C	3/m ²
172	Vinca minor 'Gertrude Jekyll'	20-30cm	10%	3L	Bushy :3/4 brks :C	3/m ²

Play Mix 6

Number	Species	Height	Mix %	Pot Size	Specification	Density
263	Allium 'Purple Sensation'		15%	2L	Full Pot :C	5/m ²
263	Bergenia 'Silberlicht'		15%	2L	Full Pot :C	5/m ²
175	Buddleia davidii 'Royal Red'	40-60cm	10%	5L	Bushy :4/6 brks :C	5/m ²
263	Carex morrowii 'Ice Dance'		15%	3L	Full Pot	5/m ²
263	Ceanothus thyrsiflorus 'Skylark'	40-60cm	15%	5L	Bushy :4/6 brks :C	5/m ²
263	Choisya 'Aztec Pearl'	30-40cm	15%	5L	Bushy :4/6 brks :C	5/m ²
263	Hebe Blush Elegance		15%	5L	Bushy :5 brks	5/m ²

Play Mix 7

Number	Species	Height	Mix %	Pot Size	Specification	Density
159	Buddleia davidii 'Royal Red'	40-60cm	10%	5L	Bushy :4/6 brks :C	4/m ²
159	Buddleia davidii 'Royal Red'	30-40cm	10%	3L	Bushy :4/6 brks :C	4/m ²
159	Carex morrowii 'Ice Dance'		10%	3L	Full Pot	4/m ²
159	Ceanothus thyrsiflorus 'Skylark'	40-60cm	10%	5L	Bushy :4/6 brks :C	4/m ²
159	Choisya 'Aztec Pearl'	30-40cm	10%	5L	Bushy :4/6 brks :C	4/m ²
159	Fatsia japonica	60-80cm	10%	5L	Bushy :4/6 brks :C	4/m ²
239	Hebe Blush Elegance		15%	5L	Bushy :5 brks	4/m ²
159	Photinia fraseri 'Red Robin'	60-80cm	10%	5L	Bushy :5/6 brks :C	4/m ²
239	Polystichum setiferum		15%	3L	Full Pot	4/m ²

Notes:

- All contractors must visit the site and be responsible for taking and checking dimensions.
- All construction information should be taken from figured dimensions only.
- Any discrepancies between drawings, specifications and site conditions must be brought to the attention of the supervising officer.
- This drawing and the works depicted are the copyright of HBA.

-						
Rev.	Date	By	Description	Ckd	Aprd	
Drawing Status: PLANNING						



landscape architecture ■ urban design
expert witness ■ environmental planning

Huskinson Brown is the trading name of David Huskinson Associates Limited
17 Upper Grosvenor Road Tunbridge Wells Kent TN11 2DU
tel: 01892 527629 email:office@huskinsonbrown.co.uk www.huskinsonbrown.co.uk

All dimensions to be checked on site

Client
CALA (South Home Counties) Ltd/ Bellway Homes Ltd

Project
Land north of Water Lane, Angmering

Drawing
Planting Schedule

Sheet	Scale:
3 of 4	NTS
Date	Drawing No.
18:05:22	HBA-875-237
Rev.	-

File location:
P:\875 Water Lane\Drawings\HBA\Current Drawings\Detail Design

Mix P1

Species	Height	Mix %	Pot Size	Specification	Density
Artemisia 'Powis Castle'		10%	3L	Full Pot :C	5/m ²
Crocsmia 'Emily McKenzie'		20%	2L	Full Pot :C	5/m ²
Helenium 'Moerheim Beauty'		10%	3L	Full Pot	5/m ²
Kniphofia 'Coral Flame'		10%	3L	Full Pot :C	5/m ²
Miscanthus sinensis 'Kleine Fontane'		25%	3L	Full Pot	5/m ²
Rudbeckia 'Goldsturm'		10%	2L	Full Pot :C	5/m ²
Stipa tenuissima		15%	3L	Full Pot	5/m ²

Mix P2

Species	Height	Mix %	Pot Size	Specification	Density
Anemanthele lessoniana		20%	3L	Full Pot	5/m ²
Asarum europaeum		20%	3L	Full Pot :C	5/m ²
Dryopteris affinis 'Cristata'		20%	2L	Full Pot	5/m ²
Hypericum 'Hidcote'	30-40cm	20%	3L	Branched :3/4 brks :C	5/m ²
Trollius japonicus		20%	2L	Full Pot :C	5/m ²

Mix P3

Species	Height	Mix %	Pot Size	Specification	Density
Alchemilla mollis		12%	3L	Full Pot :C	5/m ²
Calamagrostis acutiflora 'Karl Foerster'		59%	5-7.5L		5/m ²
Epimedium x perralchicum 'Frohnleiten'		7%	3L		5/m ²
Hypericum 'Hidcote'		5%	3L		5/m ²
Pennisetum alopecuroides 'Hameln'		10%			5/m ²
Sarcococca hookerana humilis		7%	3L		5/m ²

Mix P4

Species	Height	Mix %	Pot Size	Specification	Density
Anemanthele lessoniana		25%	3L	Full Pot	3/m ²
Cornus sericea 'Flaviramea'		25%	3L	Branched :3/4 brks :C	3/m ²
Mahonia nitens 'Cabaret'	25-30cm	25%	3L	Branched :3/4 brks :C	3/m ²
Stipa tenuissima		25%	3L	Full Pot	3/m ²

Mix V1

Species	Height	Mix %	Pot Size	Specification	Density
Echinacea purpurea		20%	3	5 Buds : :Full Pot :C	6/m ²
Geranium himalayense 'Gravetye'		20%	2L	Full Pot :C	6/m ²
Hebe 'Purple Pixie'	30-40cm	20%	3L	Bushy :C	6/m ²
Penstemon 'Blackbird'		20%	2L		6/m ²
Sedum spectabile 'Brilliant'		20%	3L	Full Pot :C	6/m ²

Mix V2

Species	Height	Mix %	Pot Size	Specification	Density
Centranthus ruber 'Albus'		20%	2L	Full Pot	7/m ²
Epimedium x perralchicum 'Frohnleiten'		20%	3L	Full Pot	7/m ²
Geranium oxonianum 'A T Johnson'		20%	2L	Full Pot	7/m ²
Pachysandra terminalis 'Green Carpet'	10-20cm	20%	3L	Several shoots :6/9 brks :C	7/m ²
Rosmarinus officinalis 'Severn Sea'	30-40cm	20%	3L	Bushy :3/5 brks :C	7/m ²

Mix V3

Species	Height	Mix %	Pot Size	Specification	Density
Astrantia major 'Rubra'		15%	2L	Full Pot :C	6/m ²
Bergenia 'Silberlicht'		15%	2L	Full Pot :C	6/m ²
Geranium oxonianum 'Wargrave Pink'		15%	2L	Full Pot :C	6/m ²
Hakonechloa macra		15%	3L	Full Pot	6/m ²
Hebe 'Green Globe'		20%	3L	Bushy :5 brks	6/m ²
Liriope muscari 'Monroe'		20%	3L		6/m ²

Mix W1

Species	Height	Mix %	Pot Size	Specification	Density
Bergenia 'Bressingham White'		20%	3L	Full Pot :C	6/m ²
Geranium phaeum 'Album'		20%	2L	Full Pot	6/m ²
Hebe 'Green Globe'	40-60cm	20%	3L	Bushy :5 brks :C	6/m ²
Liriope muscari 'Monroe'		20%	2L	Full Pot	6/m ²
Sarcococca humilis	40-60cm	20%	3L	Bushy :3 brks :C	6/m ²

Mix W2

Species	Height	Mix %	Pot Size	Specification	Density
Allium schoenoprasum		10%	2L	Full Pot :C	6/m ²
Anthriscus sylvestris 'Ravenswing'		15%	3L	4 Buds :Full Pot :C	6/m ²
Bergenia 'Bressingham White'		15%	2L	Full Pot :C	6/m ²
Polystichum setiferum		15%	3L	Full Pot	6/m ²
Stipa tenuissima		15%	3L	Full Pot	6/m ²
Tiarella 'Spring Symphony'		15%	3L	Full Pot :C	6/m ²
Vinca minor 'Alba'	30-40cm	15%	3L	Branched :3/5 brks :C	6/m ²

Mix W3

Species	Height	Mix %	Pot Size	Specification	Density
Geranium Rozanne		20%	2L		5/m ²
Hebe 'Nicola's Blush'		20%	3L		5/m ²
Liriope muscari 'Big Blue'		10%	2L		5/m ²
Liriope muscari 'Monroe White'		10%	2L		5/m ²
Pachysandra terminalis 'Green Carpet'	10-20cm	10%	3L	Several shoots :6/9 brks :C	5/m ²
Philadelphus 'Manteau d'Hermine'	20-30cm	20%	3L	Bushy :3/5 brks :C	5/m ²
Vinca minor 'Gertrude Jekyll'		10%	2L	7 brks :C	5/m ²

Mix W4

Species	Height	Mix %	Pot Size	Specification	Density
Anemone × hybrida 'September Charm'		10%	2L		4/m ²
Hebe 'Red Edge'	25-30cm	50%	3L	Bushy :5 brks :C	4/m ²
Rosa 'Kent'	40cm	20%	3L	Bushy :5 brks :C :Bushy :3 brks :C	4/m ²
Verbena bonariensis		20%	2L	Full Pot	4/m ²

Notes:

- All contractors must visit the site and be responsible for taking and checking dimensions.
- All construction information should be taken from figured dimensions only.
- Any discrepancies between drawings, specifications and site conditions must be brought to the attention of the supervising officer.
- This drawing and the works depicted are the copyright of HBA.

-					
Rev.	Date	By	Description	Ckd	Aprd
Drawing Status: PLANNING					



landscape architecture ■ urban design
expert witness ■ environmental planning

Huskinson Brown is the trading name of David Huskinson Associates Limited
17 Upper Grosvenor Road Tunbridge Wells Kent TN11 2DU
tel: 01892 527628 email:office@huskinsonbrown.co.uk www.huskinsonbrown.co.uk

All dimensions to be checked on site

Client
CALA (South Home Counties) Ltd/ Bellway Homes Ltd

Project
Land north of Water Lane, Angmering

Drawing
Doorstep Planting Mixes

Sheet	Scale:
4 of 4	NTS
Date	Drawing No.
18:05:22	HBA-875-238
File location:	Rev.
P:\875 Water Lane\Drawings\HBA\Current Drawings\Detail Design	-