

Land North of Water Lane, Angmering
Planting Schedules and Planting Notes for Planning
8th July 2022



landscape architecture ■ urban design
expert witness ■ environmental planning

Unit A Farriers Courtyard
Spelmonden Road
Goudhurst, Cranbrook
Kent
TN17 1HE

Tel: 01892 527828

Email: office@huskissonbrown.co.uk
www.huskissonbrown.co.uk

Planting Notes for Planning

General

- All planting and operations should comply with the latest version of BS 4428 'General Landscape Operations' and BS 3936 'Nursery Stock - Specification for Trees & Shrubs'.
- All plants shall be supplied in accordance with the HTA National Plant Specification and from a HTA certified nursery, and in accordance with CPSE Code of Practice for 'Handling and Establishing Landscape Plants, Parts I, II and III.
- All existing trees and hedges shall be surveyed and protected in accordance with BS 5837:2015, and temporary protection fencing erected for the duration of the construction period. Refer to arboricultural consultants drawings for location and details.
- Specification of species, position and density shall be in accordance with drawing and planting schedule provided, and should not be amended without prior approval of the Landscape Architect and Local Planning Authority. For detailed landscape specification information, please refer to the schedules accompanying this document.

Ground conditions/ Topsoil

- All topsoil areas should be clear of rocks and rubble larger than 50mm diameter and any other debris that may interfere with the establishment of plants.
- Imported topsoil to be multi-purpose grade and free of all contaminants, in accordance with the latest version of BS 3882:2015 Specification for Topsoil. Topsoil analysis should be undertaken and reported, with recommendations for improvements if below the standard for general landscape purposes.
- Minimum topsoil depths should be as follows unless specified otherwise. Suitable (loosened) subsoil should provide the remainder of the rooting depths as required, and mixed with peat-free compost. Subsoil preparation shall be in accordance with BS 8601 and BS 4428 and scarified/ ripped to a suitable depth prior to spreading of topsoil. Any weed/grass growth to be sprayed with appropriate herbicide at least 10 days prior to cultivation.
 - ornamental shrubs 450mm;
 - native shrubs 300mm;
 - seeded grass 150mm;
 - wildflower grass 50mm, or directly into existing ground;
 - tree pits to be excavated to at least twice the diameter of the root spread and 1.5 times the depth of the roots to be planted.

Cultivation

- Planting outside the usual October-March dormant season shall be pursued by approval only. If agreed all bare root plants shall be substituted with container grown stock, with additional establishment watering.
- Plants shall be bedded in random fashion to avoid formal regimented lines at densities indicated in the schedule, except for specimens, which are to be planted in locations shown on the drawing. For mixes: shrubs, perennials & grasses should be planted in groups of 3, 5, 7 of each species. Taller plant species to be planted to the rear (eg. addressing walls, fences etc) with lower species to the front.
- All planting should be watered in to field capacity immediately after planting and mulched with minimum of 50mm depth of medium grade crushed mulch. Where necessary, plants to be protected with rabbit fence and/ or individual rabbit guard securely fixed to timber stakes.

Trees & Foundations

- All trees to be supplied, planted and established in accordance with BS 8545. Trees adjacent to buildings and services shall include urban tree pit details (to the approval of the Local Planning Authority) incorporating rootbarriers, drainage, aeration and a load bearing raft system where necessary to create a healthy growing space for trees whilst protecting tree roots and surfaces.. All trees should be planted in the positions as indicated on the drawings.
- All foundation designs (by the architect/engineer) must consider the effect of existing trees, and the proposed landscape scheme in accordance with the NHBC Standards. Every effort has been made within the design to follow advice in Chapter 4.2 of the Standards, however landscape proposals should be referred to a structural engineer for checks and any conflicts made known to the Landscape Architect for necessary changes.
- Trees within hardstanding or highways visibility splays shall be clear stem to 2m high unless specified otherwise.

Maintenance

- Management operations for the site shall be carried out in accordance with a Landscape and Ecological Management Plan (to be approved by the Local Planning Authority).
- Any tree or plant which, within a period of 5 years from the implementation, dies, is removed or becomes seriously damaged or diseased, shall be replaced in the next planting season with another of a similar size and species unless otherwise agreed with the Local Planning Authority.

Soil Specification

- All Imported Topsoil: Multi-Purpose Topsoil to BS 3882: 2015; tested & certified by a Soil Scientist;
- Where imported topsoil is required for wildflower grassland: Low Fertility Specific-Purpose Topsoil to BS 3882:2015
- Existing topsoil utilised in-situ; to be tested & certified by a Soil Scientist for suitability for proposed planting.
- Existing stripped topsoil (stored and re used): to be screened / cultivated to accord with BS 3882: 2015; tested & certified.
- Proposed Tree Planting - All proposed tree planting areas to be minimum 600 mm depth subsoil overlain with a minimum of 300 mm depth of topsoil tested and certified to achieve BS 3882: 2015.
- Proposed Ornamental Planting / Hedge Planting / Native Shrub - All proposed Ornamental Planting / Hedge Planting / Native Understory Shrub planting areas to be minimum 300 mm depth subsoil overlain with a minimum of 300 mm depth of topsoil tested and certified to achieve BS 3882: 2015.
- Proposed Amenity Grassland - to be minimum 300 mm depth subsoil overlain with a minimum of 100 mm depth of topsoil tested and certified to achieve BS 3882: 2015.
- Proposed Native Wildflower Grassland - Wildflower areas are not to be subject to any soil additives, ameliorants or conditioners. Proposed wildflower grass seeded areas to be min. 300 mm depth subsoil with 150mm specialist topsoil as required.

Drawings:

The following drawings illustrate the Soft Landscape Proposals for planning approval:

- HBA-875-201 to 238 revision B Soft Landscape Plans (38 No. 1:200 scale Planting Plans)
- HBA-875-240 to 2104 Front Garden Planting (65 No. 1:100 scale Planting Plans)

These are accompanied by the following drawings illustrating the overall landscape masterplan, layout and treatment of hard landscape surface finishes, boundary treatments and play areas:

- HBA-875-001 revision J Illustrative Landscape Masterplan
- HBA-875-100 revision J Hard Landscape Plan (1:1000)
- HBA-875-101 to 138 Hard Landscape Plans (38 No. 1:200 scale Planting Plans)
- HBA-875- 301-311 Play Provision – (Landscape finishes to Play Areas) (1:200)
- HBA-875-401 to 407 Illustrative Landscape Sections

Trees

Number	Abbreviation	Species	Height	Girth	Pot Size	Specification	Density
2	ACECAM	Acer campestre	min. 550cm	35-40cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
83	Ac	Acer campestre	300-350cm	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB	Counted
24	AcE	Acer campestre 'Elsrijk'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
36	AcR	Acer campestre 'Red Shine'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
6	ACWC	Acer campestre 'William Caldwell'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
4	Agl	Alnus glutinosa	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
4	Agl	Alnus glutinosa	min. 450cm	30-35cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
1	Agl	Alnus glutinosa	400-450cm	16-18cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB	Counted
4	AMEBA	Amelanchier 'Ballerina'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
14	AMLAN	Amelanchier lamarckii	300-350cm			Multi-Stemmed :Bushy :3 Stems :3x :RB	Counted
5	ARBUN	Arbutus unedo	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
130	BETPE	Betula pendula	250-300cm			Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB	Counted
9	BETPE	Betula pendula	250-300cm			Multi-Stemmed :3 Stems :RB	Counted
15	BETPE	Betula pendula	350-400cm	14-16cm		Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB	Counted
3	BETUT	Betula utilis	250-300cm			Multi-Stemmed :3 Stems :RB	Counted
15	BTUM	Betula utilis 'Moonbeam'	350-400cm	14-16cm		Advanced Nursery Stock :Mulit-Stemmed: 3 Stems :3x :RB	Counted
7	BETJACA	Betula utilis jacquemontii	250-300cm			Multi-Stemmed :3 Stems :RB	Counted
32	CARBET	Carpinus betulus	350 min.	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB	Counted
12	CARBET	Carpinus betulus	400-450cm	16-18cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
5	CARBET	Carpinus betulus	min. 450cm	16-18cm		Extra Heavy Standard :Clear Stem min. 200 :5 brks :3x :RB	Counted
3	Cbe	Carpinus betulus	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
18	CbC	Carpinus betulus 'Columnaris'	400-450cm	14-16cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
44	CbFF	Carpinus betulus 'Frans Fontaine'	350-400cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
6	Corm	Cornus mas	2.5-3.0m			Multi-Stemmed :3/5 brks :RB	Counted
34	Ccol	Corylus colurna	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
9	EUAL	Euonymus alata	175-200cm			Multi-Stemmed :3 Stems :RB	Counted
1	FAGSY	Fagus sylvatica	min. 450cm	30-35cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
33	Ia	Ilex aquifolium	300-350cm	12-14cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB	Counted
3	Ia	Ilex aquifolium	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
1	Jr	Juglans regia	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
2	MAGKO	Magnolia kobus	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
6	MAGST	Magnolia stellata	1.5-1.8m		10L	Multi-Stemmed :C	Counted
11	MALSN	Malus 'Snowcloud'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
49	MALSY	Malus sylvestris	450-500cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
5	MALTRI	Malus trilobata	300-350cm	14-16cm		Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
20	MORNI	Morus nigra	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
24	PRUBOUA	Prunus 'Sunset Boulevard'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
35	Pav	Prunus avium	300-350cm	12-14cm		Advanced Nursery Stock :3x :RB	Counted
2	Pav	Prunus avium	350-400cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
16	PaP	Prunus avium 'Plena'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
19	Ppa	Prunus padus	400-450cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
12	PRSA	Prunus sargentii	350-400cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
3	PRUROSA	Prunus subhirtella 'Autumnalis Rosea'	min. 400cm	16-18cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
6	PRSU	Prunus subhirtella 'Autumnalis'	350-400cm	14-16cm		Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
9	PcC	Pyrus calleryana 'Chanticleer'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
20	PcC	Pyrus calleryana 'Chanticleer'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
2	PYCB	Pyrus communis 'Beech Hill'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
24	Qr	Quercus robur	350-400cm	14-16cm		Advanced Nursery Stock :Clear Stem 175-200 :3x :RB	Counted
9	QUERO	Quercus robur	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
9	ROBPSUN	Robinia pseudoacacia 'Unifoliola'	250-300cm			Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
49	Sar	Sorbus aria	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
26	SaLu	Sorbus aria 'Lutescens'	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
3	Sau	Sorbus aucuparia	350-425cm	14-16cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
8	Slnc	Sorbus incana	400-450cm	12-14cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
7	Tc	Tilia cordata	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
6	Tc	Tilia cordata	350-400cm	10-12cm		Heavy Standard :Clear Stem 175-200 :3x :RB	Counted
8	Tc	Tilia cordata	min. 600cm	40-45cm		Semi-Mature :Clear Stem min. 200 :RB	Counted
80	TilcorG	Tilia cordata 'Greenspire'	400-450cm	18-20cm		Extra Heavy Standard :Clear Stem min. 200 :3x :RB	Counted
15	UlmusNH	Ulmus 'New Horizon'	300-350cm	12-14 cm		Advanced Nursery Stock :Clear Stem 150-175 :3x :RB	Counted

Specimen Shrubs

Number	Species	Pot Size	Specification	Density
4	Buddleia davidii 'Royal Red'	10L	Branched :5/6 brks :C	Counted
3	Cornus sanguinea 'Midwinter Fire'	10L	Branched :5 brks :C	Counted
2	Corylus avellana 'Contorta'	10L	Bushy :5/7 brks :C	Counted
7	Cotinus coggygria 'Royal Purple'	10L	Bushy :5/7 brks :C	Counted
3	Exochorda macrantha 'The Bride'	10L	C	Counted
2	Forsythia intermedia 'Lynwood Variety'	10L	C	Counted
10	Hydrangea arborescens 'Annabelle'	10L	Bushy :6/9 brks :C	Counted
5	Hydrangea paniculata 'Wim's Red'	10L	Branched :5/7 brks :C	Counted
2	Kerria japonica 'Golden Guinea'	10L	C	Counted
5	Mahonia media 'Winter Sun'	10L	C	Counted
11	Rhus glabra	10L	Multi stem :C	Counted
2	Ribes sanguineum	10L		Counted
3	Syringa 'Red Pixie'	10L	Branched :5/7 brks :C	Counted
2	Viburnum bodnantense 'Dawn'	10L	Leader With Laterals :3/5 brks :C	Counted
9	Viburnum lantana	10L	Multi stem :5/6 brks :C	Counted
10	Viburnum opulus	10L	Multi stem :5/6 brks :C	Counted

Climbers

Number	Species	Pot Size	Specification	Density
10	Clematis vitalba	2L	Several Shoots :Caned	Counted
20	Hedera colchica 'Sulphur Heart'	2L	Several Shoots :Caned	Counted
33	Jasminum nudiflorum	3L	Several Shoots :Caned	Counted
18	Lonicera japonica 'Halliana'	2L	3/4 brks :Caned	Counted
8	Lonicera periclymenum	2L	Several Shoots :Caned	Counted
15	Lonicera periclymenum	2L	Several Shoots :2/3 brks :Caned	Counted
10	Parthenocissus tricuspidata 'Veitchii'			Counted
3	Parthenocissus tricuspidata 'Veitchii'	2L	3/5 brks :Caned	Counted
4	Schizophragma hydrangeoides	3L	Several Shoots :Caned	Counted

Hedges

Number	Species	Height	Pot Size	Specification	Centres	Notes
12	Carpinus betulus	1.2-1.5 m		Feather :2 Stems :2x :B	0.45Ctr	
889	Carpinus betulus	1.2-1.5 m		Feather :2 Stems :2x :B	0.5Ctr	
132	Escallonia 'Apple Blossom'	40-60cm	3L	Bushy :4 brks :C	0.5Ctr	
221	Ilex aquifolium	80-100cm	10-12L	Leader With Laterals :C	0.45Ctr	
516	Lonicera nitida	60-80cm	3L	Bushy :3/5 brks :C	0.45Ctr	
62	Lonicera nitida 'May Green'	60-80cm	3L	Bushy :3/5 brks :C	0.5Ctr	
142	Rosa 'Kent'	40cm	3L	Bushy :5 brks :C :Bushy :3 brks :C	0.4Ctr	
1	Willow tunnel				No.	24m length

SUDs Edge Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
851	Alchemilla mollis		10%	2L	C	5/m ²
851	Bergenia 'Perfect'		10%	2L	Full Pot	5/m ²
1272	Carex comans 'Bronze'		15%	2L	Full Pot	5/m ²
1272	Carex morrowii 'Ice Dance'		15%	2L	Full Pot	5/m ²
851	Cornus alba 'Kesselringii'	40-60cm	10%	3L	Several shoots :2/4 brks :C	5/m ²
851	Iris pseudacorus		10%	1L	Well Rooted	5/m ²
851	Limonium platyphyllum		10%	1L	3 brks :C	5/m ²
851	Lythrum salicaria		10%	0.5L		5/m ²
851	Myosotis scorpioides		10%	0.5L	Well Rooted	5/m ²

Hedgerow Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
363	Acer campestre	125-150cm	5%		Feather :3 brks :BR	4/m
714	Acer campestre	60-80cm	10%		1 + 1 :BR	4/m
3240	Crataegus monogyna	40-60cm	46%		1 + 1 :BR	4/m
83	Ilex aquifolium	60-80cm	1%	3L	Bushy :C	4/m
154	Ligustrum vulgare	60-80cm	2%		0/1 :Branched :BR	4/m
83	Malus sylvestris	60-80cm	1%		1 + 1 :BR	4/m
154	Prunus avium	125-150cm	2%		Feather :3 brks :BR	4/m
154	Prunus padus	60-80cm	2%		1 + 1 :BR	4/m
1767	Prunus spinosa	60-80cm	25%		1 + 1 :BR	4/m
223	Viburnum lantana	60-80cm	3%		1 + 1 :BR	4/m
223	Viburnum opulus	60-80cm	3%		1 + 1 :BR	4/m

Hedgerow Gaps (Screening) Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
5	Acer campestre	250-300cm	5%		Standard :RB	No.
10	Acer campestre	60-80cm	10%		1 + 1 :BR	No.
35	Crataegus monogyna	40-60cm	35%		1 + 1 :BR	No.
15	Ilex aquifolium	60-80cm	15%	3L	Bushy :C	No.
10	Ligustrum vulgare	60-80cm	10%		0/1 :Branched :BR	No.
1	Malus sylvestris	60-80cm	1%		1 + 1 :BR	No.
2	Prunus avium	250-300cm	2%		Standard :RB	No.
10	Prunus padus	60-80cm	10%		1 + 1 :BR	No.
10	Prunus spinosa	60-80cm	10%		1 + 1 :BR	No.
2	Viburnum opulus	60-80cm	2%		1 + 1 :BR	No.

Dormouse Mix

Number	Species	Height	Mix %	Specification	Density
206	Acer campestre	60-80cm	10%	12.5m	2Ctr
43	Betula pendula	250-300cm	2%	14m	2Ctr
64	Betula pendula	125-150cm	3%	14m	2Ctr
511	Corylus avellana	60-80cm	25%	8m	2Ctr
105	Crataegus monogyna	40-60cm	5%	8m	2Ctr
43	Ligustrum vulgare	60-80cm	2%		2Ctr
23	Malus sylvestris	250-300cm	1%	9m	2Ctr
43	Malus sylvestris	60-80cm	2%	9m	2Ctr
511	Quercus robur	60-80cm	25%	20m	2Ctr
511	Quercus robur	150-175cm	25%	20m	2Ctr

Thorny Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
3249	Crataegus monogyna	40-60cm	45%		1 + 1 :BR	3/m ²
1231	Ilex aquifolium	60-80cm	17%	3L	Bushy :C	3/m ²
222	Ligustrum vulgare	60-80cm	3%		0/1 :Branched :BR	3/m ²
1085	Prunus spinosa	60-80cm	15%		1 + 1 :BR	3/m ²
725	Rosa canina	60-80cm	10%		1 + 1 :BR	3/m ²
725	Ulex europaeus	40-60cm	10%		1 + 1 :BR	3/m ²

Woodland Buffer Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
55	Acer campestre	60-80cm	5%		12.5m	2Ctr
106	Acer campestre	125-150cm	10%		12.5m	2Ctr
469	Crataegus monogyna	40-60cm	45%			2Ctr
13	Ilex aquifolium	60-80cm	1%	3L		2Ctr
23	Ligustrum vulgare	60-80cm	2%			2Ctr
23	Lonicera periclymenum	20-40cm	2%	2L		2Ctr
13	Malus sylvestris	60-80cm	1%		9m	2Ctr
23	Prunus avium	250-300cm	2%		17m	2Ctr
23	Prunus padus	125-150cm	2%		8m	2Ctr
261	Prunus spinosa	60-80cm	25%			2Ctr
33	Viburnum lanata	60-80cm	3%		4m	2Ctr
23	Viburnum opulus	60-80cm	2%		6m	2Ctr

Woodland Edge Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
81	Acer campestre	60-80cm	5%		12.5m	2Ctr
160	Acer campestre	125-150cm	10%		12.5m	2Ctr
704	Crataegus monogyna	40-60cm	45%			2Ctr
18	Ilex aquifolium	60-80cm	1%	3L		2Ctr
35	Ligustrum vulgare	60-80cm	2%			2Ctr
35	Lonicera periclymenum	20-40cm	2%	2L		2Ctr
18	Malus sylvestris	60-80cm	1%		9m	2Ctr
35	Prunus avium	250-300cm	2%		17m	2Ctr
35	Prunus padus	125-150cm	2%		8m	2Ctr
315	Prunus spinosa	60-80cm	20%			2Ctr
81	Quercus robur	150-175cm	5%		20m	2Ctr
49	Viburnum lantana	60-80cm	3%		4m	2Ctr
35	Viburnum opulus	60-80cm	2%		6m	2Ctr

Woodland Floor Mix

Number	Species	Height	Mix %	Pot Size	Specification	Density
192	Anemone nemorosa		10%	2L	C : Full Pot	2/m ²
192	Corylus avellana	60-80cm	10%		1 + 1 : BR	2/m ²
192	Crataegus monogyna	40-60cm	10%		1 + 1 : BR	2/m ²
192	Ilex aquifolium	60-80cm	10%	3L	Bushy : C	2/m ²
97	Ligustrum vulgare	60-80cm	5%		0/1 : Branched : BR	2/m ²
381	Lonicera periclymenum	20-40cm	20%	2L	Branched : CG	2/m ²
192	Primula vulgaris		10%	2L	C : Full Pot	2/m ²
286	Prunus spinosa	60-80cm	15%		1 + 1 : BR	2/m ²
192	Viburnum opulus	60-80cm	10%		1 + 1 : BR	2/m ²

Amenity Mix 1

Number	Species	Height	Mix %	Pot Size	Specification	Density
101	Cornus alba 'Sibirica'	60-80cm	25%	5L	Branched : 4 brks : C	3/m ²
81	Cornus sanguinea 'Midwinter Fire'	80-100cm	20%	10L	Branched : 5 brks : C	3/m ²
61	Corylus avellana	80-100cm	15%		1 + 2 : Transplant - seed raised : Branched : 4 brks : BR	3/m ²
61	Ilex aquifolium	60-80cm	15%	5L	Branched : 3/6 brks : C	3/m ²
101	Rubus cockburnianus	60-80cm	25%	5L	Branched : 3/6 brks : C	3/m ²

Amenity Mix 1 Underplanting

Number	Species	Height	Mix %	Pot Size	Specification	Density
184	Anemone nemorosa		50%	3L		5/m ²
184	Galium odoratum		50%	3L		5/m ²

Amenity Mix 2

Number	Species	Height	Mix %	Pot Size	Specification	Density
157	Cornus stolonifera 'Flaviramea'	60-80cm	16%	5L	Branched : 5/6 brks : C	4/m ²
157	Cotoneaster 'Coral Beauty'	30-40cm	16%	3L	Branched : 3/4 brks : C	4/m ²
157	Epimedium x perralchicum 'Frohnleiten'		16%	2L	Full Pot : C	4/m ²
157	Hypericum 'Hidcote'	40-60cm	16%	3L	Branched : 5/6 brks : C	4/m ²
174	Kniphofia 'Emberglow'		18%	3L	Full Pot	4/m ²
174	Polystichum aculeatum		18%	2L	Full Pot	4/m ²

Amenity Mix 3

Number	Species	Height	Mix %	Pot Size	Specification	Density
306	Anemone nemorosa		15%	3L	Full Pot	4/m ²
306	Anemone hybrida 'Queen Charlotte'		15%	3L		4/m ²
402	Crocus 'Spitfire'		20%	2L	Full Pot : C	4/m ²
205	Knautia macedonica		10%	3L		4/m ²
402	Mahonia nitens 'Cabaret'	30-40cm	20%	3L	Branched : 3/4 brks : C	4/m ²
402	Miscanthus sinensis 'Gracillimus'		20%	5L	Full Pot	4/m ²

Amenity Mix 4

Number	Species	Height	Mix %	Pot Size	Specification	Density
353	Cotoneaster 'Coral Beauty'	30-40cm	25%	3L	Branched :3/4 brks :C	4/m ²
353	Euonymus alatus	40-60cm	25%	3L	Branched :5/6 brks :C	4/m ²
353	Euonymus fortunei 'Emerald Gaiety'	20-30cm	25%	3L	Bushy :3/4 brks :C	4/m ²
353	Spiraea japonica 'Goldflame'	30-40cm	25%	3L	Branched :5/6 brks :C	4/m ²

Amenity Mix 4 Underplanting

Number	Species	Height	Mix %	Pot Size	Specification	Density
844	Geranium phaeum 'Samobar'		50%	3L		5/m ²
844	Polystichum setiferum		50%	3L		5/m ²

Amenity Mix 5

Number	Species	Height	Mix %	Pot Size	Specification	Density
151	Bergenia 'Perfect'		20%	2L	Full Pot	5/m ²
116	Brachyglottis 'Sunshine'	40-60cm	15%	3L	Bushy :3/5 brks :C	5/m ²
116	Persicaria amplexicaulis 'Firetail'		15%	3L		5/m ²
116	Skimmia japonica reevesiana		15%	3L		5/m ²
116	Stachys byzantina		15%	3L		5/m ²
151	Vinca minor 'Burgundy'	30-40cm	20%	3L	Branched :3/6 brks :C	5/m ²

Amenity Mix 6

Number	Species	Height	Mix %	Pot Size	Specification	Density
151	Bergenia 'Perfect'		20%	2L	Full Pot	5/m ²
116	Brachyglottis 'Sunshine'	40-60cm	15%	3L	Bushy :3/5 brks :C	5/m ²
116	Persicaria amplexicaulis 'Firetail'		15%	3L		5/m ²
116	Skimmia japonica reevesiana		15%	3L		5/m ²
116	Stachys byzantina		15%	3L		5/m ²
151	Vinca minor 'Burgundy'	30-40cm	20%	3L	Branched :3/6 brks :C	5/m ²

Amenity Mix 7

Number	Species	Height	Mix %	Pot Size	Specification	Density
67	Allium schoenoprasum		13%	2L	Full Pot :C	4/m ²
78	Anemone hybrida 'Honorine Jobert'		15%	3L	Full Pot	4/m ²
78	Bergenia 'Bressingham White'		15%	2L	Full Pot :C	4/m ²
78	Osmanthus burkwoodii	60-80cm	15%	5L	Branched :3/5 brks :C	4/m ²
67	Pimpinella major 'Rosea'		13%	3L	Full Pot	4/m ²
78	Polystichum setiferum		15%	3L	Full Pot	4/m ²
78	Sedum spectabile 'Stardust'		15%	3L	Full Pot	4/m ²

Amenity Mix 8

Number	Species	Height	Mix %	Pot Size	Specification	Density
189	Bergenia 'Bressingham White'		20%	3L	Full Pot :C	5/m ²
234	Geranium phaeum 'Album'		25%	2L	Full Pot	5/m ²
144	Hebe 'Red Edge'	30-40cm	15%	5L	Bushy :C	5/m ²
144	Liriope muscari 'Monroe'		15%	2L	Full Pot	5/m ²
234	Sarcococca humilis	40-60cm	25%	3L	Bushy :3 brks :C	5/m ²

Amenity Mix 9

Number	Species	Height	Mix %	Pot Size	Specification	Density
56	Hedera colchica 'Sulphur Heart'	80-100cm	30%	3L	3/5 brks :Caned	3/m ²
56	Rosa rugosa 'Alba'	60-80cm	30%	3L		3/m ²
74	Skimmia japonica 'Kew White'	60-80cm	40%	3L	Bushy :5/6 brks :C	3/m ²

Amenity Mix 10

Number	Species	Height	Mix %	Pot Size	Specification	Density
80	Bergenia 'Bressingham White'		15%	3L	Full Pot :C	4/m ²
105	Hebe 'Green Globe'	40-60cm	20%	3L	Bushy :5 brks :C	4/m ²
80	Liriope muscari 'Monroe White'		15%	3L		4/m ²
105	Sarcococca humilis	40-60cm	20%	3L	Bushy :3 brks :C	4/m ²
80	Skimmia confusa 'Kew Green'	40-60cm	15%	3L	Bushy :3 brks :C	4/m ²
80	Tellima grandiflora		15%	3L		4/m ²

Amenity Mix 11

Number	Species	Height	Mix %	Pot Size	Specification	Density
26	Anemanthelle lessoniana		25%	3L	Full Pot	3/m ²
26	Miscanthus sinensis 'Gracillimus'		25%	5L	Full Pot	3/m ²
51	Photinia fraseri 'Red Robin'	80-100cm	50%	5-7.5L	Bushy :5/6 brks :C	3/m ²

Amenity Mix 12

Number	Species	Height	Mix %	Pot Size	Specification	Density
47	Cornus alba 'Sibirica'	60-80cm	25%	5L	Branched: 4 brks: C	2/m ²
29	Ilex aquifolium 'Golden van Tol'	60-80cm	15%	5L	Branched :3/6 brks :C	2/m ²
29	Pachysandra terminalis 'Green Carpet'	20-30cm	15%	3L	Bushy :3/5 brks :C	2/m ²
38	Rosa rugosa 'Alba'	30-40cm	20%	3L	Branched :Bushy :3/4 brks :C	2/m ²
47	Rubus cockburnianus	60-80cm	25%	5L	Branched :3/6 brks :C	2/m ²

Amenity Mix 13

Number	Species	Height	Mix %	Pot Size	Specification	Density
219	Alchemilla mollis		13%	3L		5/m ²
219	Astrantia major 'Rubra'		13%	2L	Full Pot :C	5/m ²
219	Bergenia 'Sunningdale'		13%	2L	Full Pot :C	5/m ²
219	Blechnum spicant		13%	3L		5/m ²
219	Geranium oxonianum 'Wargrave Pink'		13%	2L	Full Pot :C	5/m ²
219	Hebe 'Green Globe'		13%	3L	Bushy :5 brks	5/m ²
219	Liriope muscari 'Big Blue'		13%		Full Pot :C	5/m ²
219	Miscanthus sinensis 'Zebrinus'		13%	5L	Full Pot	5/m ²

Amenity Mix 14

Number	Species	Height	Mix %	Pot Size	Specification	Density
184	Bergenia 'Sunningdale'		13%	2L	Full Pot :C	5/m ²
184	Coreopsis verticillata 'Moonbeam'		13%	3L		5/m ²
184	Crocsmia 'George Davison'		13%	3L		5/m ²
184	Escallonia laevis 'Pink Elle'		13%	3L		5/m ²
184	Hebe albicans		13%	3L	Bushy :5 brks	5/m ²
184	Mahonia aquifolium 'Apollo'		13%	3L	Bushy :3/5 brks :C	5/m ²
184	Sedum 'Ruby Glow'		13%	2L	Full Pot :C	5/m ²
184	Vinca major	20-30cm	13%	2L	Bushy :3/4 brks :C	5/m ²

Amenity Mix 15

Number	Species	Height	Mix %	Pot Size	Specification	Density
63	Helleborus x hybridus 'Harvington Smokey Blues'		15%	3L		5/m ²
63	Heuchera 'Pluie de Feu'		15%	3L		5/m ²
71	Mahonia aquifolium 'Apollo'		17%	3L	Bushy :3/5 brks :C	5/m ²
71	Potentilla fruticosa 'Primrose Beauty'	30-40cm	17%	3L	Bushy :3/5 brks :C	5/m ²
71	Sedum 'Ruby Glow'		17%	2L	Full Pot :C	5/m ²
71	Vinca major	20-30cm	17%	2L	Bushy :3/4 brks :C	5/m ²

Mix P1

No.	Species	Height	Pot Size	Specification	Density	Mix %
267	Artemisia 'Powis Castle'		3L	Full Pot :C	5/m ²	10%
511	Crocasmia 'Emily McKenzie'		2L	Full Pot :C	5/m ²	20%
267	Helenium 'Moerheim Beauty'		3L	Full Pot	5/m ²	10%
267	Kniphofia 'Coral Flame'		3L	Full Pot :C	5/m ²	10%
633	Miscanthus sinensis 'Kleine Fontane'		3L	Full Pot	5/m ²	25%
267	Rudbeckia 'Goldsturm'		2L	Full Pot :C	5/m ²	10%
389	Stipa tenuissima		3L	Full Pot	5/m ²	15%

Mix P2

No.	Species	Height	Pot Size	Specification	Density	Mix %
317	Anemantele lessoniana		3L	Full Pot	5/m ²	15%
274	Asarum europaeum		3L	Full Pot :C	5/m ²	13%
317	Dryopteris affinis 'Cristata'		2L	Full Pot	5/m ²	15%
274	Epimedium x warleyense		3L	Full Pot :C	5/m ²	13%
317	Hypericum 'Hidcote'	30-40cm	3L	Branched :3/4 brks :C	5/m ²	15%
317	Physocarpus opulifolius 'Little Angel'		3L		5/m ²	15%
317	Trollius japonicus		2L	Full Pot :C	5/m ²	15%

Mix P3

No.	Species	Height	Pot Size	Specification	Density	Mix %
506	Alchemilla mollis		3L	Full Pot :C	5/m ²	13%
506	Blechnum spicant		3L	Full Pot	5/m ²	13%
582	Calamagrostis acutiflora 'Karl Foerster'		5-7,5L		5/m ²	15%
506	Epimedium x perralchicum 'Frohnleiten'		3L		5/m ²	13%
399	Helenium 'Moerheim Beauty'		3L	Full Pot	5/m ²	10%
506	Hypericum 'Hidcote'		3L		5/m ²	13%
506	Pennisetum alopecuroides 'Hameln'				5/m ²	13%
506	Sarcococca hookerana humilis		3L		5/m ²	13%

Mix P4

No.	Species	Height	Pot Size	Specification	Density	Mix %
601	Anemantele lessoniana		3L	Full Pot	3/m ²	20%
601	Cornus sericea 'Flaviramea'		3L	Branched :3/4 brks :C	3/m ²	20%
601	Mahonia nitens 'Cabaret'	25-30cm	3L	Branched :3/4 brks :C	3/m ²	20%
601	Spiraea japonica 'Goldflame'		3L		3/m ²	20%
601	Stipa tenuissima		3L	Full Pot	3/m ²	20%

Mix P5

No.	Species	Height	Pot Size	Specification	Density	Mix %
120	Astrantia major 'Hadspen Blood'		3L	Full Pot	5/m ²	10%
175	Bergenia cordifolia 'Purpurea'		3L	Full Pot	5/m ²	15%
120	Crocasmia 'George Davison'		3L	Full Pot	5/m ²	10%
231	Deschampsia cespitosa		3L		5/m ²	20%
175	Heuchera 'Pluie de Feu'		3L	Full Pot	5/m ²	15%
175	Pulmonaria rubra		3L	Full Pot	5/m ²	15%
175	Veronica austriaca teucrium 'Roseum'		3L	Full Pot	5/m ²	15%

Mix P6

No.	Species	Height	Pot Size	Specification	Density	Mix %
140	Alchemilla mollis		3L		5/m ²	15%
95	Bergenia 'Abendglut'		3L		5/m ²	10%
140	Coreopsis verticillata 'Moonbeam'		3L		5/m ²	15%
140	Crocasmia 'Lucifer'		3L		5/m ²	15%
140	Pennisetum setaceum 'Sky Rocket'		3L		5/m ²	15%
140	Persicaria amplexicaulis 'Blackfield'		3L		5/m ²	15%
140	Pimpinella major 'Rosea'		3L		5/m ²	15%

Mix V1

No.	Species	Height	Pot Size	Specification	Density	Mix %
701	Echinacea purpurea	30-40cm	3	5 Buds : :Full Pot :C	6/m ²	15%
701	Geranium himalayense 'Gravetye'		2L	Full Pot :C	6/m ²	15%
701	Hebe 'Purple Pixie'		3L	Bushy :C	6/m ²	15%
701	Penstemon 'Blackbird'		2L		6/m ²	15%
612	Pulmonaria 'Blue Ensign'		3L	Full Pot :C	6/m ²	13%
701	Sedum spectabile 'Brilliant'		3L	Full Pot :C	6/m ²	15%
612	Stachys byzantina 'Big Ears'		3L	Full Pot :C	6/m ²	13%

Mix V2

No.	Species	Height	Pot Size	Specification	Density	Mix %
566	Agastache 'Black Adder'		3L	Full Pot	6/m ²	10%
730	Artemisia 'Powis Castle'		3L	Full Pot	6/m ²	13%
730	Centranthus ruber		3L	Full Pot	6/m ²	13%
730	Cistus purpureus		3L	C	6/m ²	13%
566	Iris 'Dutch Chocolate'		3L	Full Pot	6/m ²	10%
834	Pennisetum alopecuroides 'Hamel'		3L	Full Pot	6/m ²	15%
730	Phlomis italica		3L	Full Pot	6/m ²	13%
834	Spiraea japonica 'Shirobana'		3L	C	6/m ²	15%

Mix V3

No.	Species	Height	Pot Size	Specification	Density	Mix %
462	Astrantia major 'Rubra'		2L	Full Pot :C	5/m ²	15%
462	Bergenia 'Silberlicht'		2L	Full Pot :C	5/m ²	15%
462	Geranium oxonianum 'Wargrave Pink'		2L	Full Pot :C	5/m ²	15%
462	Hakonechloa macra		3L	Full Pot	5/m ²	15%
599	Hebe 'Green Globe'		3L	Bushy :5 brks	5/m ²	20%
599	Liriope muscari 'Monroe'		3L		5/m ²	20%

Mix V4

No.	Species	Height	Pot Size	Specification	Density	Mix %
750	Centranthus ruber 'Albus'		2L	Full Pot	7/m ²	17%
750	Cistus purpureus		3L	C	7/m ²	17%
750	Epimedium x perralchicum 'Frohnleiten'		3L	Full Pot	7/m ²	17%
750	Geranium oxonianum 'A T Johnson'		2L	Full Pot	7/m ²	17%
663	Pachysandra terminalis 'Green Carpet'	10-20cm	3L	Several shoots :6/9 brks :C	7/m ²	15%
663	Rosmarinus officinalis 'Severn Sea'	30-40cm	3L	Bushy :3/5 brks :C	7/m ²	15%

Mix V5

No.	Species	Height	Pot Size	Specification	Density	Mix %
328	Anemone hupehensis 'September Charm'		3L	Full Pot	5/m ²	15%
328	Aster frikartii 'Monch'		3L	Full Pot	5/m ²	15%
228	Bergenia 'Bressingham Ruby'		3L	Full Pot	5/m ²	10%
328	Carex oshimensis 'Everest'		3L	Full Pot	5/m ²	15%
228	Coreopsis verticillata 'Moonbeam'		3L	Full Pot	5/m ²	10%
228	Matteuccia struthiopteris		3L	Full Pot	5/m ²	10%
328	Sanguisorba 'Tanna'		3L	Full Pot	5/m ²	15%
228	Veronica longifolia 'Charlotte'		3L	Full Pot	5/m ²	10%

Mix V6

No.	Species	Height	Pot Size	Specification	Density	Mix %
133	Aster 'Little Carlow'		3L		5/m ²	15%
91	Hebe 'Garden Beauty Blue'		3L		5/m ²	10%
91	Hemerocallis 'Stella de Oro'		3L		5/m ²	10%
133	Lavandula angustifolia 'Hidcote'		3L		5/m ²	15%
91	Philadelphus 'Belle Etoile'		3L		5/m ²	10%
133	Rudbeckia fulgida deamii		3L		5/m ²	15%
91	Santolina chamaecyparissus		3L		5/m ²	10%
133	Stipa tenuissima		3L		5/m ²	15%

Mix W1

No.	Species	Height	Pot Size	Specification	Density	Mix %
152	Bergenia 'Bressingham White'		3L	Full Pot :C	6/m ²	15%
172	Geranium phaeum 'Album'		2L	Full Pot	6/m ²	17%
172	Hebe 'Green Globe'	40-60cm	3L	Bushy :5 brks :C	6/m ²	17%
172	Liriope muscari 'Monroe'		2L	Full Pot	6/m ²	17%
152	Persicaria affinis 'Superba'		3L	Full Pot	6/m ²	15%
172	Sarcococca humilis	40-60cm	3L	Bushy :3 brks :C	6/m ²	17%

Mix W2

No.	Species	Height	Pot Size	Specification	Density	Mix %
132	Allium schoenoprasum		2L	Full Pot :C	6/m ²	10%
191	Anthriscus sylvestris 'Ravenswing'		3L	4 Buds :Full Pot :C	6/m ²	15%
191	Bergenia 'Bressingham White'		2L	Full Pot :C	6/m ²	15%
191	Polystichum setiferum		3L	Full Pot	6/m ²	15%
191	Stipa tenuissima		3L	Full Pot	6/m ²	15%
191	Tiarella 'Spring Symphony'		3L	Full Pot :C	6/m ²	15%
191	Vinca minor 'Alba'	30-40cm	3L	Branched :3/5 brks :C	6/m ²	15%

Mix W3

No.	Species	Height	Pot Size	Specification	Density	Mix %
21	Geranium Rozanne		2L		5/m ²	20%
21	Hebe 'Nicola's Blush'		3L		5/m ²	20%
11	Liriope muscari 'Big Blue'		2L		5/m ²	10%
11	Liriope muscari 'Monroe White'		2L		5/m ²	10%
11	Pachysandra terminalis 'Green Carpet'	10-20cm	3L	Several shoots :6/9 brks :C	5/m ²	10%
21	Philadelphus 'Manteau d'Hermine'	20-30cm	3L	Bushy :3/5 brks :C	5/m ²	20%
11	Vinca minor 'Gertrude Jekyll'		2L	7 brks :C	5/m ²	10%

Mix W4

No.	Species	Height	Pot Size	Specification	Density	Mix %
36	Anemone × hybrida 'September Charm'		2L		4/m ²	10%
36	Astrantia major sub. involucreta 'Shaggy'		3L	Full Pot	4/m ²	10%
98	Hebe 'Red Edge'	25-30cm	3L	Bushy :5 brks :C	4/m ²	30%
36	Perovskia 'Blue Spire'		3L	Full Pot	4/m ²	10%
67	Rosa 'Kent'	40cm	3L	Bushy :3 brks :C	4/m ²	20%
67	Verbena bonariensis		2L	Full Pot	4/m ²	20%

Mix W5

No.	Species	Height	Pot Size	Specification	Density	Mix %
26	Euonymus fortunei 'Emerald Gaiety'	20-30cm	3L	Bushy :3/4 brks :C	4/m ²	15%
26	Osmanthus burkwoodii	60-80cm	5L	Branched :3/5 brks :C	4/m ²	15%
33	Polystichum munitum		2L	Full Pot	4/m ²	20%
26	Prunus laurocerasus 'Rotundifolia'	60-80cm	4L	Bushy :4/6 brks :C	4/m ²	15%
33	Symphoricarpos doorei. 'White Hedge'	40-60cm	3L	Bushy :4/6 brks :C	4/m ²	20%
26	Viburnum tinus	40-60cm	3L	Branched :3/5 brks :C	4/m ²	15%