

**Brook Lane
Whitehill & Bordon**

Plant Schedule

122-SCH-001

Revision	Status	Date
P1	For Planning	27.01.2021

Notes

To be read alongside the latest revision of the following Greenhalgh Landscape Architecture Planting Plans:

- 176-201
- 176-202
- 176-203
- 176-204
- 176-205
- 176-206

TREES						
Note: All trees can be supplied as rootballed stock if brought to site and planted inside the planting season. Otherwise, Airpot is the default specification.						
Entrance Road and Meadow and Play area						
Species	Common Name	Girth (cm)	Height (cm)	Form	Cont/ root	Qty
<i>Acer campestre</i>	Field Maple	20-25cm		c/s	RB	17
<i>Castanea sativa</i>	Sweet Chestnut	20-25cm		c/s	RB	15
<i>Sorbus aria</i>	Whitebeam	20-25cm		c/s	RB	35
<i>Tamarix tetrandra</i>	Four Stamen Tamarisk	3m		c/s	RB	18
<i>Quercus robur</i>	English oak	20-25cm		c/s	RB	25

Southern Lane and Communal Gardens						
<i>Acer campestre</i> 'Elsrijk'	Field Maple Elsrijk	20-25cm		c/s	RB	9
<i>Acer x freemanii</i> 'Autumn Blaze'	Freeman Maple	30-35cm		c/s	RB	13
<i>Amelanchier lamarkii</i> 'Robin Hill'	Juneberry / Snow Mespilus	20-25cm		c/s	RB	13
<i>Amelanchier lamarkii</i>	Juneberry / Snow Mespilus	2-3m		m/s	RB	5
<i>Elaeagnus angustifolia</i>	Russian Olive	20-25cm		c/s	RB	16
<i>Syringa josikaea</i>	Hungarian Lilac	2-3m		m/s	RB	9

Parking Courts						
<i>Crataegus x persimillis</i> 'Splendens'	Frosted Thorn	20-25cm		c/s	RB	2
<i>Gleditsia triacanthos</i> 'Shademaster'	Honey Locust	30-35cm		c/s	RB	3
<i>Sorbus aucuparia</i> 'Joseph Rock'	Mountain Ash Joseph Rock	20-25cm		c/s	RB	4
<i>Sorbus aucuparia</i> 'Sheerwater Seedling'	Mountain Ash Sheerwater Seedling	20-25cm		c/s	RB	17

Pond Area						
<i>Alnus glutinosa</i>	Alder	3-4m		ftd	RB	17
<i>Betula nigra</i>	River Birch	3-4m		ftd	RB	33
<i>Salix alba</i>	White Willow	3-4m		ftd	RB	15
<i>Salix caprea</i>	Goat Willow	3-4m		ftd	RB	32
<i>Populus nigra</i>	White Poplar	3-4m		ftd	RB	13

Boundaries						
<i>Betula pendula</i>	Silver Birch	14-15cm		ftd	RB	15
<i>Carpinus betulus</i>	Hornbeam	18-20cm		c/s	RB	7
<i>Crataegus monogyna</i>	Hawthorn	14-16cm		ftd	RB	12
<i>Quercus ilex</i>	Holm Oak	2-3m		ftd	RB	29
<i>Sorbus aucuparia</i>	Mountain Ash	18-20cm		c/s	RB	10
<i>Sorbus torminalis</i>	Service Tree	18-20cm		c/s	RB	6

Care Home						
<i>Arbutus unedo</i>	Strawberry Tree	2-3m		m/s	RB	4
<i>Amelanchier lamarkii</i>	Juneberry / Snow Mespilus	2-3m		m/s	RB	3
<i>Cercis siliquastrum</i>	Judas Tree	2-3m		m/s	RB	5
<i>Juglans regia</i>	English Walnut	20-25cm		c/s	RB	7
<i>Syringa vulgaris</i> 'Madame Lemoine'	Hungarian Lilac	2-3m		m/s	RB	11
<i>Malus</i> 'Egremont Russet'	Apple 'Egremont Russet'	Half Standard	1.5-2m	MM106	cont	5
<i>Malus</i> 'Scrumptious'	Apple 'Scrumptious'	Half Standard	1.5-2m	MM106	cont	3
<i>Pyrus communis</i> 'Concorde'	Pear 'Concorde'	Half Standard	12L	or Kirchn	pot	5

Fruit/ garden trees						
Species	Common Name	Specification	Height (cm)	Rootstock	Cont/ root	Qty
<i>Malus domestica</i> 'Sunset'	Apple 'Sunset'	Half Standard	1.5-2m	MM106	cont	20
<i>Malus domestica</i> 'Falstaff'	Apple 'Falstaff'	Half Standard	1.5-2m	MM106	cont	9
<i>Prunus domestica</i> 'Victoria'	Plum 'Victoria'	Half Standard	1.5-2m		cont	10
<i>Prunus domestica</i> 'Oullins Golden Gage'	Greengage 'Oullins Golden Gage'	Half Standard	1.5-2m			15
<i>Pyrus communis</i> 'Sensation'	Pear 'Sensation'	Half Standard	12L	or Kirchn	pot	29

NATIVE STRUCTURE PLANTING							
Species	Common Name	Code	Height (cm)	Habit	Breaks	Density / m ²	%
<i>Acer campestre</i>	Field Maple	1+1	60/75	Bushy	5	1	20
<i>Berberis thunbergii</i>	Barberry	1+1	60/75	Bushy		1	20
<i>Crataegus monogyna</i>	Hawthorn	1+1	60/75	Bushy	5	1	20
<i>Ilex aquifolium</i>	Ivy		3L	Busy to base		1	10
<i>Viburnum opulus</i>	Guelder Rose	1+1	40/60	Bushy	3	1	10
<i>Rosa canina</i>	Dog Rose	1+1	45/60	Bushed		1	10
<i>Ulex minor</i>	Dwarf gorse		3L	Busy		1	10

WET WOODLAND MIX							
Species	Common Name	Code	Height (cm)	Habit	Breaks	Density / m ²	%
<i>Alnus glutinosa</i>	Alder	1+1	60/80	Branched	5	1	20
<i>Sambucus nigra</i>	Elder	1+1	60/80	Branched	5	1	10
<i>Populus nigra</i>	Black Poplar	1+1	60/80	Branched	5	1	10
<i>Salix caprea</i>	Goat Willow	1+1	60/80	Bushy	5	1	20
<i>Salix fragilis</i>	Crack Willow	1+1	60/80	Bushy	5	1	10
<i>Salix viminalis</i>	Osier	1+1	60/80	Branched	5	1	20
<i>Quercus robur</i>	Oak	1+1	60/80	Bushy	5	1	10

NATIVE HEDGEROW MIX H1							
Species	Common Name	Code	Height (cm)	Habit	Breaks	Density / m ²	%
Planted density at 5 plants per linear meter in a double staggered row							
<i>Crataegus monogyna</i>	Hawthorn	1+1	40/60	Bushy	3		30
<i>Sambucus nigra</i>	Elder	1+1	40/60	Bushy	3		20
<i>Prunus spinosa</i>	Spindle	1+1	40/60	Bushy	3		20
<i>Rosa canina</i>	Dog rose	1+1	40/60	Bushy	3		10
<i>Viburnum opulus</i>	Guelder Rose	1+1	40/60	Bushy	3		10
<i>Viburnum lantana</i>	Wayfaring Tree	1+1	40/60	Bushy	3		10

ORNAMENTAL HEDGEROW MIX H2							
Species	Common Name	Code	Height (cm)	Habit	Breaks	Density / m ²	%
Planted density at 4 plants per linear meter in a double staggered row							
<i>Griselinia littoralis</i>	New Zealand Privet	1+1	40/60	Bushy	3		30

ORNAMENTAL HEDGEROW MIX H3							
Species	Common Name	Code	Height (cm)	Habit	Breaks	Density / m ²	%
Planted density at 5 plants per linear meter in a double staggered row							
<i>Prunus lusitanica</i>	Portuguese Laurel	1+1	80/100	Bushy	3		30

AMENITY GRASS SEED MIX							
					%	Sowing rate	
Germinal Amenity "A4 (Low Maintenance Mix)"						50g/m ² (500kg/ha)	

AMENITY LAWNS							
Rolawn "Medallion" Turf							

MEADOW GRASS SEED MIX							
Emorsgate "EM3 (Special General Purpose)"							

INFRASTRUCTURE LANDSCAPE - PLANTING MIX A TO D

Planting Mix: A					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Cornus stolonifera</i> 'Flaviramea'	Golden Twig Dogwood	3	2.5		10
<i>Ceanothus</i> 'Burkwoodii'	Californian lilac 'Burkwoodii'	2	3		10
<i>Lavandula angustifolia</i> 'Munstead'	Lavender	3	5		20
<i>Leucanthemum</i> × <i>superbum</i>	Shasta Daisy	3	7		20
<i>Skimmia japonica</i>	Japanese Skimmia	3	3.5		20
<i>Panicum elegans</i> 'Frosted Explosion'	Switchgrass	5	5		20

Planting Mix: B					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Nepeta racemosa</i> 'Walker's Low'	Cat Mint	2L	4		25
<i>Rosa</i> 'Kent'	White groundcover rose	3	3.5		30
<i>Rosmarinus officinalis</i>	Rosemary	5	5		20
<i>Skimmia japonica</i>	Japanese Skimmia	3	3.5		25

Planting Mix: C					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Leucanthemum</i> × <i>superbum</i> 'Banana Cream'	Shasta Daisy	2	7		15
<i>Sesleria autumnalis</i>	Moor grass	5	5		25
<i>Skimmia</i> × <i>confusa</i> 'Kew Green'	Skimmia 'Kew Green'	3	3.5		15
<i>Panicum virgatum</i> 'Rehbraun'	Switchgrass	5	4.5		15
<i>Persicaria amplexicaulis</i> 'Firetail'	Red bistort	2	7		15
<i>Phlomis russeliana</i>	Turkish sage	5	4.5		15

Planting Mix: D					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Allium ursinum</i>	Wild Garlic	3	3	3	20
<i>Anemathele lessonia</i>	Pheasant Grass	3	3	3	30
<i>Hyacinthoides non-scripta</i>	Bluebells	3	3	3	bulbs
<i>Geranium pratense</i>	Meadow Crane's-bill	3	5	5	15
<i>Polystichum munitum</i>	Sword fern	3	5	5	20
<i>Vinca major</i>	Greater periwinkle	3	3	5	15

PRIVATE PLOT LANDSCAPE - PLANTING MIX 1 TO 8
Planting Mix 1: Entrances - Narrow planting beds in full/partial sun

Species	Common Name	Pot/ root	Density / m ²		%
<i>Agapanthus africanus</i>	African Lily	2	5		30
<i>Choysia ternata</i>	Mexican orange blossom	3	3		25
<i>Rosa</i> 'Amber Carpet'	Amber groundcover rose	5	3.5		30
<i>Salvia</i> 'Blue Note'	Hardy Salvia	2	5		15

Planting Mix 2: Entrances - Large planting beds in full/partial sun

Species	Common Name	Pot/ root	Density / m ²		%
<i>Choysia ternata</i>	Mexican orange blossom	3	3		10
<i>Libertia grandiflora</i>	New Zealand Satin Flower	3	4		20
<i>Nepeta racemosa</i> 'Walker's Low'	Cat Mint	2	5		20
<i>Rosa</i> 'Amber Carpet'	Amber groundcover rose	5	3.5		30
<i>Salvia rosmarinus</i> 'Miss Jessopp's Upright'	Rosemary	5	5		10
<i>Salvia</i> 'Blue Note'	Hardy Salvia	2	5		10

Planting Mix 3: Entrances - Narrow planting beds in shade

Species	Common Name	Pot/ root	Density / m ²		%
<i>Anemone × hybrida</i> 'Honorine Jobert'	Japanese anemone	2	6		25
<i>Geranium</i> 'Rozanne'	Hardy Geranium	2	6		20
<i>Pittosporum tobira</i> 'Nanam'	Dwarf Japanese Mock Orange	10L	3		30
<i>Rosa</i> 'Kent'	White groundcover rose	5	3.5		25

Planting Mix 4: Entrances - Large planting beds in shade

Species	Common Name	Pot/ root	Density / m ²		%
<i>Astilbe</i> 'Rheinland'	False goatsbeard	2	5		20
<i>Hydrangea</i> 'Bluebird'	Hydrangea	3	3.5		10
<i>Geranium</i> 'Rozanne'	Hardy Geranium	2	6		20
<i>Philadelphus</i> 'Belle Etoile'	Mock orange	10L	spec		spec
<i>Polystichum polyblepharum</i>	Japanese tassel fern	5L	3.5		20
<i>Pittosporum tobira</i> 'Nanam'	Dwarf Japanese Mock Orange	10L	3		15
<i>Skimmia japonica</i>	Japanese skimmia	3L	3.5		15

Planting Mix: 5 - Communal Gardens

Species	Common Name	Pot/ root	Density / m ²		%
<i>Leucanthemum × superbum</i> 'Banana Cream'	Shasta Daisy	2	7		15
<i>Pachysandra terminalis</i>	Japanese spurge	2	5		15
<i>Salvia</i> 'Blue Note'	Salvia 'Blue Note'	2	5		10
<i>Salvia</i> 'Caradonna'	Salvia 'Caradonna'	2	5		10
<i>Sesleria autumnalis</i>	Moor grass	5	4		25
<i>Rosa Gold Rosa Carpet</i>	Gold groundcover rose	5	3.5		25

Planting Mix: 6 - Communal Gardens

Species	Common Name	Pot/ root	Density / m ²		%
<i>Crocsmia</i> 'George Davidson'	Crocsmia	3	4		20
<i>Calamagrostis x acutifolia</i> 'Karl Foerster'	Feather reed-grass 'Karl Foerster'	5	4		20
<i>Leucanthemum × superbum</i> 'Banana Cream'	Shasta Daisy	2	7		15
<i>Persicaria amplexicaulis</i> 'Firetail'	Red Bistort	2	4		20
<i>Phlomis russeliana</i>	Turkish sage	2	4		10
<i>Skimmia x confusa</i> 'Kew Green'	Skimmia 'Kew Green'	3	3.5		15

Planting Mix CH1 - Care Home Gardens in full/partial sun					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Agapanthus africanus</i>	African Lily	2	5		20
<i>Choysia ternata</i>	Mexican orange blossom	2	3		10
<i>Libertia grandiflora</i>	New Zealand Satin Flower	2	4		10
<i>Nepeta racemosa</i> 'Walker's Low'	Cat Mint	2	5		30
<i>Rosa</i> 'Kent'	White groundcover rose	5	3.5		20
<i>Salvia rosmarinus</i> 'Miss Jessopp's Upright'	Rosemary	3	5		10

Planting Mix CH2 - Care Home Gardens in full/partial sun					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Hesperantha coccinea</i> 'Major'	Crimson Flag	2	6		5
<i>Hesperantha coccinea</i> 'Sunrise	Crimson Flag	2	6		5
<i>Miscanthus sinensis</i> 'Gracillimus'	Chinese silver grass	5	2		10
<i>Nepeta racemosa</i> 'Walker's Low'	Cat Mint	2	5		10
<i>Paeonia lactiflora</i> 'Karl Rosenfield'	Red Peony	5	4		10
<i>Pittosporum tenuifolium</i> 'Golf Ball'	Golf ball pittisporum	10	spec		5
<i>Rosa</i> 'Suffolk'	Pink groundcover rose	3	3.5		10
<i>Salvia</i> 'Jezebel'	Salvia 'Jezebel'	2	5		10
<i>Sesleria autumnalis</i>	Moor grass	5	4		5
<i>Panicum elegans</i> 'Frosted Explosion'	Switchgrass	5	4		10
<i>Oenothera lindheimeri</i> 'Siskiyou Pink'	Gaura	2	5		10
<i>Sarcococca confusa</i>	Sweet box	5	4		10
Bulb planting					
<i>Allium</i> 'Purple Sensation'	Ornamental onion 'Purple Sensation'	10 bulbs groups of 15 planted through the beds			
<i>Allium</i> 'Universe'	Ornamental onion 'Universe'	10 bulbs groups of 15 planted through the beds			

Planting Mix CH3 - Care Home Gardens in shade					
Species	Common Name	Pot/ root	Density / m ²		%
<i>Anemone</i> × <i>hybrida</i> 'September Charm'	Japanese anemone	2	5		20
<i>Geranium</i> 'Rozanne'	Hardy Geranium	2	6		25
<i>Pachysandra terminalis</i>	Japanese spurge	2	5		15
<i>Philadelphus</i> 'Belle Etoile'	Mock orange	10L	spec		spec
<i>Polystichum polyblepharum</i>	Japanese tassel fern	5L	3.5		25
<i>Tiarella</i> 'Spring Symphony'	Foam flower	2L	8		15

POND PLANTING MIXES

NOTE: To be planted in same-species groups of 3, 5 or 7.

Planting Mix: P1

Species	Common Name	Pot/ root	Density / m ²		%	
<i>Butomus umbellatus</i>	Flowering Rush	2L	8		20	
<i>Caltha palustris</i>	Marsh Marigold	p 9	6		10	
<i>Nymphaea alba</i>	Water lily	1L	5		50	
<i>Callitriche autumnalis</i>	Water starwort	1L	5		50	

Planting Mix: P2

MEADOW GRASS SEED MIX

Emorsgate "EM8 – MEADOW MIXTURE FOR WETLANDS"

Planting Mix: P3

Species	Common Name	Pot/ root	Density / m ²		%	
<i>Carex sp. *</i>	Carex	p 9	6		5	
<i>Carex vulpina **</i>	Carex	p 9	6		5	
<i>Carex paniculata *</i>	Carex	p 9	6		5	
<i>Cyperis longus</i>	Galingale	p 9	8		5	
<i>Epilobium sp. *</i>	Willowherb	p 9	6		5	
<i>Filipendula ulmaria *</i>	Meadow Sweet	p 9	6		5	
<i>Glyceria maxima *</i>	Reed sweet-grass	p 9	6		5	
<i>Iris pseudocorus *</i>	Yellow Flag Iris	p 9	6		10	
<i>Juncus effusus *</i>	Common Rush	p 9	6		5	
<i>Lythrum salicaria</i>	Loosestrife	p 9	6		10	
<i>Phalaris arundinacea *</i>	Phalaris arundinacea	p 9	6		15	
<i>Ranunculus lingua</i>	Greater spearwort	p 9	5		10	
<i>Sparganium erectum *</i>	Branched bur-reed	p 9	6		5	
<i>Typhus angustifolia</i>	Lesser Bulrush	p 9	5		10	

Sources of species recommendations:

* Ecology Report

** Sussex Wildlife Trust