N

EXISTING HIGH LEVEL, HIGH VOLTAGE ELECTRICITY CABLES. REFER TO UKPN GS6 SURVEY AND CONSTRAINTS PLAN FOR FURTHER INFORMATION AND SAFE WORKING HEIGHTS

EXISTING HIGH LEVEL, HIGH VOLTAGE ELECTRICITY CABLES. REFER TO UKPN GS6 SURVEY AND CONSTRAINTS PLAN FOR FURTHER INFORMATION AND SAFE WORKING HEIGHTS

EXISTING LIVE RISING MAIN PRESENT WITHIN WORKS AREA. REFER TO PROJECT SPECIFIC RAMS DOCUMENTATION

EXTENT NOT SURVEYED, TBC ON SITE

EXISTING HIGH LEVEL, HIGH VOLTAGE ELECTRICITY CABLES. REFER TO UKPN GS6 SURVEY AND CONSTRAINTS PLAN FOR FURTHER INFORMATION AND SAFE WORKING HEIGHTS

Ham Manor Barn

Reservoir (covered)

L.A.P & AREA IN ABEYANCE

AREA IN ABEYANCE

L.E.A.P

L.E.A.P

Substation

Cycles

Bins

Gas

FOR CONTINUATION SEE CIV-1-4006

FOR CONTINUATION SEE CIV-1-4004

FOR CONTINUATION SEE CIV-1-4006

REFER TO PATRICK PARSON DRAWINGS FOR 5278 DETAILS

GOLFERS LANE

REPRODUCED FROM ORDNANCE SURVEY @ BY THE PERMISSION OF THE CONTROLLER OF HER MAJESTY'S STATIONERY OFFICE. © CROWN COPYRIGHT. ALL RIGHTS RESERVED. LICENCE NUMBER 100045322.

P:\23-104 - Rustington Golf Course\Tech\Acad\Drawings\CIV-1-4005 - Construction Makeup Sheet 2 of 3.dwg

NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE MANUAL FOR CONTRACT DRAWINGS, VOLUME 1, SPECIFICATION FOR HIGHWAY WORKS AND ALL OTHER RELATED DRAWINGS ISSUED.
2. IF THERE IS ANY AMBIGUITY BETWEEN THE SPECIFICATION AND THE DRAWINGS, THE CONTRACTOR SHALL IMMEDIATELY INFORM THE ENGINEER.
3. ALL MATERIALS AND WORKMANSHIP SHALL COMPLY FULLY WITH THE NHBC SPECIFICATION MANUAL FOR CONTRACT DOCUMENTS FOR HIGHWAY WORKS, VOLUME 1, SPECIFICATION FOR HIGHWAY WORKS.
4. NO DEVIATION FROM THE DETAILS SHOWN ON THIS DRAWING IS PERMITTED WITHOUT PERMISSION FROM THE ENGINEER.
5. THE CONTRACTOR SHALL UNDERTAKE SUCH MATERIALS TESTING AS INDICATED IN THE SPECIFICATIONS AND SHALL INCLUDE THE COST OF TESTING IN THE TENDER.
6. REFER TO LANDSCAPE ARCHITECT PLANS FOR FENCE/ BOUNDARY DETAILS.
7. FOR HIGHWAY CONSTRUCTION DETAILS REFER TO ODYSSEY DRAWING CIV-1-4007.

LEGEND:

- SITE BOUNDARY
- PRECAST CONCRETE BULLNOSE KERB WITH 25mm UPSTAND
- PRECAST CONCRETE BULLNOSE KERB 0-6mm UPSTAND REQUIRED AT TACTILE CROSSING POINTS
- PRECAST CONCRETE BULLNOSE KERB INVERTED AND LAID FLUSH
- PRECAST CONCRETE EDGING KERB LAID FLUSH
- PRECAST CONCRETE HALF BATTERED KERB WITH 125mm UPSTAND
- TRANSITION KERB
- 1.8m CLOSEBOARD FENCE
- COMBINED BRICK PIER & FENCE PANEL WALL - REFER TO BDWH DRAWING DB-SD13-013
- PROPOSED TREE RPA FENCING
- ROOT PROTECTION ZONE AND FENCING
- EXISTING RISING MAIN AND 6m EASEMENT
- EXISTING RISING MAIN EXTENT NOT SURVEYED. DEPTH AND LOCATION TBC ON SITE PRIOR TO COMMENCEMENT OF WORKS
- EXISTING ELECTRIC CABLE BLOWOUT DISTANCES AND 3m EASEMENT
- 1.8m OFFSET SAFE BUILD ZONE
- ASPHALT CARRIAGEWAY
- PRIVATE ASPHALT DRIVEWAY
- PERMEABLE BLOCK PAVING
- ASPHALT FOOTWAY
- ASPHALT VEHICLE CROSSOVER
- IMPERMEABLE BLOCK PAVING
- PRIVATE PATH PAVING SLAB CONSTRUCTION
- GRASS
- UNCONTROLLED PEDESTRIAN CROSSING. 400x400mm BUFF BLISTER TACTILE PAVING SLABS
- HAZARD WARNING PAVING. 400x400mm BUFF CORDUROY TACTILE PAVING SLABS
- BIN STORAGE AND COLLECTION POINTS COMPRISED OF PAVING SLAB CONSTRUCTION

FOR CONSTRUCTION DETAILS REFER TO ODYSSEY DRAWING CIV-1-4007 UNLESS SPECIFIED OTHERWISE

WHERE PAVING SLAB CONSTRUCTION DOESN'T ABUT A BUILDING, PEA SHINGLE INFILL IS TO BE INCORPORATED

FOR CONSTRUCTION

SUBJECT TO TECHNICAL APPROVAL

Rev	Amendments	Drn	Chk	App	Date
E	KERB TYPE UPDATED	CLL	BOM	TG	04.12.24
D	UPDATED TO SUIT NEW SITE LAYOUT	CLL	LP	TG	03.09.24
C	PHASE 2 DETAILS ADDED	CLL	LP	TG	26.01.24
B	UPDATED TO SUIT NEW SITE LAYOUT	CLL	LP	TG	11.12.23
A	BOUNDARY TREATMENTS ADDED	CLL	LP	TG	05.09.23

ODYSSEY
Tuscany House
White Hart Lane
Basingstoke
Hampshire RG21 4AF
Telephone: 01256 331144
Fax: 01256 331134
E: info@odysseyconsult.co.uk
W: www.odysseyconsult.co.uk

Job Title: RUSTINGTON GOLF COURSE

Drawing Title: CONSTRUCTION MAKEUP SHEET 2 OF 3

Client: BARRATT DEVELOPMENTS PLC

Scale	Date	Designed
1:250 @A0	AUG 23	JD
Drawn	Checked	Approved
JD	LP	TG

Job No	Drawing No	Rev
23-104	CIV-1-4005	E