

Tree Planting								
No.	Abb. Text	Species	Form	Age	Girth	Height	Clear Stem	Root
1	Acr cm	Acer campestre	Standard (Heavy)	3x	12-14cm	400-450cm	min 200cm	RB
22	Be pnd	Betula pendula	Standard (Heavy)	2x	12-14cm	350-425cm	175-200cm	RB
6	Crpns bt F	Carpinus betulus 'Fastigiata'	Semi-Mature	4x	20-25cm	450-500cm	min 200cm	RB
1	Crpns bt F	Carpinus betulus 'Fastigiata'	Standard (Heavy)	3x	12-14cm	400-450cm	175-200cm	RB
2	Cstn st	Castanea sativa	Standard (Heavy)	3x	12-14cm	400-450cm	175-200cm	RB
22	Liq sty	Liquidambar styraciflua	Standard (Heavy)	3x	12-14cm	400-450cm	min 200cm	B
3	Mgn kbs	Magnolia kobus	Standard (Heavy)	3x	12-14cm	400-450cm	min 200cm	RB
6	Pns sy	Pinus sylvestris	Standard (Heavy)	5x	12-14cm	250-300cm		RB
21	Pms av	Prunus avium	Standard (Heavy)	2x	12-14cm	300-350cm	175-200cm	B
12	Pms pd	Prunus padus	Standard (Extra Heavy)	2x	14-16cm	300-350cm	175-200cm	B
15	Pys cl C	Pyrus calleryana 'Chanticleer'	Standard (Selected)	2x	10-12cm	300-350cm	175-200cm	RB
1	Qr ro	Quercus robur	Standard (Heavy)	3x	12-14cm	400-450cm	175-200cm	RB
1	Ti cr	Tilia cordata	Standard (Selected)	2x	10-12cm	300-350cm	175-200cm	RB
5	Ti cr GS	Tilia cordata 'Green Spire'	Standard (Heavy)	3x	12-14cm	400-450cm	175-200cm	RB
118								

Edge Mix								
Qty	Abb. Text	Species	Root	Height	Habit	Age	Centres	Mix %
49	Acr cm	Acer campestre	B	200-250cm		2x	1.000	7.00 %
103	Cor san	Cornus sanguinea	B	60-80cm		1/2	1.000	15.00 %
103	Cryls av	Corylus avellana	B	200-250cm	Branched	2x	1.000	15.00 %
103	Iix aq	Ilex aquifolium	B	60-80cm		1/1	1.000	15.00 %
49	Mal syl	Malus sylvestris	B	60-80cm	Branched	1/1	1.000	7.00 %
34	Pru spi	Prunus spinosa	B	60-80cm		1/1	1.000	5.00 %
96	Smb ng	Sambucus nigra	B	60-80cm	Branched	1/1	1.000	14.00 %
49	Sor auc	Sorbus aucuparia	B	200-250cm		2x	1.000	7.00 %
103	Vib op	Viburnum opulus	B	60-80cm		1/1	1.000	15.00 %
689								

Native Hedge Mix								
Qty	Abb. Text	Species	Root	Height	Habit	Form	Age	Centres (m)
211	Acr cm	Acer campestre	B	60-80cm		Transplant	1/1	0.400
369	Crtg mn	Crataegus monogyna	B	60-80cm		Seedling	1/0	0.400
263	Cryls av	Corylus avellana	B	60-80cm	Branched		1u1	0.400
106	Ii aq	Ilex aquifolium	C	60-80cm				0.400
53	Pms sp	Prunus spinosa	B	60-80cm	Branched		1/1	0.400
53	Rs on	Rosa canina	B	60-80cm				0.400
1055								

Mixed native thicket / hedgerow planting								
Qty	Abb. Text	Species	Root	Height	Habit	Form	Age	Centres (m)
40	Crtg mn	Crataegus monogyna	B	60-80cm			1/1	0.500
6	Cryls av	Corylus avellana	B	60-80cm	Branched		1/2	0.500
6	Ii aq	Ilex aquifolium	C	40-60cm	Bushy			0.500
14	Rs on	Rosa canina	B	60-80cm	Branched		1/1	0.500
6	Vb op	Viburnum opulus	B	60-80cm	Branched		1/1	0.500
72								

Hedge Planting						
Qty	Abb. Text	Species	Container	Root	Height	Centres
12	Cms sn	Cornus sanguinea	3L	C	50-60cm	0.600
710	Crpns bt	Carpinus betulus		B	60-80cm	0.600
285	Fm aln	Frangula alnus	3L	C	40-50cm	0.600
263	Lgs ov	Ligustrum ovalifolium	3L	C	60-80cm	0.600
254	Pms lauro	Prunus laurocerasus	5-7.5L	C	80-100cm	0.600
1524						

Shrub Planting						
Qty	Abb. Text	Species	Container	Root	Height	Density / m2
6	Cms al S	Cornus alba 'Sibirica'	10L	C	80-100cm	
6	Cms sn MWF	Cornus sanguinea 'Mid-Winter Fire'	15L	C	60-80cm	
16	Cryls av	Corylus avellana		B	60-80cm	2.00
16	Ii aq	Ilex aquifolium	5L	C	40-60cm	2.00
14	Lvn an H	Lavandula angustifolia 'Hidcote'	5L	C	30-40cm	
432	Lvn an M	Lavandula angustifolia 'Munstead'	5-7.5L	C	30-40cm	5.00
490						

Climber						
Qty	Abb. Text	Species	Container	Root	Height	Support Method
4	Clmt vif	Clematis vitalba	2L	C	60-80cm	Several Shoots
16	Hdr hl	Hedera helix	2L	C	50-60cm	Several Shoots
14	Jsm nd	Jasminum nudiflorum	5-7.5L	C	60-80cm	Branched
10	Rs ND	Rosa 'New Dawn'	4L	C		
24	Watr fl L	Wisteria floribunda 'Lawrence'	10L	C	150-200cm	Several Shoots
68						Cane or Framework

Herbaceous Shrub Planting						
Qty	Abb. Text	Species	Container	Root	Height	Propagation Method
39	All sp	Allium sphaerocephalon			0.500	
202	Crx cmn BF	Carex comans 'Bronze Form'	3L	C	0.500	
120	Dsch ce	Deschampsia cespitosa	3L	C	0.500	
12	Hyl tip Js Abr	Hylotelephium telephium 'Jose Aubergine'	1-2L	C	25-30cm	
202	Kir glc	Koeleria glauca	3L	C	0.500	
120	Pm al H	Pennisetum alopecuroides 'Hamein'	3L	C	0.500	
120	Slp tn	Stipa tenuissima	3L	C	0.500	
815						

Mix A								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
467	Chey tr S	Choisya ternata 'Sundancer'	5-7.5L	C	40-60cm	Bushy	0.500	35.00 %
324	Cnth BM	Ceanothus 'Blue Mound'	10L	C	40-60cm(D)	Bushy	0.600	35.00 %
276	Pms lauro OL	Prunus laurocerasus 'Otto Luyken'	5-7.5L	C	40-60cm(D)	Bushy	0.600	30.00 %
1067								

Mix B								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
760	Hb WG	Hebe 'White Gem'	5-7.5L	C	30-40cm	Bushy	0.400	40.00 %
453	Lvn an R	Lavandula angustifolia 'Rosea'	5-7.5L	C	30-40cm	Bushy	0.450	30.00 %
453	Priv at BS	Perovskia atriplicifolia 'Blue Spire'	3L	C	30-40cm	Bushy	0.450	30.00 %
1666								

Mix C								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
166	Cnth th R	Ceanothus thyrsiflorus 'Repens'	10L	C	60-80cm(D)	Bushy	0.450	10.00 %
417	Crx mr ID	Carex morrowii 'Ice Dance'		PT			0.450	25.00 %
417	Gm F	Geum 'Fireball'	1-2L	C			0.450	25.00 %
665	Lvn an M	Lavandula angustifolia 'Munstead'	5-7.5L	C	30-40cm	Bushy	0.450	40.00 %
1665								

Mix D Planting								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Ctrs	%age Mix
57	Cms st K	Cornus stolonifera 'Kelsey'	2L	C	30-40cm	Several Shoots	0.500	30.00 %
53	Lnc pl	Lonicera pileata	5-7.5L	C	40-60cm(D)	Bushy	0.600	40.00 %
57	Src hm	Sarcococca humilis	3L	C	20-25cm	Bushy	0.500	30.00 %
167								

Mix E								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
360	Eny fr EG	Euonymus fortunei 'Emerald Gaiety'	5-7.5L	C	30-40cm(D)	Bushy	0.400	30.00 %
309	Mtn aq A	Mahonia aquifolium 'Apollo'	5-7.5L	C	40-60cm	Branched	0.500	40.00 %
230	Vb dv	Viburnum davidii	5-7.5L	C	30-40cm	Bushy	0.500	30.00 %
899								

Mix F								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
167	Da R	Danae racemosa	3L	C	30-40cm	Bushy	0.500	25.00 %
424	Eny fr EG	Euonymus fortunei 'Emerald Gaiety'	5-7.5L	C	30-40cm(D)	Bushy	0.400	40.00 %
236	Fch MP	Fuchsia 'Mrs Popple'	3L	C	30-40cm	Bushy	0.500	35.00 %
827								

Mix G								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
15	Brb th B	Berberis thunbergii 'Bagatelle'	3L	C	30-40cm	Branched	0.400	30.00 %
35	Lnc pl	Lonicera pileata	5-7.5L	C	40-60cm(D)	Branched	0.300	40.00 %
15	Pch tr V	Pachysandra terminalis 'Variegata'	3L	C	15-20cm(D)	Several Shoots	0.400	30.00 %
65								

Mix H								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
124	Acb jp C	Aucuba japonica 'Crototifolia'	10L	C	40-60cm	Bushy	0.600	25.00 %
124	Chey tr	Choisya ternata	5-7.5L	C	40-60cm	Bushy	0.600	25.00 %
124	Phit x fr RR	Photinia x fraseri 'Red Robin'	10L	C	60-80cm	Branched	0.600	25.00 %
124	Pms lauro OL	Prunus laurocerasus 'Otto Luyken'	5-7.5L	C	40-60cm	Bushy	0.600	25.00 %
496								

Mix J								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
17	Cnth AB	Ceanothus 'Autumnal Blue'	3L	C	40-60cm		0.600	25.00 %
17	Eny jp	Euonymus japonicus	3L	C	30-40cm	Branched	0.600	25.00 %
17	Hb MB	Hebe 'Midsummer Beauty'	5-7.5L	C	40-60cm	Bushy	0.600	25.00 %
17	Vb tn EP	Viburnum tinus 'Eve Price'	5-7.5L	C	40-60cm	Bushy	0.600	25.00 %
68								

Mix K								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
91	Hb al RE	Hebe albicans 'Red Edge'	5-7.5L	C	30-40cm(D)	Bushy	0.400	25.00 %
91	Sdm spc B	Sedum spectabile 'Brilliant'	5-7.5L	C			0.400	25.00 %
91	Slv nm Os	Salvia nemorosa 'Ostfriesland'	3L	C			0.400	25.00 %
91	SsIr at	Sesleria autumnalis	4L	C			0.400	25.00 %
364								

Mix L								
Qty	Abb. Text	Species	Container	Root	Height	Habit	Centres	%age Mix
30	Blc sp	Blechnum spicant	1-2L	C			0.450	20.00 %
30	Brgn BW	Bergenia 'Bressingham White'	3-5L	C	30-40cm(D)		0.450	20.00 %
30	Crx mr ID	Carex morrowii 'Ice Dance'	2L	C			0.450	20.00 %
30	Eny fr EG	Euonymus fortunei 'Emerald Gaiety'	5-7.5L	C	30-40cm(D)	Branched	0.450	20.00 %
30	Epm yn R	Epimedium youngianum 'Roseum'	3-5L	C			0.450	20.00 %
150								

Fern Planting						
Qty	Abb. Text	Species	Container	Root	Height	Habit
17	Blc sp	Blechnum spicant	1-2L	C		
4	Dryp fl	Dryopteris filix-mas	1-2L	C		
3	Plys mn	Polystichum munitum	1-2L	C		
24						

Refer to drawings LAND-1-5101 to LAND-1-5108 for proposed landscaping strategy

Refer to drawing LAND-1-5603 for Landscape Specifications

EG21 Fine Lawn Grass Mixture (Sow at 250Kg/hectare or 25g/m2)			
Composition: Emorsgate EG22 is composed of top quality, fine leaved varieties of bent and fescue grasses. The choice of varieties means that this mixture is ideal for producing a first class lawn but also has the qualities required for a low maintenance grass sward.			
Grasses (100%)			
%	Latin name	Common name	
10	<i>Agrostis capillaris</i>	Common Bent	
50	<i>Festuca rubra</i>	Slender creeping Red-fescue	
40	<i>Festuca rubra</i> spp. <i>commutata</i>	Chewing's Fescue	

EM2 Standard General Purpose Meadow Mixture (Sow at 40Kg/hectare or 4g/m2)			</
---	--	--	----