

12K Acoustic EnviroFence

Acoustic Fencing | Jacksons Security

Jacksons Fencing
Stowting Common | Ashford | TN25 6BN
www.jacksons-security.co.uk
+44 (0) 1233 750 393

Jacksons
Quality that lasts
Fencing & Access Solutions



Applications

✓ Parks ✓ Schools ✓ Residential ✓ Demarcation ✓ Low - Medium Risk

A lighter 20mm thick board than our Jakoustic fencing, maintaining the same 123mm cover face. Distinguished from the heavier boards by the small chamfers which form a V-join between boards.

Standard Dimensions

Height	Post Length	Spur Posts
2.0m	2.9m	N/A
2.5m	3.4m	2.0m
3.0m	3.9m	2.5m
3.5m	4.4m	2.7m
4.0m	4.9m	3.3m

Features

- Light weight with a 20 x 125mm x 4.8m boards (planed)
- Attractive timber construction
- Achieves the Planning / Architects' normal acoustic specification of 10 - 12kg per sqm
- Capping rail 34 x 145mm x 4.8m
- Counter rail size 34 x 70mm x 2.4m
- Only available in reflective

Gates

Matching gates are available in swing, cantilever sliding and tracked in either automated or manual operation. Please ask for specifications and details.

Specify us, register online to download detailed and specific drawings and diagrams of our security products



12k EnviroFence