

Roundstone Lane Angmering

Internal Luminaire Schedule

Contents Amendment Record

This document has been issued and amended as follows (Revisions highlighted on subsequent pages):





Revision	Description	Date	Signed
T01	Issue for Tender	19 December 2019	BY
T02	Issue for Tender	31 January 2020	MEH
C01	Construction Issue	14 February 2020	MEH
C02	Construction Issue	08 April 2020	MEH
C03	Construction - EXL01 not emergency lights	01 September 2020	MEH

Roundstone Lane Angmering Internal Luminaire Schedule


No.	Manufacturer	Model	Image	Description	Lamp	Notes
Internal Lighting						
L1	TBC by Client	TBC by Client	TBC by Client	Pendan light	TBC by Client	To be placed above tables
L2 (a)	Aurora	LEDLine		LED strip lighting to all shelving (and open central area) & inside of panel - lighting facing back of wall	9.6W LED per metre 750 lumens per metre 2500-6000K (adjustable)	Refer to layouts for length
L2 (b)				Coffered ceiling with LED tape light		
L2 (c)				Inset brass kick bound with LED strip lighting		
L3	Aurora	LinearPac		Ceiling mounted Linear LED	25W LED 3000 Lumens 4000K 120lm/W	IP65 Anti-Corrosive; Length 1500mm
L4	TBC by Client	TBC by Client	TBC by Client	Table lamp	TBC by Client	/
L5	TBC by Client	TBC by Client	TBC by Client	Wall mounted light	TBC by Client	/
L6	TBC by Client	TBC by Client	TBC by Client	Wall mounted picture light	TBC by Client	/




Roundstone Lane Angmering Internal Luminaire Schedule




L7	Aurora	M-Pro		Recessed LED downlight Dimmable as standard	7W LED 640 lumens 4000K 94lm/W Non-Dimmable IP65	/
L8	Aurora	M-Pro		Recessed LED downlight Dimmable as standard	7W LED 640 lumens 4000K 94lm/W Non-Dimmable IP65	Linked to Nurse call system for activation with bed sensor at night time only
L9	Dar Lighting	Paolo		Ceiling mounted fitting with fabric shade	4No. E27 holders to be supplied with 4No. Philips 5W LED lamps (470 lumens each) 4000K Non-dimmable	dia. 800mm x 150mm high
L10	Dar Lighting	Renoir		Wall mounted fitting with fabric shade	1No. E27 holder to be supplied with 1No. Philips 5W LED lamps (470 lumens each) 4000K Non-dimmable	300mm wide x 200mm high x 180mm deep
L11	Aurora	LinkE		Linear fitting	LED Switched by door contact	Wardrobe light fitting

Roundstone Lane Angmering Internal Luminaire Schedule

L12	Aurora	Duolite		Recessed	30W LED 3000 lumens 4000K 100lm/W Non-dimmable	600 x 600 for lay in grid ceilings
L13	Aurora	Lumi-fit		Recessed slimline LED downlight	13W LED 1260 Lumens 4000K 97lm/W Dimmable IP54	dia. 145mm
L14	Aurora	LinearPac		Ceiling mounted Linear LED	40W LED 4400 Lumens 4000K 110lm/W	IP65 Anti-Corrosive; Length 1200mm
L15	Dar Lighting	Easyfit Pendant		Grey shade	1No. E27 holders to be supplied with 3No. Philips 5W LED lamps (470 lumens each) 4000K Non-dimmable	Ceiling mounted shade fitting
L16	TBC by Client	TBC by Client	TBC by Client	TBC by Client	TBC by Client	CAFÉ table feature
L17	TBC by Client	TBC by Client	TBC by Client	TBC by Client	TBC by Client	Reception desk





Roundstone Lane Angmering Internal Luminaire Schedule




L18	Searchlight	Stainless steel globe wall light		Wall mounted light	LED Lamp IP44	bathroom wall lights
L19	Aurora	Lumi-fit		Recessed slimline LED downlight	18W LED 1900 Lumens 4000K 106lm/W Dimmable	dia. 228mm
L20	Photonstar	Nemesis		Recessed LED downlight	LED Lamp 2500-6500K (adjustable)	Dementia En-suites
L21	Photonstar	LuxLoop Circadian		Ceiling mounted fitting	LED Lamp 2500-6500K (adjustable)	Dementia bedroom main light
L22	Aurora	Backlite		Recessed LED 600mm panel	36W LED 3600 lumens 100lumens/w IP20 4000K Non-dimmable	






Roundstone Lane Angmering Internal Luminaire Schedule

L23	Aurora	Versatile		Recessed LED 600mm panel	38W LED 3900 lumens 103lumens/w IP65 4000K Non-dimmable	Kitchen light fitting
L24	Sunheat	Mini Sunheat		Twin bulb heat lamp	Install with 2300K bulb. Luminaire fitted with 2no. 275W Infra-red heat lamps	Heat lamp for assisted bathrooms, recessed in coffered ceilings above baths
Emergency Lighting						
EL1	Emergency Lighting Products Ltd.	LDE3F/C		Ceiling recessed emergency downlight with battery pack. Corridor model designed to thrown narrow beam down corridors.	1.5WLED 160lumens 4500K 3hr battery back up DALI Self-test operation	dia. 35mm
EL2	Emergency Lighting Products Ltd.	LDE3F/WIDE		Ceiling recessed emergency downlight with battery pack. Wide beam distribution for open areas.	1.5WLED 160lumens 4500K 3hr battery back up DALI Self-test operation	dia. 35mm
EL3	Emergency Lighting Products Ltd.	Mexodus		Architectural LED exit sign - recessed or suspended	2.4W LED 4500K 3hr battery back up DALI Self-test operation	Contractor to select running man arrow direction to suit fire strategy layouts

Roundstone Lane Angmering Internal Luminaire Schedule

EL4	Emergency Lighting Products Ltd.	Finesse		Ceiling/wall mounted Emergency bulkhead	3W LED 170lumens 4500K 3hr battery back up DALI Self-test operation	Not with running man sticker
ELP	Emergency Lighting Products Ltd.	Surepath		Emergency lighting testing system. Remote accessible via network using surelink software	Automatic fault indication and routine dunction/duration tests.	Each panel is suitable for up to 128 devices.
External Lighting						
EXL1	Design Plan	Terminus Wall S12		Wall mounted downlight	10W LED 905 lumens IP65 4000K	Wall mounted fitting
EXL2	NOT USED					
EXL3	NOT USED					
EXL4	Fagerhult	Rondo G3 Recessed		RECESSED, ANTHRACITE GREY	10W LED Wide beam, 4000K	Recessed in eaves of roof terrace

Roundstone Lane Angmering Internal Luminaire Schedule

EXL5	Disano	1756 Monza FX		Aluminium Luminaire for high level lighting of car park areas. Directional, facing away from buildings.	26W LED, 3723lm, 4000K, CRI 70	Mounted on arm of 4m tall lighting column, as Disano 1409 Fluted Pole oxy Natural (426335-00 4100) Controlled with Timeclock and photocell.
EXL6	Glamox	O13-55 LED O13830038330		External spotlight for feature lighting across site.	4W LED, 425lm, 3000K	Mounted on earth spike (as extra from manufacturer) or directly to concrete/ hard floor surfaces. With integral control gear.
EXL7	Whitecroft	Kolo Bollard/ BLY233KSRB		Bollard light for paths across site, black finish, 998mm tall, symmetric	13.8 W, 1500 lm, 3000K	With "Kolo Bollard Root Mount" when mounted in soft surface. Flanged when mounted in hard surfaces.
EXL8	Elipta	MicroLED Warm White		LED strip light, warm white,, IP65 or greater,	6 W/m, 325lm/ m, customisable length	To be installed on the underside of each high level pergola beam. Install complete with mounting channel and waterproof as per manufacturer's recommendations. Allow for remote driver(s)
EXL9E	Whitecroft	Spectre WX		Wall mounted downlight with integrated 3hr emergency battery	3000K LED, 1119 lm	

