

P:\21-254 - Roundstone Lane, Angmering - Detailed Design\Tech\Acad\Drawings\21-254-304_305 MH Schedules.dwg

SURFACE WATER MANHOLE SCHEDULE							
CHAMBER NUMBER	COVER LEVEL (CL)	INVERT LEVEL (IL)	PIPE DIAMETER (m)	DEPTH TO SOFFIT (m)	SIZE (m)	TYPE	COVER TYPE
S1	10.465	9.328	0.150	0.987	0.45 DIA	3	A15
S2	10.595	9.066	0.225	1.304	0.60 DIA	3	A15
S3	10.555	8.901	0.225	1.429	0.60 DIA	3	A15
S4 (ST)	10.425	8.704	0.225	1.496	1.2 DIA	2	B125
S5	10.700	9.635	0.100	0.965	0.45 DIA	3	A15
S6	10.634	9.294	0.150	1.190	0.45 DIA	3	A15
S7	10.720	9.878	0.100	0.742	0.45 DIA	3	A15
S8 (*) (MA)	10.000	7.070	0.225	2.705	1.2 DIA	B	B125
S9	10.700	9.340	0.150	1.210	0.45 DIA	3	A15
S10	10.700	9.192	0.150	1.358	0.45 DIA	3	A15
S11	10.645	8.849	0.225	1.571	0.60 DIA	3	B125
S12	10.610	8.779	0.225	1.606	0.60 DIA	3	A15
S13	10.550	8.720	0.225	1.605	0.60 DIA	3	A15
S14	10.600	8.661	0.225	1.714	0.60 DIA	3	B125
S15 (**) (MA)	10.000	7.070	0.225	2.705	1.2 DIA	B	B125
S16 (ST)	10.440	8.469	0.225	1.746	1.2 DIA	2	B125
S17	10.520	9.690	0.100	0.730	0.45 DIA	3	A15
S18 (ST) (MA)	10.520	9.579	0.150	0.791	0.45 DIA	3	A15
S19 (ST)	10.520	9.600	0.100	0.820	0.45 DIA	3	A15
S20 (ST)	10.670	9.600	0.100	0.970	0.45 DIA	3	A15
S21 (ST) (MA)	10.670	9.579	0.150	0.941	0.45 DIA	3	A15
S22 (ST) (MA)	10.670	9.620	0.150	0.900	0.45 DIA	3	A15
S23 (ST)	10.670	9.700	0.100	0.870	0.45 DIA	3	A15

SURFACE WATER MANHOLE SCHEDULE							
CHAMBER NUMBER	COVER LEVEL (CL)	INVERT LEVEL (IL)	PIPE DIAMETER (m)	DEPTH TO SOFFIT (m)	SIZE (m)	TYPE	COVER TYPE
S24 (ST) (MA)	10.670	9.620	0.150	0.900	0.45 DIA	3	A15
S25	10.697	9.687	0.100	0.910	0.45 DIA	3	D400
S26 (ST) (MA)	10.670	9.144	0.150	1.376	0.45 DIA	3	A15
S27 (ST)	10.700	9.200	0.100	1.400	0.45 DIA	3	A15
S28 (ST)	10.700	9.200	0.100	1.400	0.45 DIA	3	A15
S29 (MA)	10.700	8.200	0.225	2.275	1.2 DIA	2	B125
S30 (ST)	10.550	9.200	0.100	1.250	0.45 DIA	3	A15
S31 (ST)	10.670	10.070	0.100	0.500	0.25 DIA	4	A15
S32 (ST)	10.520	9.920	0.100	0.500	0.25 DIA	4	A15
S33 (ST)	10.550	9.144	0.150	1.256	0.45 DIA	3	A15
S38	10.464	9.885	0.150	0.429	0.45 DIA	3	D400
S39	10.560	9.885	0.150	0.525	0.45 DIA	3	D400
S40	10.440	9.885	0.150	0.405	0.45 DIA	3	D400

HATCHED AREAS REFER TO CHAMBERS/MANHOLES THAT ARE ALREADY INSTALLED
(ST) - CHAMBER TO INCORPORATE SILT TRAP
(MA) - CHAMBER TO ALLOW ACCESS FOR INTERNAL MAINTENANCE OF THE ADJACENT FEATURE
(*) - S8-1, S8-2 AND S8-3 TO BE OF THE SAME TYPE AND HAVE THE SAME IL
(**) - S15-1, S15-2 AND S15-3 TO BE OF THE SAME TYPE AND HAVE THE SAME IL

NOTES:
1. FOR DRAINAGE LAYOUT REFER TO DRAWINGS 21-254-701, 21-254-702 AND 21-254-703.

B	MANHOLES 8 AND 15 UPDATED	AK	BO	BAC	05.03.26
A	NEW CHAMBERS/MANHOLE ADDED. SCHEDULE UPDATED WITH INSTALLED INFORMATION	AK	BO	BAC	16.07.25
Rev	Amendments	Drn	Chk	App	Date
Scale NTS @A3		Date DEC 2022		Designed AK	
Drawn AK		Checked SW		Approved SW	
Job No 21-254		Drawing No 21-254-304			Rev B



Unit 1 Pucknall Farm
Dores Lane
Romsey
Hampshire SO51 0QJ

Telephone: 01794 537980
E: info@odysseyconsult.co.uk
W: www.odysseyconsult.co.uk

ODYSSEY

Job Title	FORMER SHRUBLANDS NURSERY ROUNDSTONE LANE, ANGMERING
Drawing Title	MANHOLE SCHEDULE SURFACE WATER

Client	SIGMA HOMES
--------	-------------