

**WEST SUSSEX COUNTY COUNCIL
FLOOD RISK MANAGEMENT CONSULTATION**

DATE: 10th May 2018

FROM: Kevin Brook

**TO: Arun District Council
FAO: Ross Leal**

PLANNING REFERENCE: A/51/18/PL

LOCATION: Pound Place, Roundstone Lane, Angmering, BN16 4AL

RECOMMENDATION:

Advice	☒	Modification	☐	More Information	☐
Objection	☐	No Objection	☒	Refusal	☐

West Sussex County Council (WSSCC), in its capacity as the Lead Local Flood Authority (LLFA), has been consulted on the above proposed development in respect of surface water drainage.

The following is the detailed comments of the LLFA relating to surface water drainage and flood risk for the proposed development and any associated observations and advice.

Current surface water flood risk based on uFMfSW:	Moderate risk
Comments: Current uFMfSW mapping shows the majority of the site is at a low risk from surface water flooding. Some higher risk exists in the north east corner of the site and on Roundstone Lane adjacent to the site. Any existing surface water flow paths across the site must be maintained. Reason: NPPF paragraph 103 states – ‘When determining planning applications, local planning authorities should ensure flood risk is not increased elsewhere..’ Therefore, a wholesale site level rise via the spreading of excavated material should be avoided. Any excavated material kept on site should be located in areas designed and designated for that purpose.	

Modelled groundwater flood hazard classification:	High risk
Comments: The proposed development site is shown to be at high risk from groundwater flooding. This risk and appropriate mitigation should be considered in any future designs especially with regard to underground structures and utilities. Ground water contamination and Source Protection Zones. The potential for ground water contamination within a source protection zone has not been considered by the LLFA. The LPA should consult with the EA if this is considered as risk.	

Records of any ordinary/culverted watercourses within or in close vicinity to the site:	No
Comments: Current Ordnance Survey mapping shows no ordinary watercourses within or in close proximity of the site boundary. Local or field boundary ditches, not shown on Ordnance Survey mapping, may exist around the site. If present these should be maintained and highlighted on future plans.	

Records of any historic flooding within the site or within close proximity of the site:	No
Comments: We do not have any records of historic surface water flooding either within the confines of the proposed site or in the immediate vicinity. This should not be taken that this site itself has never suffered from flooding, only that it has never been reported to the LLFA.	

Future development - Sustainable Drainage Systems (SuDs)

The Drainage Design Strategy Report included with this application proposes that permeable paving and infiltration will be used to control the runoff from the development. This method would, in principle, meet the requirements of the NPPF, PPG and associated guidance documents.

Development should not commence until finalised detailed surface water drainage designs and calculations for the site, based on sustainable drainage principles, for the development have been submitted to and approved in writing by the Local Planning Authority. The drainage designs should demonstrate that the surface water runoff generated up to and including the 1 in 100 year, plus climate change, critical storm will not exceed the run-off from the current site following the corresponding rainfall event.

Development shall not commence until full details of the maintenance and management of the SUDs system is set out in a site-specific maintenance manual and submitted to, and approved in writing, by the Local Planning Authority. The scheme shall subsequently be implemented in accordance with the approved designs.

Please note that Schedule 3 of the Flood and Water Management Act 2010 has not yet been implemented and WSCC does not currently expect to act as the SuDS Approval Body (SAB) in this matter.

Kevin Brook
Flood Risk Management Team