

DRAINAGE DESIGN CALCULATIONS

POUND PLACE, ANGMERING

SAVISTA DESIGN AND BUILD

OCTOBER 2019

1612-ISS-XX-XX-RP-C-0001

ISSUES STRUCTURES

LONDON

20 IRONMONGER LANE
LONDON
EC2V 8EP




BRISTOL

85-95 REDCLIFF STREET
BRISTOL
BS1 6LU



MANCHESTER

COMMERCIAL WHARF
5 COMMERCIAL STREET
MANCHESTER
M15 4PZ



DRAINAGE DESIGN CALCULATIONS

1612-ISS-XX-XX-RP-C-0001

REPORT ISSUE

Revision	Date	Notes
P01	31/10/2019	First Issue
P02	22/11/2019	Second Issue Following Planner's Comments
P03	05/02/2020	Updated following additional Infiltration Testing in East Area of Site
P04	10/03/2020	Calculations and drawings in the appendices amended to suit LLFA comments
P05	22/04/2020	Site plan amended to 64bed scheme, calculations amended to suit

PREPARED BY


Paul Lavery October 2019

REVIEWED BY

Tom Wilson October 2019

DISCLAIMER

This report has been prepared by Iesis Structures for the sole use of the client. It may not be assigned to, relied upon or used by any third party in part or in whole without the written permission of Iesis Structures.



LONDON • BRISTOL • MANCHESTER

IESISGROUP

Iesis Special Structures Limited is registered in England and Wales
Registered Address: 20 Ironmonger Lane, London, EC2V 8EP Company Number: 07301412

CONTENTS

1	SUMMARY SHEET	1
2	APPROVED STRATEGY	2
3	DESIGN STATEMENT	3
4	DESIGN PROCEDURE	4
APPENDIX A		
APPENDIX B		
APPENDIX C		
APPENDIX D		
APPENDIX E		

1 SUMMARY SHEET

Design Codes	Sewers for Adoption (latest Edition) BRegs Document 'H' BS 752:2017 Drain and Sewer Systems outside of buildings	
Intended Use of Structure	Care home	
FRA or DSR	Drainage Design Strategy Report (DDSR) by Arc Engineers Site Investigation report by Ashdown Site Investigation limited Key pages extracted Site Investigation report by Ashdown Site Investigation limited	Ref – 18 031 Ref: R18-12844 (dated April 18) Refer to Arc Engineers drainage plan for soakaway locations and tables for infiltration rates for west area of site Ref: R14051 (dated 31/01/20)
Surface Water Modelling	Site modelled using Causeway Program Flow 1yr – no surcharging of sewers – criteria met (only pipes connecting to attenuation cells surcharge) 30yr – sewers surcharge but no flooding - criteria met 100yr + CC – flooding in controlled areas and non-excessive depths – criteria met (0.029m ³ located to the south east corner in the soft landscaping area) Causeway Program Flow output for the 4 networks draining to separate soakaways provided (ref SE1612-ISS-XX-XX-CA-C-0051 to 0054)	
Foul Water Flows	Flow rates for main runs calculated using unit discharge method. Refer to calculation sheet ref SE1612-ISS-XX-XX-CA-C-0002 for flow calculations. Causeway Program Flow printout ref SE1612-ISS-XX-XX-CA-C-0050.	
Any Other Relevant Information		

2 APPROVED STRATEGY

The Drainage Design Strategy Report (DDSR) set out the general strategy for the site to which this design has followed.

Surface water is to discharge to ground in multiple locations across the site by means of cellular storage soakaways. Permeable paving is to be used in the parking bays to provide water quality assurances before discharging to the soakaways.

Extracts of the DDSR can be found in Appendix A that shows the location and the resulting infiltration testing for 3 trial pits.

Foul water is to drain to the public sewer network via a new connection being offered for adoption by Southern Water in Roundstone Lane.

Ground water monitoring was not carried out as part of the original site investigation, however, ground water monitoring was undertaken as part of the development to the south of the site, and carried out between October 2011 to November 2012, i.e. during the winter period, and recorded the ground water levels to be below 4mbgl. An extract of the site investigation for this development (ref. Former Nursery Adjacent to Roundstone Lane, Angmering, West Sussex) is provided in Appendix A.

Additional infiltration testing was requested by Arun District Council in the location of the proposed soakaways to the east of the site.

3 DESIGN STATEMENT

The care home is to consist of standard domestic showers, sinks, toilet facilities and a canteen kitchen. Foul flows are to gravitate to the west via private sewers, with final discharge to the existing sewer in Roundstone Lane, which was installed as part of the nearby recent development. The sewer in Roundstone Lane installed as part of the adjacent development has been adopted by Southern Water, who have consented to connection to the sewer under a S106 application. A new sewer will be laid between the site entrance and the existing sewer, to the south in Roundstone Lane.

Surface water flows will infiltrate to the ground using cellular storage crates and have been sized to infiltrate through the sides only in accordance with the Arun District Council guidance. Infiltration rates are provided in the site investigation reports by Ashdown and can be found in Appendix B.

Additional infiltration testing was requested by Arun District Council in the location of the proposed soakaways to the east of the site, which was undertaken during January 2020. The report and infiltration rates can be found in Appendix B.

All drainage is to be designed to Sewers For Adoption (7th Edition) and Approved Document H where applicable.

4 DESIGN PROCEDURE

Causeway Program Flow has been used to model the surface water using the infiltration rates as per the DDSR with a dummy manhole downstream of the soakaway with a weir looping any discharge back to the soakaway. The results show that all storm water is contained and infiltrated by the soakaway with the half drain time stated in the details for the individual units

Below ground drainage design results in the following;

- ✧ 1yr Storm event – Pipes do not surcharge except the pipes connecting to the cellular storage, but this does not result in above ground flooding.
- ✧ 10yr storm event – The water level in the soakaway is not higher than the incoming pipes
- ✧ 30yr event – The proposed networks do not flood.
- ✧ 100yr event + 40% CC – There is no flooding for any of the networks.

Causeway Program Flow has been used to model the foul water network using base flows to represent the combined flows calculated using the unit discharge method. Southern Water advised to the Client that they prefer the site to drain to their network to the west, rather than to the east. An application to connect the site to the public sewer has been submitted and approved by Southern Water. A new sewer from the site entrance to the existing sewer within Roundstone Lane is to be offered for adoption under a S104 agreement.

Surface water drainage has been designed in accordance with the Arun District Council checklist titled '*Surface Water Drainage Proposal Checklist2*', which has been completed and provided in Appendix C.

Calculations including Causeway Program Flow reports can be found in Appendix D. The Iesis drainage strategy, drainage construction details, impermeable area plans can be found in Appendix E. The detailed drainage plan has followed the principles of the DDSR with the appropriate amendments as the designs by the other disciplines have been detailed and refined.

APPENDIX A

APPENDIX B

APPENDIX C

APPENDIX D

APPENDIX E