



FIRE STRATEGY LEGEND:

Phoenix 2 Duo (P2-15W with Elite 6x4 chassis)

Overall Length	11.200m
Overall Width	2.530m
Min Body Ground Clearance	3.751m
Track Width	0.304m
Lock to lock time	2.500m
Kerb to Kerb Turning Radius	4.00s
	9.500m

Length of access route for a pump appliance to furthest point of house. (max 45m)

Reversing distance for Fire Tender Vehicle (max 20m)

REFUSE STRATEGY:

Private Refuse storage for houses is generally located in rear gardens, and moved by residents on collection day, to kerbside (on curtilage) or communal refuse collection points.

Private Refuse collection is from within the property boundary, adjacent to the highway or from communal refuse collection points.

Private refuse storage locations, generally in rear gardens. Moved on collection day by resident.

Kerbside refuse collection points for individual houses.

Communal refuse collection points for multiple houses.

Location of Communal refuse collection points for multiple houses / Bin Store.

'Residents' wheeled distance from garden gate to Refuse Collection Point

Operative travel distance from refuse collection point or communal bin store to carriageway (max. 15m).

Travel Distances

Operatives	generally 15m, maximum 25m
Residents	Carry / wheeled maximum 30m

0 25m
Scale 1:500

-	-	-
-	-	-
-	-	-
Rev		Date

PERSIMMON
Together, we make a home

Persimmon Homes Thames Valley
Persimmon House, Knoll Road,
Camberley, Surrey GU15 3TQ
Tel: 01276 808080

Site:	Date:
Dapper's Lane	Nov 2019
Angmering	Scale:
Littlehampton	1:500 @A1
	Org No:
	A77-PL-09

Drawing Title:
Refuse and Fire Strategy Plan

Drawing Status:	Drawn by:	Checked by:
SUBMITTED	VW	ME
	Rev:	-