dwg 16

dwg 18

Plant schedule 18

Trees

Number	Species	Height	Girth	Specification	Density
2 No.	Magnolia x loe. Leonard Messel	200-250cm		C	Counted
5 No.	Sorbus aucuparia	400-450cm	14-16cm	Extra Heavy Standard ,Clear Stem min. 200 /RB	Counted
4 No.	Tilia euchlora	400-450cm	14-16cm	Extra Heavy Standard ,Clear Stem min. 200 /RB	Counted

Shrubs

Number	Species	Height	Pot Size	Specification	Density
25 No.	Hydrangea macrophylla 'Altona'	40-60cm	3L	Branched	4/m²
8 No.	Cotoneaster franchetii	40-60cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset
18 No.	Ligustrum vulgare	60-80cm	3L	Branched	0.5Ctr Double Staggered at 0.5m offset
14 No.	Pittosporum tenuifolium 'Tom Thumb'	40-60cm	3L	Bushy	4/m²
19 No.	Euonymus fortunei 'Emerald n' Gold'	30-40cm	3L	Bushy	4/m²
7 No.	Choisya ternata 'Sundance'	40-60cm	3L	Bushy	4/m²
4 No.	Pieris japonica 'Debutante'	40-60cm	3L	Bushy	4/m²
29 No.	Lonicera nitida	40-60cm	3L	Bushy	4/m²
12 No.	Lonicera nitida 'Baggesen's Gold'	40-60cm	3L	Bushy	4/m²
107 No.	Ilex crenata	40-60cm	3L	Leader With Laterals	0.5Ctr Double Staggered at 0.5m offset
55 No.	Ilex altaclarensis 'Golden King'	40-60cm	3L	Leader With Laterals	0.5Ctr Double Staggered at 0.5m offset
9 No.	Philadelphus 'Manteau d'Hermine'	40-60cm	3L	Bushy	4/m²
34 No.	Euonymus fortunei 'Emerald Gaiety'	30-40cm	3L	Bushy	4/m²
10 No.	Syringa meyeri 'Palibin'	40-60cm	3L	Bushy	4/m²
17 No.	Choisya 'Aztec Pearl'	40-60cm	3L	Bushy	4/m²
105 No.	Ligustrum ovalifolium	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset
24 No.	Daphne odora rubra	40-60cm	3L	Branched	4/m²
18 No.	Prunus laurocerasus 'Otto Luyken'	40-60cm	3L	Bushy	4/m²
18 No.	Deutzia elegantissima 'Rosealind'	40-60cm	3L	Branched	4/m²
22 No.	Skimmia japonica 'Kew White'	40-60cm	3L	Bushy	4/m²
22 No.	Hebe 'Midsummer Beauty'	40-60cm	3L	Bushy	4/m²
11 No.	Spiraea japonica 'Goldflame'	30-40cm	3L	Bushy	4/m²
13 No.	Cistus corbariensis	40-60cm	3L	Bushy	4/m²
9 No.	Olearia haastii	40-60cm	3L	Bushy	4/m²

Herbaceous

Number	Species	Height	Pot Size	Specification	Density
3 No.	Bergenia 'Bressingham Ruby'		3L	Full Pot	6/m²
13 No.	Helleborus niger		3L	Full Pot	6/m²
7 No.	Helleborus orientalis		3L	Full Pot	6/m²
11 No.	Miscanthus sinensis 'Gracilimus'		3L		4/m²

Conifers

Number	Species	Height	Pot Size	Specification	Density
273 No.	Taxus baccata	80-100cm		Leaders: RB	0.5Ctr Double Staggered at 0.5m offset

Bulbs

Number	Species	Specification	Density
74 No.	Crocus chrysanthus 'Blue Pearl'	topsize	25/m²
220 No.	Crocus chrysanthus 'Snow Bunting'	topsize	25/m²
218 No.	Galanthus nivalis	topsize ; to be in the green when planted	25/m²
146 No.	Hyacinthoides non scripta	9+ topsize	25/m²
351 No.	Narcissus pseudonarcissus	topsize	25/m²

Tree Planting Pit Detail within Soft Landscape

All components as sup-plied from Green Leaf or s imilar and approved

SPECIFICATION

Forestry Commission Practice note 88.

All native species should be of local stock. Native trees and shrubs certified as British Native plant stock.

All planting stock should comply with the Horticultural Trade Association National Plant specification.

All planting preparation, handling, planting & maintenance should be in accordance with CPSE Code for Handling and Establishing plants.

All trees and shrubs to comply with BS 3936 Part 1 1992, planted to BS 4043:1989 and BS 4428:1989.

All works generally, to comply with the written Soft Landscape Specification.

Topsoil incorporated into planting beds to be gently mounded towards the centre of each bed to allow for settlement.

On completion of planting the whole area of the shrub bed shall be mulched with 75mm consolidated thickness of medium textured decorative grade natural pine bark having first been prepared in accordance with the specification.

Free standing hedges shall have a 3 strand galvanised wire and tanalised softwood timber post fence, to BS 1722-2:2000, erected along a line between the two rows of hedge plants.

All existing trees and hedges to be protected in accordance with BS5837:2012 for the duration of the construction period.

Legend

- Existing vegetation to be retained
- Existing hedgerow to be trimmed back to 4m width and maintained as a native hedgerow
- Proposed tree planting within soft landscape. See detail on dwg
- Proposed tree planting within hard landscape. See detail on dwg 21-22
- Proposed specimen shrub pl anting
- Proposed climbing plants to be trained up adjacent wall/ fence/pergola with galvanised wires and hook set 250mm apart with support canes removed prior to planting
- Proposed hedge planting to be planted in a double staggered row 500mm apart and at 500mm centres in each row and maintained at 1m height
- Proposed shrub planting
- Proposed shrub planting to be maintained as a clipped rectangular form at 50cm height
- Proposed bulb planting
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Proposed wildflower grassland to be seeded with a combination of WFG18 Butterfly and Honey Bee and WFG7 Free Draining Soils wildflower seed mix as supplied by BSH. Shaded areas to be seeded with WFG8 wildflower seed mix by BSH or similar and appro ved.
- Cut lines
- Site Boundary

Rev	Date	Details	Drawn
A	24.07.12	Ecologist comments	DKM

ACD

Ecology
Arboriculture
Landscape Architecture

ACD Landscape Architects & ACD Ecology
Rodbourne Rail Business Centre, Grange Lane, Malmesbury, Wilts, SN16 0ES
Tel: 01666 825646 Fax: 01666 824654

ACD Arboriculture
Tanners, Lower Street, Haslemere, Surrey, GU27 2PE
Tel: 01483 425714 Fax: 01428 641090

ACD (Landscape Architects) Southampton
12 Southgate Street, Winchester, Hampshire, SO23 9EF
Tel: 01962 855604

www.acdlandscape.co.uk

Space to live
David Wilson Homes

scheme: Roundstone Lane Angmering
client: Barratt David Wilson
drawing: Soft Landscape Proposals
date: July 2012
scale: 1:200@A1
drawing no: BSH 17576 18A
drawn: DKM checked: AW

Copyright of ACD Landscape Architects Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted: 2012:. Copyright of this plan remains with ACD until all fees have been paid in full.