



West Sussex County Council
Development Standard for Highway Lighting

Residential Roads BS5489-1:2003 Class S4 - S6

- Lighting columns** - 6m straight shaft (no outreach bracket). Coating Amercoat 71PPSX 700 polysiloxane and Amercoat 4560 GF epoxy glass flake root protection. Colour as specified by the Authority (Stanton)

- Lanterns (Part Night dimmed)** - WRTL 'Libra Performer' with 24/36/55W PLL lamp, dimming ballast HF-R 1-10volt with Dynadimmer set midnight to 5:30 40%, or or WRTL 'Arc 80' with 60W Cosmopolis lamp dimming ballast Lumastep set midnight to 5:30 40% dim post-top mounted, max tilt 5 degrees

- Switch controls** - 35/18 Zodion SS12

- Lanterns (Part Night switched)** - WRTL 'Libra Performer' with 24/36/55W PLL lamp, ballast HF-R or WRTL 'Arc 80' with 45/60W Cosmopolis lamp electronic ballast 'post-top mounted, max tilt 5 degrees

- Switch controls** - 35/18 Zodion SS19 set midnight to 5:30

PRELIMINARY FOR PLANNING ONLY			INITIALS
REV. NO.	DATE	DESCRIPTION	
Client			
David Wilson Homes			
Project Roundstone Lane			
Angmering			
Title			
Proposed street light layout			
MJA CONSULTING			
CIVIL AND STRUCTURAL ENGINEERS			
16-22 Oak Street, Angmering			
Tel: 01235 555173			
Fax: 01235 523226			
Drawing No.			
4528.P501			
Date			
July 12			
Scale			
1:500 @ A0			
Overhead			
Rev			
KTG			