



West Sussex County Council

Development Standard for Highway Lighting

Residential Roads BS5489-1:2003 Class S4 - S6

Lighting columns - 6m straight shaft (no outreach bracket), Coating Amercoat 71P/PSX 700 polysiloxane and Amercoat 4560 GF epoxy glass flake root protection. Colour as specified by the Authority (Stainton)

Lanterns
(Part Night dimmed) - WRTL 'Libra Performer' with 24/36/55W PLL lamp, dimming ballast HF-R 1-10volt with Dynadimmer set midnight to 5:30 40%, or or WRTL 'Arc 80' with 60W Cosmopolis lamp dimming ballast Lumastep set midnight to 5:30 40% dim post-top mounted, max tilt 5 degrees

Switch controls - 35/18 Zodion SS12

Lanterns
(Part Night switched) - WRTL 'Libra Performer' with 24/36/55W PLL lamp, ballast HF-R or WRTL 'Arc 80' with 45/60W Cosmopolis lamp electronic ballast 'post-top mounted, max tilt 5 degrees

Switch controls - 35/18 Zodion SS19 set midnight to 5:30

PRELIMINARY FOR PLANNING ONLY

REV. No.	A	19.02.14	Planning layout updated	KTG
DATE			DESCRIPTION	INITIALS
Client	David Wilson Homes			
Project	Roundstone Lane Angmering			
Title	Proposed street light layout			
Scale	1:500	Drawn	July 12	Drawing No. 4528:P501
Checked		Drawn	KTG	Rev A

MJA CONSULTING
CIVIL AND STRUCTURAL ENGINEERS
53-62 Oak Street, Abingdon
Oxon. OX14 5BZ
Tel: 01235 555173
Fax: 01235 523226

