




# ROSEMARY CLAY CLASSIC

The Rosemary name is synonymous with quality clay plain tiles. For over 175 years Rosemary has been adding character to British roofs.



Rosemary Clay Classic, Red,  
Mansion House, Shandwick, Troon, Scotland

[WWW.REDLAND.CO.UK/ROSEMARYCLAYCLASSIC](http://WWW.REDLAND.CO.UK/ROSEMARYCLAYCLASSIC)



## ROSEMARY CLAY CLASSIC

Produced from the finest clays, Rosemary is offered in a range of weathered, brindled and single colours.

### KEY ADVANTAGES

- Rosemary brand synonymous with clay plain tiles
- Smooth and sanded finishes
- Mellows naturally with age

### TECHNICAL DATA

|                                                                 |                                                                    |
|-----------------------------------------------------------------|--------------------------------------------------------------------|
| <b>Size</b> (overall)                                           | 265 x 165mm                                                        |
| <b>Minimum Pitch</b>                                            | 35°                                                                |
| <b>Maximum Pitch</b> (subject to fixing specification)          | 90°                                                                |
| <b>Minimum Headlap</b>                                          | Below 90° 65mm / at 90° 35mm                                       |
| <b>Maximum Headlap</b>                                          | 88mm                                                               |
| <b>Minimum Gauge/Batten Spacing</b>                             | 88mm                                                               |
| <b>Maximum Gauge/Batten Spacing</b>                             | below 90° 100mm / at 90° 115mm                                     |
| <b>Hanging Length</b> (approx.)                                 | 255mm                                                              |
| <b>Cover</b> (all figures are net and do not allow for wastage) |                                                                    |
| Linear cover of 1 tile                                          | 165mm                                                              |
| Covering capacity                                               | below 90° 60 tiles/m <sup>2</sup> / at 90° 52 tiles/m <sup>2</sup> |
| <b>Weight</b>                                                   | below 90° 78kg/m <sup>2</sup> / at 90° 68kg/m <sup>2</sup>         |
| per pallet, including pallet (approx.)                          | 1.11 tonnes                                                        |
| per 1000                                                        | 1.30 tonnes                                                        |
| <b>Battens Required</b> (at max. gauge)                         | below 90° 10.0m/m <sup>2</sup>                                     |
| <b>Batten Size</b>                                              |                                                                    |
| Rafter centres up to 600mm                                      | 38 x 25mm                                                          |
| <b>Nail Size for Tiles*</b>                                     | 40 x 2.65mm (A/A)                                                  |
| <b>Pallet Quantities</b>                                        | Tiles per pallet 840 / Tiles per pack 14 / Packs per pallet 60     |

\* (A/A) Aluminium Alloy

### FITTINGS & ACCESSORIES

|                            |                                                                                                                                                                                                    |
|----------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Ornamental Tile</b>     | Club Tiles                                                                                                                                                                                         |
| <b>Angles</b>              | External Angles<br>Internal Angles                                                                                                                                                                 |
| <b>Hip</b>                 | Universal Bonnet Hip<br>Arris Hips<br>Third Round Hip<br>Baby Ridge<br>Dry Hip<br>Rapid Hip                                                                                                        |
| <b>Valley</b>              | Valley Tiles<br>125 GRP Valley<br>Dry Valley                                                                                                                                                       |
| <b>Ridge</b>               | Half Round Ridge                                                                                                                                                                                   |
| <b>Ventilation Systems</b> | RedVent EavesVent<br>RedVent 25 Over-Fascia Vent<br>Rapid Eaves Vent<br>Top Edge Abutment Ventilation<br>DryVent Ridge<br>Continuous Ridge System<br>Uni-Vent Rapid Ridge/Hip<br>RedLine Vent Tile |

### COLOURS



**80** Red      **81** Light Mixed Brindle      **82** Medium Mixed Brindle      **83** Heather Brindle (Sanded)



**87** Blue Brindle      **91** Burnt Blend (Sanded)      **94** Russet Mix (Sanded)      **95** Dark Antique