



- - - - - EXISTING GROUND PROFILE
 ————— PROPOSED CENTRELINE PROFILE
 ————— PROPOSED FOUL SEWER
 ————— PROPOSED STORM SEWER

**ALL PIPE BEDDING TO BE
CLASS 'S' GRANULAR
SURROUND UNLESS NOTED
OTHERWISE ON THE
DRAWING**

- ## PERMITTED PIPE MATERIALS

CLAYWARE (FOR SEWERS 150mm & 225mm)

All clayware pipes to be vitrified clay to BS EN 295-1:1991 and a minimum crushing strength of 45kN Class 200 for diameters of 225mm. For 150mm diameter pipes a minimum crushing strength of 28kN shall be used.

CONCRETE (FOR SEWERS 300mm AND ABOVE)
All concrete pipes are to be pipe strength Class 120 to BS 5911-1:2004 unless indicated otherwise on the drawings.

B	03.21	RD01, RD05, RD05TH, RD06, RD07, RD09, RD09TH updated	DS	SL
A	12.20	First issue	SM	SL
Rev	Date	Description	Drawn	Checked



3 Tealgate, Charnham Park
Hungerford, Berkshire RG17 0YT
www.alpce.co.uk Tel: 01488 684390

Client
**BARRATT DAVID
WILSON HOMES**

Project

WATER LANE, ANGMERING

Title
LONG SECTIONS
SHEET 1

FOR TENDER

Scale 1:500 H @ A1 1:100 V	Date DEC 2020	Drawn SM	Checked SL
Drawing No CIV-1-4011 B			Revision B
A290-111			