

Design Settings

Rainfall Methodology FSR
Return Period (years) 5
Additional Flow (%) 0
FSR Region England and Wales
M5-60 (mm) 19.000
Ratio-R 0.350
CV 0.750
Time of Entry (mins) 5.00
Maximum Time of Concentration (mins) 30.00
Maximum Rainfall (mm/hr) 50.0
Minimum Velocity (m/s) 1.00
Connection Type Level Soffits
Minimum Backdrop Height (m) 9.990
Preferred Cover Depth (m) 1.200
Include Intermediate Ground ✓
Enforce best practice design rules ✓

Nodes

Name	Area (ha)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)
1	0.033	14.650	1200	507319.782	104517.785	1.750

Simulation Settings

Rainfall Methodology	FSR	Analysis Speed	Detailed
FSR Region	England and Wales	Skip Steady State	x
M5-60 (mm)	19.000	Drain Down Time (mins)	240
Ratio-R	0.350	Additional Storage (m³/ha)	20.0
Summer CV	0.750	Check Discharge Rate(s)	x
Winter CV	0.840	Check Discharge Volume	x

Storm Durations

15 | 30

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
10	10	0	0
100	40	0	0

Node 1 Depth/Area Storage Structure

Base Inf Coefficient (m/hr)	0.17485	Porosity	0.95
Side Inf Coefficient (m/hr)	0.17485	Invert Level (m)	12.900
Safety Factor	6.5	Time to half empty (mins)	663

Depth (m)	Area (m²)	Inf Area (m²)	Depth (m)	Area (m²)	Inf Area (m²)	Depth (m)	Area (m²)	Inf Area (m²)	Depth (m)	Area (m²)	Inf Area (m²)
0.000	25.0	25.0	0.400	25.0	35.0	0.800	25.0	35.0	0.801	0.0	35.0

Results for 10 year +10% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
30 minute winter	1	33	13.113	0.213	7.0	5.1506	0.0000	OK
Link Event (Upstream Depth)	US Node	Link	Outflow (l/s)					
30 minute winter	1	Infiltration	0.2					

Results for 100 year +40% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
30 minute winter	1	34	13.365	0.465	14.8	11.2225	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	Outflow (l/s)
30 minute winter	1	Infiltration	0.3