

Regulations Compliance Report

Approved Document L1A, 2013 Edition, England assessed by Stroma FSAP 2012 program, Version: 1.0.4.25

Printed on 04 May 2020 at 15:59:10

Project Information:

Assessed By: Leighton Howe (STRO004042)

Building Type: Detached House

Dwelling Details:

NEW DWELLING DESIGN STAGE

Total Floor Area: 127.68m²

Site Reference : XG-10

Plot Reference: Type D1 - Plot 26

Address : Type D1 Plot 26, Manor Nursery Site, Angmering, RH13 6NU

Client Details:

Name: Roffey Homes

Address :

This report covers items included within the SAP calculations.

It is not a complete report of regulations compliance.

1a TER and DER

Fuel for main heating system: Mains gas

Fuel factor: 1.00 (mains gas)

Target Carbon Dioxide Emission Rate (TER)

16.65 kg/m²

Dwelling Carbon Dioxide Emission Rate (DER)

16.43 kg/m²

OK

1b TFEE and DFEE

Target Fabric Energy Efficiency (TFEE)

57.6 kWh/m²

Dwelling Fabric Energy Efficiency (DFEE)

48.8 kWh/m²

OK

2 Fabric U-values

Element

Average

Highest

External wall

0.20 (max. 0.30)

0.20 (max. 0.70)

OK

Floor

0.11 (max. 0.25)

0.11 (max. 0.70)

OK

Roof

0.11 (max. 0.20)

0.15 (max. 0.35)

OK

Openings

1.40 (max. 2.00)

1.40 (max. 3.30)

OK

2a Thermal bridging

Thermal bridging calculated from linear thermal transmittances for each junction

3 Air permeability

Air permeability at 50 pascals

5.00 (design value)

Maximum

10.0

OK

4 Heating efficiency

Main Heating system:

Boiler systems with radiators or underfloor heating - mains gas

Data from manufacturer

Efficiency 89.2 % SEDBUK2009

Minimum 88.0 %

OK

Secondary heating system:

None

5 Cylinder insulation

Hot water Storage:

Measured cylinder loss: 1.97 kWh/day

Permitted by DBSCG: 2.30 kWh/day

OK

Primary pipework insulated:

Yes

OK

Regulations Compliance Report

6 Controls

Space heating controls	TTZC by plumbing and electrical services	OK
Hot water controls:	Cylinderstat	OK
	Independent timer for DHW	OK
Boiler interlock:	Yes	OK

7 Low energy lights

Percentage of fixed lights with low-energy fittings	100.0%	
Minimum	75.0%	OK

8 Mechanical ventilation

Continuous extract system (decentralised)		
Specific fan power:	0.19 0.24 0.25	
Maximum	0.7	OK

9 Summertime temperature

Overheating risk (South East England):	Slight	OK
--	--------	----

Based on:

Overshading:	Average or unknown
Windows facing: North	6.53m ²
Windows facing: South	4.49m ²
Windows facing: South	6.85m ²
Windows facing: West	2.23m ²
Windows facing: East	1.01m ²
Windows facing: East	3.33m ²
Roof windows facing: Horizontal	2.04m ²
Ventilation rate:	4.00
Blinds/curtains:	None

10 Key features

Thermal bridging	0.035 W/m ² K
Roofs U-value	0.1 W/m ² K
Floors U-value	0.11 W/m ² K

SAP WorkSheet: New dwelling design stage

User Details

Assessor Name: Leighton Howe
Software Name: Stroma FSAP 2012

Stroma Number: STRO004042
Software Version: Version: 1.0.4.25

Property Address: Type D1 - Plot 26

Address : Type D1 Plot 26, Manor Nursery Site, Angmering, RH13 6NU

1. General dwelling dimensions

	Area(m ²)		Av. Height(m)		Volume(m ³)
Ground floor	69.11	(1a) x	2.4	(2a) =	165.86 (3a)
First floor	58.57	(1b) x	2.66	(2b) =	155.97 (3b)
Total floor area TFA = (1a)+(1b)+(1c)+(1d)+(1e)+.....(1n)	127.68	(4)			
Dwelling volume				(3a)+(3b)+(3c)+(3d)+(3e)+.....(3n) =	321.84 (5)

2. Ventilation rate

	main heating		secondary heating		other		total		m ³ per hour
Number of chimneys	0	+	0	+	0	=	0	x 40 =	0 (6a)
Number of open flues	0	+	0	+	0	=	0	x 20 =	0 (6b)
Number of intermittent fans							0	x 10 =	0 (7a)
Number of passive vents							0	x 10 =	0 (7b)
Number of flueless gas fires							0	x 40 =	0 (7c)

Air changes per hour

Infiltration due to chimneys, flues and fans = (6a)+(6b)+(7a)+(7b)+(7c) =	0	÷ (5) =	0 (8)
<i>If a pressurisation test has been carried out or is intended, proceed to (17), otherwise continue from (9) to (16)</i>			
Number of storeys in the dwelling (ns)			0 (9)
Additional infiltration		[(9)-1]x0.1 =	0 (10)
Structural infiltration: 0.25 for steel or timber frame or 0.35 for masonry construction			0 (11)
<i>if both types of wall are present, use the value corresponding to the greater wall area (after deducting areas of openings); if equal user 0.35</i>			
If suspended wooden floor, enter 0.2 (unsealed) or 0.1 (sealed), else enter 0			0 (12)
If no draught lobby, enter 0.05, else enter 0			0 (13)
Percentage of windows and doors draught stripped			0 (14)
Window infiltration	0.25 - {0.2 x (14) ÷ 100} =		0 (15)
Infiltration rate	(8) + (10) + (11) + (12) + (13) + (15) =		0 (16)
Air permeability value, q50, expressed in cubic metres per hour per square metre of envelope area			5 (17)
If based on air permeability value, then (18) = [(17) ÷ 20] + (8), otherwise (18) = (16)			0.25 (18)
<i>Air permeability value applies if a pressurisation test has been done or a degree air permeability is being used</i>			
Number of sides sheltered			1 (19)
Shelter factor	(20) = 1 - {0.075 x (19)} =		0.92 (20)
Infiltration rate incorporating shelter factor	(21) = (18) x (20) =		0.23 (21)
Infiltration rate modified for monthly wind speed			

Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

Monthly average wind speed from Table 7

(22)m=	5.1	5	4.9	4.4	4.3	3.8	3.8	3.7	4	4.3	4.5	4.7
--------	-----	---	-----	-----	-----	-----	-----	-----	---	-----	-----	-----

SAP WorkSheet: New dwelling design stage

Wind Factor (22a)m = (22)m ÷ 4

(22a)m=	1.27	1.25	1.23	1.1	1.08	0.95	0.95	0.92	1	1.08	1.12	1.18
---------	------	------	------	-----	------	------	------	------	---	------	------	------

Adjusted infiltration rate (allowing for shelter and wind speed) = (21a) x (22a)m

	0.29	0.29	0.28	0.25	0.25	0.22	0.22	0.21	0.23	0.25	0.26	0.27
--	------	------	------	------	------	------	------	------	------	------	------	------

Calculate effective air change rate for the applicable case

If mechanical ventilation:

0.5 (23a)

If exhaust air heat pump using Appendix N, (23b) = (23a) × Fmv (equation (N5)) , otherwise (23b) = (23a)

0.5 (23b)

If balanced with heat recovery: efficiency in % allowing for in-use factor (from Table 4h) =

0 (23c)

a) If balanced mechanical ventilation with heat recovery (MVHR) (24a)m = (22b)m + (23b) × [1 – (23c) ÷ 100]

(24a)m=	0	0	0	0	0	0	0	0	0	0	0	0
---------	---	---	---	---	---	---	---	---	---	---	---	---

(24a)

b) If balanced mechanical ventilation without heat recovery (MV) (24b)m = (22b)m + (23b)

(24b)m=	0	0	0	0	0	0	0	0	0	0	0	0
---------	---	---	---	---	---	---	---	---	---	---	---	---

(24b)

c) If whole house extract ventilation or positive input ventilation from outside

if (22b)m < 0.5 × (23b), then (24c) = (23b); otherwise (24c) = (22b) m + 0.5 × (23b)

(24c)m=	0.54	0.54	0.53	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.51	0.52
---------	------	------	------	-----	-----	-----	-----	-----	-----	-----	------	------

(24c)

d) If natural ventilation or whole house positive input ventilation from loft

if (22b)m = 1, then (24d)m = (22b)m otherwise (24d)m = 0.5 + [(22b)m² x 0.5]

(24d)m=	0	0	0	0	0	0	0	0	0	0	0	0
---------	---	---	---	---	---	---	---	---	---	---	---	---

(24d)

Effective air change rate - enter (24a) or (24b) or (24c) or (24d) in box (25)

(25)m=	0.54	0.54	0.53	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.51	0.52
--------	------	------	------	-----	-----	-----	-----	-----	-----	-----	------	------

(25)

3. Thermal losses and heat loss parameter

ELEMENT	Gross area (m²)	Openings m²	Net Area A ,m²	U-value W/m²K	A X U (W/K)	k-value kJ/m²·K	A X k kJ/K
Doors Type 1			1.98	1.4	2.772		(26)
Doors Type 2			1.91	1.4	2.674		(26)
Windows Type 1			6.53	$\times 1/[1/(1.4) + 0.04]$	8.66		(27)
Windows Type 2			4.49	$\times 1/[1/(1.4) + 0.04]$	5.95		(27)
Windows Type 3			6.85	$\times 1/[1/(1.4) + 0.04]$	9.08		(27)
Windows Type 4			2.23	$\times 1/[1/(1.4) + 0.04]$	2.96		(27)
Windows Type 5			1.01	$\times 1/[1/(1.4) + 0.04]$	1.34		(27)
Windows Type 6			3.33	$\times 1/[1/(1.4) + 0.04]$	4.41		(27)
Rooflights			2.04	$\times 1/[1/(1.4) + 0.04]$	2.856		(27b)
Floor			69.11	0.11	7.6021		(28)
Walls	179.89	28.33	151.56	0.2	30.31		(29)
Roof Type1	58.57	0	58.57	0.1	5.86		(30)
Roof Type2	10.65	2.04	8.61	0.15	1.29		(30)
Total area of elements, m²			318.22				(31)
Internal wall **			142				(32c)
Internal floor			37.08				(32d)
Internal ceiling			37.08				(32e)

SAP WorkSheet: New dwelling design stage

* for windows and roof windows, use effective window U-value calculated using formula $1/[(1/U\text{-value})+0.04]$ as given in paragraph 3.2

** include the areas on both sides of internal walls and partitions

Fabric heat loss, W/K = $S (A \times U)$ (26)...(30) + (32) = 85.61 (33)

Heat capacity $C_m = S(A \times k)$ ((28)...(30) + (32) + (32a)...(32e) = 18676.23 (34)

Thermal mass parameter (TMP = $C_m \div TFA$) in kJ/m²K Indicative Value: Medium 250 (35)

For design assessments where the details of the construction are not known precisely the indicative values of TMP in Table 1f can be used instead of a detailed calculation.

Thermal bridges : $S (L \times Y)$ calculated using Appendix K 11.21 (36)

if details of thermal bridging are not known (36) = $0.05 \times (31)$

Total fabric heat loss (33) + (36) = 96.82 (37)

Ventilation heat loss calculated monthly (38)m = $0.33 \times (25)m \times (5)$

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(38)m=	57.87	57.25	56.64	53.57	53.1	53.1	53.1	53.1	53.1	53.1	54.18	55.41	(38)

Heat transfer coefficient, W/K (39)m = (37) + (38)m

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(39)m=	154.69	154.07	153.46	150.39	149.92	149.92	149.92	149.92	149.92	149.92	151	152.23	
Average = $\text{Sum}(39)_{1...12} / 12 =$												151.28	(39)

Heat loss parameter (HLP), W/m²K (40)m = (39)m $\div$ (4)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(40)m=	1.21	1.21	1.2	1.18	1.17	1.17	1.17	1.17	1.17	1.17	1.18	1.19	
Average = $\text{Sum}(40)_{1...12} / 12 =$												1.18	(40)

Number of days in month (Table 1a)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(41)m=	31	28	31	30	31	30	31	31	30	31	30	31	(41)

4. Water heating energy requirement

Assumed occupancy, N 2.89 (42)

if TFA > 13.9, $N = 1 + 1.76 \times [1 - \exp(-0.000349 \times (TFA - 13.9)^2)] + 0.0013 \times (TFA - 13.9)$

if TFA ≤ 13.9, N = 1

Annual average hot water usage in litres per day $V_{d, \text{average}} = (25 \times N) + 36$ 102.81 (43)

Reduce the annual average hot water usage by 5% if the dwelling is designed to achieve a water use target of not more than 125 litres per person per day (all water use, hot and cold)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(44)m=	113.09	108.98	104.86	100.75	96.64	92.53	92.53	96.64	100.75	104.86	108.98	113.09	
Total = $\text{Sum}(44)_{1...12} =$												1233.68	(44)

Energy content of hot water used - calculated monthly = $4.190 \times V_{d,m} \times n_m \times DT_m / 3600$ kWh/month (see Tables 1b, 1c, 1d)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(45)m=	167.71	146.68	151.36	131.96	126.62	109.26	101.25	116.18	117.57	137.01	149.56	162.41	
Total = $\text{Sum}(45)_{1...12} =$												1617.55	(45)

If instantaneous water heating at point of use (no hot water storage), enter 0 in boxes (46) to (61)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(46)m=	25.16	22	22.7	19.79	18.99	16.39	15.19	17.43	17.64	20.55	22.43	24.36	(46)

Water storage loss:

Storage volume (litres) including any solar or WWHRS storage within same vessel 210 (47)

If community heating and no tank in dwelling, enter 110 litres in (47)

Otherwise if no stored hot water (this includes instantaneous combi boilers) enter '0' in (47)

Water storage loss:

a) If manufacturer's declared loss factor is known (kWh/day): 1.97 (48)

Temperature factor from Table 2b 0.54 (49)

SAP WorkSheet: New dwelling design stage

Energy lost from water storage, kWh/year	(48) x (49) =	1.06	(50)										
b) If manufacturer's declared cylinder loss factor is not known:													
Hot water storage loss factor from Table 2 (kWh/litre/day)		0	(51)										
If community heating see section 4.3													
Volume factor from Table 2a		0	(52)										
Temperature factor from Table 2b		0	(53)										
Energy lost from water storage, kWh/year	(47) x (51) x (52) x (53) =	0	(54)										
Enter (50) or (54) in (55)		1.06	(55)										
Water storage loss calculated for each month	((56)m = (55) x (41)m												
(56)m=	32.98	29.79	32.98	31.91	32.98	31.91	32.98	32.98	31.91	32.98	31.91	32.98	(56)
If cylinder contains dedicated solar storage, (57)m = (56)m x [(50) - (H11)] ÷ (50), else (57)m = (56)m where (H11) is from Appendix H													
(57)m=	32.98	29.79	32.98	31.91	32.98	31.91	32.98	32.98	31.91	32.98	31.91	32.98	(57)
Primary circuit loss (annual) from Table 3		0	(58)										
Primary circuit loss calculated for each month (59)m = (58) ÷ 365 x (41)m	(modified by factor from Table H5 if there is solar water heating and a cylinder thermostat)												
(59)m=	23.26	21.01	23.26	22.51	23.26	22.51	23.26	23.26	22.51	23.26	22.51	23.26	(59)
Combi loss calculated for each month (61)m = (60) ÷ 365 x (41)m													
(61)m=	0	0	0	0	0	0	0	0	0	0	0	0	(61)
Total heat required for water heating calculated for each month (62)m = 0.85 x (45)m + (46)m + (57)m + (59)m + (61)m													
(62)m=	223.95	197.47	207.6	186.38	182.86	163.69	157.49	172.42	171.99	193.25	203.99	218.65	(62)
Solar DHW input calculated using Appendix G or Appendix H (negative quantity) (enter '0' if no solar contribution to water heating)													
(add additional lines if FGHRs and/or WWHRs applies, see Appendix G)													
(63)m=	0	0	0	0	0	0	0	0	0	0	0	0	(63)
Output from water heater													
(64)m=	223.95	197.47	207.6	186.38	182.86	163.69	157.49	172.42	171.99	193.25	203.99	218.65	
Output from water heater (annual) $\sum_{i=1}^{12}$												2279.74	(64)
Heat gains from water heating, kWh/month $0.25 \times [0.85 \times (45)m + (61)m] + 0.8 \times [(46)m + (57)m + (59)m]$													
(65)m=	100.75	89.41	95.32	87.42	87.09	79.87	78.66	83.62	82.63	90.55	93.27	98.99	(65)
include (57)m in calculation of (65)m only if cylinder is in the dwelling or hot water is from community heating													

5. Internal gains (see Table 5 and Appendix L)

Metabolic gains (Table 5), Watts	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(66)m=	173.32	173.32	173.32	173.32	173.32	173.32	173.32	173.32	173.32	173.32	173.32	173.32	(66)
Lighting gains (calculated in Appendix L, equation L9 or L9a), also see Table 5													
(67)m=	65.73	58.38	47.48	35.94	26.87	22.68	24.51	31.86	42.76	54.29	63.37	67.55	(67)
Appliances gains (calculated in Appendix L, equation L13 or L13a), also see Table 5													
(68)m=	440.15	444.72	433.21	408.71	377.78	348.71	329.29	324.72	336.23	360.73	391.66	420.73	(68)
Cooking gains (calculated in Appendix L, equation L15 or L15a), also see Table 5													
(69)m=	55.22	55.22	55.22	55.22	55.22	55.22	55.22	55.22	55.22	55.22	55.22	55.22	(69)
Pumps and fans gains (Table 5a)													
(70)m=	3	3	3	3	3	3	3	3	3	3	3	3	(70)
Losses e.g. evaporation (negative values) (Table 5)													
(71)m=	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	-115.55	(71)

SAP WorkSheet: New dwelling design stage

Water heating gains (Table 5)

(72)m=	135.42	133.05	128.12	121.41	117.06	110.93	105.72	112.4	114.77	121.71	129.54	133.06	(72)
--------	--------	--------	--------	--------	--------	--------	--------	-------	--------	--------	--------	--------	------

Total internal gains = (66)m + (67)m + (68)m + (69)m + (70)m + (71)m + (72)m

(73)m=	757.3	752.14	724.8	682.06	637.7	598.31	575.51	584.97	609.75	652.73	700.57	737.34	(73)
--------	-------	--------	-------	--------	-------	--------	--------	--------	--------	--------	--------	--------	------

g. Solar gains

Solar gains are calculated using solar flux from Table 6a and associated equations to convert to the applicable orientation.

Orientation:	Access Factor Table 6d			Area m ²	Flux Table 6a			g_ Table 6b	FF Table 6c			Gains (W)	
North	0.9x	0.77	x	6.53	x	10.63	x	0.63	x	0.7	=	21.22	(74)
North	0.9x	0.77	x	6.53	x	20.32	x	0.63	x	0.7	=	40.55	(74)
North	0.9x	0.77	x	6.53	x	34.53	x	0.63	x	0.7	=	68.91	(74)
North	0.9x	0.77	x	6.53	x	55.46	x	0.63	x	0.7	=	110.69	(74)
North	0.9x	0.77	x	6.53	x	74.72	x	0.63	x	0.7	=	149.11	(74)
North	0.9x	0.77	x	6.53	x	79.99	x	0.63	x	0.7	=	159.62	(74)
North	0.9x	0.77	x	6.53	x	74.68	x	0.63	x	0.7	=	149.03	(74)
North	0.9x	0.77	x	6.53	x	59.25	x	0.63	x	0.7	=	118.24	(74)
North	0.9x	0.77	x	6.53	x	41.52	x	0.63	x	0.7	=	82.85	(74)
North	0.9x	0.77	x	6.53	x	24.19	x	0.63	x	0.7	=	48.27	(74)
North	0.9x	0.77	x	6.53	x	13.12	x	0.63	x	0.7	=	26.18	(74)
North	0.9x	0.77	x	6.53	x	8.86	x	0.63	x	0.7	=	17.69	(74)
East	0.9x	0.77	x	1.01	x	19.64	x	0.63	x	0.7	=	6.06	(76)
East	0.9x	0.77	x	3.33	x	19.64	x	0.63	x	0.7	=	19.99	(76)
East	0.9x	0.77	x	1.01	x	38.42	x	0.63	x	0.7	=	11.86	(76)
East	0.9x	0.77	x	3.33	x	38.42	x	0.63	x	0.7	=	39.1	(76)
East	0.9x	0.77	x	1.01	x	63.27	x	0.63	x	0.7	=	19.53	(76)
East	0.9x	0.77	x	3.33	x	63.27	x	0.63	x	0.7	=	64.39	(76)
East	0.9x	0.77	x	1.01	x	92.28	x	0.63	x	0.7	=	28.48	(76)
East	0.9x	0.77	x	3.33	x	92.28	x	0.63	x	0.7	=	93.91	(76)
East	0.9x	0.77	x	1.01	x	113.09	x	0.63	x	0.7	=	34.91	(76)
East	0.9x	0.77	x	3.33	x	113.09	x	0.63	x	0.7	=	115.09	(76)
East	0.9x	0.77	x	1.01	x	115.77	x	0.63	x	0.7	=	35.73	(76)
East	0.9x	0.77	x	3.33	x	115.77	x	0.63	x	0.7	=	117.82	(76)
East	0.9x	0.77	x	1.01	x	110.22	x	0.63	x	0.7	=	34.02	(76)
East	0.9x	0.77	x	3.33	x	110.22	x	0.63	x	0.7	=	112.17	(76)
East	0.9x	0.77	x	1.01	x	94.68	x	0.63	x	0.7	=	29.22	(76)
East	0.9x	0.77	x	3.33	x	94.68	x	0.63	x	0.7	=	96.35	(76)
East	0.9x	0.77	x	1.01	x	73.59	x	0.63	x	0.7	=	22.71	(76)
East	0.9x	0.77	x	3.33	x	73.59	x	0.63	x	0.7	=	74.89	(76)
East	0.9x	0.77	x	1.01	x	45.59	x	0.63	x	0.7	=	14.07	(76)
East	0.9x	0.77	x	3.33	x	45.59	x	0.63	x	0.7	=	46.4	(76)

SAP WorkSheet: New dwelling design stage

East	0.9x	0.77	x	1.01	x	24.49	x	0.63	x	0.7	=	7.56	(76)
East	0.9x	0.77	x	3.33	x	24.49	x	0.63	x	0.7	=	24.92	(76)
East	0.9x	0.77	x	1.01	x	16.15	x	0.63	x	0.7	=	4.99	(76)
East	0.9x	0.77	x	3.33	x	16.15	x	0.63	x	0.7	=	16.44	(76)
South	0.9x	0.77	x	4.49	x	46.75	x	0.63	x	0.7	=	64.15	(78)
South	0.9x	0.77	x	6.85	x	46.75	x	0.63	x	0.7	=	97.87	(78)
South	0.9x	0.77	x	4.49	x	76.57	x	0.63	x	0.7	=	105.07	(78)
South	0.9x	0.77	x	6.85	x	76.57	x	0.63	x	0.7	=	160.29	(78)
South	0.9x	0.77	x	4.49	x	97.53	x	0.63	x	0.7	=	133.84	(78)
South	0.9x	0.77	x	6.85	x	97.53	x	0.63	x	0.7	=	204.18	(78)
South	0.9x	0.77	x	4.49	x	110.23	x	0.63	x	0.7	=	151.26	(78)
South	0.9x	0.77	x	6.85	x	110.23	x	0.63	x	0.7	=	230.77	(78)
South	0.9x	0.77	x	4.49	x	114.87	x	0.63	x	0.7	=	157.63	(78)
South	0.9x	0.77	x	6.85	x	114.87	x	0.63	x	0.7	=	240.48	(78)
South	0.9x	0.77	x	4.49	x	110.55	x	0.63	x	0.7	=	151.69	(78)
South	0.9x	0.77	x	6.85	x	110.55	x	0.63	x	0.7	=	231.43	(78)
South	0.9x	0.77	x	4.49	x	108.01	x	0.63	x	0.7	=	148.21	(78)
South	0.9x	0.77	x	6.85	x	108.01	x	0.63	x	0.7	=	226.12	(78)
South	0.9x	0.77	x	4.49	x	104.89	x	0.63	x	0.7	=	143.94	(78)
South	0.9x	0.77	x	6.85	x	104.89	x	0.63	x	0.7	=	219.59	(78)
South	0.9x	0.77	x	4.49	x	101.89	x	0.63	x	0.7	=	139.81	(78)
South	0.9x	0.77	x	6.85	x	101.89	x	0.63	x	0.7	=	213.29	(78)
South	0.9x	0.77	x	4.49	x	82.59	x	0.63	x	0.7	=	113.32	(78)
South	0.9x	0.77	x	6.85	x	82.59	x	0.63	x	0.7	=	172.89	(78)
South	0.9x	0.77	x	4.49	x	55.42	x	0.63	x	0.7	=	76.04	(78)
South	0.9x	0.77	x	6.85	x	55.42	x	0.63	x	0.7	=	116.01	(78)
South	0.9x	0.77	x	4.49	x	40.4	x	0.63	x	0.7	=	55.43	(78)
South	0.9x	0.77	x	6.85	x	40.4	x	0.63	x	0.7	=	84.57	(78)
West	0.9x	0.77	x	2.23	x	19.64	x	0.63	x	0.7	=	13.39	(80)
West	0.9x	0.77	x	2.23	x	38.42	x	0.63	x	0.7	=	26.18	(80)
West	0.9x	0.77	x	2.23	x	63.27	x	0.63	x	0.7	=	43.12	(80)
West	0.9x	0.77	x	2.23	x	92.28	x	0.63	x	0.7	=	62.89	(80)
West	0.9x	0.77	x	2.23	x	113.09	x	0.63	x	0.7	=	77.07	(80)
West	0.9x	0.77	x	2.23	x	115.77	x	0.63	x	0.7	=	78.9	(80)
West	0.9x	0.77	x	2.23	x	110.22	x	0.63	x	0.7	=	75.12	(80)
West	0.9x	0.77	x	2.23	x	94.68	x	0.63	x	0.7	=	64.52	(80)
West	0.9x	0.77	x	2.23	x	73.59	x	0.63	x	0.7	=	50.15	(80)
West	0.9x	0.77	x	2.23	x	45.59	x	0.63	x	0.7	=	31.07	(80)
West	0.9x	0.77	x	2.23	x	24.49	x	0.63	x	0.7	=	16.69	(80)
West	0.9x	0.77	x	2.23	x	16.15	x	0.63	x	0.7	=	11.01	(80)
Rooflights	0.9x	1	x	2.04	x	26	x	0.63	x	0.7	=	21.05	(82)

SAP WorkSheet: New dwelling design stage

Rooflights 0.9x	1	x	2.04	x	54	x	0.63	x	0.7	=	43.72	(82)
Rooflights 0.9x	1	x	2.04	x	96	x	0.63	x	0.7	=	77.73	(82)
Rooflights 0.9x	1	x	2.04	x	150	x	0.63	x	0.7	=	121.45	(82)
Rooflights 0.9x	1	x	2.04	x	192	x	0.63	x	0.7	=	155.46	(82)
Rooflights 0.9x	1	x	2.04	x	200	x	0.63	x	0.7	=	161.94	(82)
Rooflights 0.9x	1	x	2.04	x	189	x	0.63	x	0.7	=	153.03	(82)
Rooflights 0.9x	1	x	2.04	x	157	x	0.63	x	0.7	=	127.12	(82)
Rooflights 0.9x	1	x	2.04	x	115	x	0.63	x	0.7	=	93.11	(82)
Rooflights 0.9x	1	x	2.04	x	66	x	0.63	x	0.7	=	53.44	(82)
Rooflights 0.9x	1	x	2.04	x	33	x	0.63	x	0.7	=	26.72	(82)
Rooflights 0.9x	1	x	2.04	x	21	x	0.63	x	0.7	=	17	(82)

Solar gains in watts, calculated for each month

(83)m = Sum(74)m ... (82)m

(83)m=	243.73	426.78	611.7	799.46	929.74	937.13	897.69	798.98	676.82	479.46	294.13	207.13	(83)
--------	--------	--------	-------	--------	--------	--------	--------	--------	--------	--------	--------	--------	------

Total gains – internal and solar (84)m = (73)m + (83)m , watts

(84)m=	1001.03	1178.92	1336.5	1481.52	1567.44	1535.45	1473.2	1383.95	1286.57	1132.19	994.69	944.47	(84)
--------	---------	---------	--------	---------	---------	---------	--------	---------	---------	---------	--------	--------	------

7. Mean internal temperature (heating season)

Temperature during heating periods in the living area from Table 9, Th1 (°C)

21

(85)

Utilisation factor for gains for living area, h1,m (see Table 9a)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	
(86)m=	0.99	0.99	0.96	0.9	0.78	0.6	0.44	0.49	0.73	0.93	0.99	1	(86)

Mean internal temperature in living area T1 (follow steps 3 to 7 in Table 9c)

(87)m=	19.84	20.04	20.32	20.65	20.87	20.97	20.99	20.99	20.93	20.63	20.18	19.82	(87)
--------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	------

Temperature during heating periods in rest of dwelling from Table 9, Th2 (°C)

(88)m=	19.91	19.91	19.92	19.94	19.94	19.94	19.94	19.94	19.94	19.94	19.93	19.93	(88)
--------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	-------	------

Utilisation factor for gains for rest of dwelling, h2,m (see Table 9a)

(89)m=	0.99	0.98	0.95	0.87	0.72	0.51	0.34	0.38	0.64	0.91	0.98	0.99	(89)
--------	------	------	------	------	------	------	------	------	------	------	------	------	------

Mean internal temperature in the rest of dwelling T2 (follow steps 3 to 7 in Table 9c)

(90)m=	18.4	18.68	19.08	19.55	19.83	19.92	19.94	19.94	19.89	19.54	18.9	18.37	(90)
--------	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	------	-------	------

fLA = Living area ÷ (4) =

0.14

(91)

Mean internal temperature (for the whole dwelling) = fLA × T1 + (1 – fLA) × T2

(92)m=	18.6	18.87	19.25	19.7	19.97	20.07	20.09	20.09	20.04	19.69	19.08	18.57	(92)
--------	------	-------	-------	------	-------	-------	-------	-------	-------	-------	-------	-------	------

Apply adjustment to the mean internal temperature from Table 4e, where appropriate

(93)m=	18.45	18.72	19.1	19.55	19.82	19.92	19.94	19.94	19.89	19.54	18.93	18.42	(93)
--------	-------	-------	------	-------	-------	-------	-------	-------	-------	-------	-------	-------	------

8. Space heating requirement

Set Ti to the mean internal temperature obtained at step 11 of Table 9b, so that Ti,m=(76)m and re-calculate the utilisation factor for gains using Table 9a

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
--	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

Utilisation factor for gains, hm:

(94)m=	0.99	0.97	0.94	0.86	0.71	0.51	0.34	0.38	0.64	0.89	0.97	0.99	(94)
--------	------	------	------	------	------	------	------	------	------	------	------	------	------

Useful gains, hmGm , W = (94)m x (84)m

(95)m=	988.4	1147.8	1258.87	1277.32	1117.49	782.46	498.83	527.3	823.06	1011.76	969.12	935.13	(95)
--------	-------	--------	---------	---------	---------	--------	--------	-------	--------	---------	--------	--------	------

Monthly average external temperature from Table 8

(96)m=	4.3	4.9	6.5	8.9	11.7	14.6	16.6	16.4	14.1	10.6	7.1	4.2	(96)
--------	-----	-----	-----	-----	------	------	------	------	------	------	-----	-----	------

SAP WorkSheet: New dwelling design stage

10a Fuel costs - individual heating systems

	Fuel kWh/year	Fuel Price (Table 12)	Fuel Cost £/year
Space heating - main system 1	(211) x	3.48 x 0.01 =	158.86 (240)
Space heating - main system 2	(213) x	0 x 0.01 =	0 (241)
Space heating - secondary	(215) x	13.19 x 0.01 =	0 (242)
Water heating cost (other fuel)	(219)	3.48 x 0.01 =	93.95 (247)
Pumps, fans and electric keep-hot	(231)	13.19 x 0.01 =	24.2 (249)
(if off-peak tariff, list each of (230a) to (230g) separately as applicable and apply fuel price according to Table 12a			
Energy for lighting	(232)	13.19 x 0.01 =	61.24 (250)
Additional standing charges (Table 12)			120 (251)
Appendix Q items: repeat lines (253) and (254) as needed			
Total energy cost	(245)...(247) + (250)...(254) =		458.25 (255)

11a SAP rating - individual heating systems

Energy cost deflator (Table 12)		0.42 (256)
Energy cost factor (ECF)	[(255) x (256)] ÷ [(4) + 45.0] =	1.11 (257)
SAP rating (Section 12)		84.45 (258)

12a CO2 emissions - individual heating systems including micro-CHP

	Energy kWh/year	Emission factor kg CO2/kWh	Emissions kg CO2/year
Space heating (main system 1)	(211) x	0.216 =	986.03 (261)
Space heating (secondary)	(215) x	0.519 =	0 (263)
Water heating	(219) x	0.216 =	583.12 (264)
Space and water heating	(261) + (262) + (263) + (264) =		1569.15 (265)
Electricity for pumps, fans and electric keep-hot	(231) x	0.519 =	95.22 (267)
Electricity for lighting	(232) x	0.519 =	240.97 (268)
Total CO2, kg/year		sum of (265)...(271) =	1905.35 (272)
CO2 emissions per m²		(272) ÷ (4) =	14.92 (273)
EI rating (section 14)			85 (274)

13a Primary Energy

	Energy kWh/year	Primary factor	P. Energy kWh/year
Space heating (main system 1)	(211) x	1.22 =	5569.25 (261)
Space heating (secondary)	(215) x	3.07 =	0 (263)
Energy for water heating	(219) x	1.22 =	3293.56 (264)
Space and water heating	(261) + (262) + (263) + (264) =		8862.81 (265)

SAP WorkSheet: New dwelling design stage

Electricity for pumps, fans and electric keep-hot	{231} x	3.07	=	563.28	{267}
Electricity for lighting	{232} x	0	=	1425.41	{268}
'Total Primary Energy		sum of {265}...{271} =		10851.5	{272}
Primary energy kWh/m²/year		{272} ÷ (4) =		84.99	{273}