Road Sign Schedule (Traffic Signs Regulations and General Directions 2016)			
Drawing Callout	Comment	TSRGD Reference	Notes
RSOS / 01-04	0.6m Diameter	Diagram 616, Schedule 3, Part 3, Item 10	Including 'EXCEPT BUSES AND CYCLES' plate below

ANPR Camera Location Specification:

- ANPR Cameras should be certified by DFT for enforcement purposes and VCA approved.
- ANPR Cameras to be provided by either Videalert, SEA, Siemens or TES and shall be installed in accordance with WSCC 'Bus Gate Enforcement Developer's Pack'
- Location of ANPR Camera facing west towards Dappers Lane.

RSOS/ 03 +04

TWO-WAY BUS LINK

Bus, Emergency Vehicle, Cycle, Pedestrian Access

RSOS/ 01+02

Bus Stop

Notes

1. Any discrepancies should be reported to the architect and/or engineer immediately, so that clarification can be sought prior to the commencement of works.
3. This drawing has been based upon survey information supplied by RK Surveys and Motion cannot guarantee the accuracy of the data provided.
4. This drawing should be read in conjunction with all other relevant architect and engineering details, drawings and specification.

Legend

- Bus Route
- Vehicular Block Paving With Granite Sett Transition Strip To Raised Road Tables

Revision Notes:		Drn	Chk	App	Date
B	Bus Link amended to become 2-way	KL	JH	HM	06/07/2022
A	First Issue	KL	JH	HM	31/03/2022

Drawing Status:

FOR PLANNING
NOT FOR CONSTRUCTION

motion

84 North Street, Guildford, Surrey, GU1 4AU, 01483 531300
9 Greyfriars Road, Reading, Berkshire, RG1 1NU, 0118 206 2930
Golden Cross House, 8 Duncannon Street, London, WC2N 4JF, 020 7031 8141
www.motion.co.uk

Client: CALA HOMES

Project: Land North of Water Lane, Angmering

Title: Condition 39 Bus Route General Arrangement

Scale: 1:500 | Size: A0 | Project No: 2003033

Drawing: 2003033-C39-05-0100 | Revision: B

SCALE IN METRES 1:500

© Crown Copyright. All rights reserved. Licence number 100043605

C:\Users\kirs.hinson\Desktop\Bus Link\2003033\Drawings\0100.dwg - Layout: 2003033\Drawings\0100.dwg - Bus Link\2003033-C39-05-0100 (Condition 39 Bus Route).dwg