

By rba Architects for PMC Construction Limited November 2012

Photo 66 10 External: 1 100 m

drawing number	consultant name	revision
----------------	-----------------	----------

-
- CSH ENE 4 : External 1 - 2 Beds**
Secure drying space with rotary drier to be provided in each garden with minimum of 4mtrs x washing line length with suitable base and post fixing
- CSH WAS 3 : Home Composting**
Dedicated space in the kitchen for a 7 litre waste container and for an accessible external composteur within 30m of the front door. The home shall be provided with an information leaflet.
- CSH WAS 3 : Home Composting**
Dedicated space in the kitchen for a 7 litre waste container and for an accessible external composteur within 30m of the front door. The home shall be provided with an information leaflet.
- CSH ENE 8 : 2 - 3 Bed with Shed (2 Credit)**
Internal secure cycle storage for 2no. bicycles per dwelling within 2.0 x 2.0m timber garden store with 44mm door, 5 lever mortice lock. 1 No. Sheffield cycle hoop for 2no. bicycles internally for secure cycle storage and 1sqm for storage of garden tools
- Tarmac to parking areas and access road to Structural Engineers Specification
- Tarmac to paving areas at the front of the properties and around the parking court to Structural Engineers Specification
- 450 x 450mm paving slabs to private patios and garden paths
- Grass

PLAYING FIELD

Rev C4. Final Issue	22.09.2014	APY	PJB
Rev C3. Dropped Kerbs Added	14.05.2014	SC	APY
Rev C2. External areas added to schedule	02.05.2013	SC	APY
Rev C1. Issued for Construction	25.02.2013	SC	APY
Rev D1. Building Control Issue revisions	19.11.2012	SC author date	APY author QA level b QA level b

t: 07809 432 992
e: mail@rba-uk.eu
w: www.rba-uk.eu

project

Residential Development of the former
Family Tree Public House _____
North Bersted
West Sussex

drawing
Site Layout Plan

scale	date	author QA level a	author QA level b
1 : 100	@ A1 November 2012	SC	APY
job no	drawing no	rev	
1219	3.100	C4	

Revision Codes : P=Preliminary D=Design Stage T=Tender Issue C=Construction Issue