**Proposed Single - Species Ornamental Hedgerow**
14 no. *Pittosporum tenuifolium* 'Silver Queen'; 10ltr CG
Total lenght of hedge: 2.8m
Hedging Stock: 60-90cm height
Hedging to be 2 no. staggered rows 400mm apart @400mm centres.

**Proposed Single - Species Ornamental Hedgerow**
14 no. *Pittosporum tenuifolium* 'Silver Queen'; 10ltr CG
Total lenght of hedge: 2.8m
Hedging Stock: 60-90cm height
Hedging to be 2 no. staggered rows 400mm apart @400mm centres.
1 no. *Phormium* 'Maori Queen'; 7.5ltr CG.
3 no. *Escallonia* Golden Carpet = 'Alcaura'; 3ltr CG.
3 no. *Hebe pinguifolia 'Pagei'*; 2ltr CG; 4p/m$^2$.
9 no. *Heuchera* 'Green Spice'; 2ltr CG.
1 no. *Edgeworthia chrysantha*; 3ltr CG.
3 no. *Chasmanthium latifolium*; 3ltr CG, 4p/m$^2$.
3 no. *Vinca major* 'Variegata'; 2ltr CG; 4p/m$^2$.
9 no. *Persicaria affinis* 'Superba'; 2ltr CG.

9 no. *Heuchera* 'Chocolate Ruffles'; 2ltr CG.
3 no. *Nandina domestica*; 3ltr CG.
3 no. Bergenia *'Bressingham White'*; 2ltr CG, 4p/m$^2$.
3 no. *Luzula sylvatica*; 3ltr CG.

**Proposed Single - Species Ornamental Hedgerow**
41 no. *Pittosporum tenuifolium* 'Silver Queen'; 10ltr CG
Total lenght of hedge: 8.2m
Hedging Stock: 60-90cm height
Hedging to be 2 no. of staggered rows 400mm apart @400mm centres.

**Proposed Single - Species Ornamental Hedgerow**
16 no. *Elaeagnus* × *submacrophylla*; 10ltr CG
Total lenght of hedge: 3.3m
Hedging Stock: 80-100cm height
Hedging to be 2 no. staggered rows 300 and 400mm apart @400mm centres.

**Proposed Single - Species Ornamental Hedgerow**
11 no. *Rosmarinus officinalis* 'Miss Jessopp's Upright'; 3ltr CG
Total lenght of hedge: 3.1m
Hedging Stock: 30-40cm height
Hedging to be 2 no. of staggered rows 300mm apart @400mm centres.

**Proposed Single - Species Ornamental Hedgerow**
11 no. *Rosmarinus officinalis* 'Miss Jessopp's Upright'; 3ltr CG
Total lenght of hedge: 3.1m
Hedging Stock: 30-40cm height
Hedging to be 2 no. of staggered rows 300mm apart @400mm centres.

**Proposed Single - Species Ornamental Hedgerow**
80 no. *Euonymus fortunei* 'Emerald 'n' Gold'; 5ltr CG
Total lenght of hedge: 16m
Hedging Stock: 30-40cm height
Hedging to be 1 row @400mm centres.

5 no. *Viburnum* × *juddii*; 5ltr CG
3 no. *Pulmonaria* 'Diana Clare'; 2ltr CG; 4p/m$^2$.
9 no. *Heuchera* 'Berry Smoothie'; 2ltr CG.
4 no. *Liriope muscari*; 2ltr CG; 4p/m$^2$.
3 no. *Luzula sylvatica*; 3ltr CG.
3 no. *Sarcococca ruscifolia*; 3ltr CG
3 no. *Carex* 'Ice Dance'; 2ltr CG; 4p/m$^2$.
6 no. *Pulmonaria rubra*; 2ltr CG.
6 no. *Pachysandra terminalis* 'Variegata'; 2ltr CG; 4p/m$^2$.
2 no. *Calamagrostis brachytricha*; 3ltr CG.
4 no. *Ajuga reptans* 'Atropurpurea'; 2ltr CG; 4p/m$^2$.
o. *Escallonia laevis* Pink Elle = 'Lades' ; 3ltr CG.

N
0 0.5 1 2 m
Scale 1:50

# Detailed Planting Plan 4 of 7
# The Cottage, Shripney Road, Bognor Regis, West Sussex

## Legend

- **Proposed - Planting Areas**
- **Proposed - Ornamental Shrub/ Grasses Planting**
- **Proposed - Herbaceous Planting**
- **Proposed - Ornamental Hedge**

***Soil Specification***

1. *All Imported Topsoil: to be Multi-Purpose Topsoil to BS 3882: 2015. Topsoil to be tested and certified by a Soil Scientist;*
2. *Existing stripped topsoil (stored and re used): to be screened / cultivated to accord with BS 3882: 2015; tested and certified by a Soil Scientist.*

**Proposed Ornamental Planting / Hedge Planting**
All proposed Ornamental Planting / Hedge Planting / Native Understory Shrub planting areas to be 300mm depth subsoil overlain with a of 300mm depth of topsoil tested and certified to achieve *BS 3882: 2015*. Topsoil to be tested and certified by a Soil Scientist.

***Mulching***
All proposed planting areas to be overlain with 75mm depth Ornamental Bark Mulch. Planting areas to be mulched with fine graded ornamental bark mulch; 5 - 35mm nominal particle size; *BS4970:1987*.

**Notes:**
1. Dimensions shall not be scaled. All dimensions to be checked on site.
2. Drawing is to be read in conjunction with all relevant Landscape Architect's drawings and specification.
3. For Hard and Soft Landscape General Arrangement refer to *LLD1851-LAN-DWG-100.*
4. For detailed soft landscape scheme proposals refer to *LLD-LAN-DWG-200 series - Detailed Planting Plan; LLD1851-LAN-SCH-001 - Detailed Plant Schedule and Specification; LLD1851-LAN-REP-001 - Long Term Management Plan.*
5. Refer to *LLD1851-LAN-SPE-001* for *Hard and Soft Landscape specification.*



## PLANNING ISSUE

| Rev | Description | Date | Initials |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| 00 | Planning Issue | 19.12.19 | ML |


LIZARD
Landscape Design and Ecology
The Old Bank, 34 South Street, Tarring, Worthing, West Sussex, BN14 7LH
T. 01903 216033 E. lizardlandscape@btconnect.com W. lizardlandscapeecology.com


*Client*
ECE Planning
*Project Title and Location*
**The Cottage**
Shripney Road, Bognor Regis, West Sussex
*Drawing Title*
**Detail Planting Plan 4 of 7**
Ornamental Planting

| *Scale* | *Drawn* | *Approved* | *Date* |
|---|---|---|---|
| **1:50@A1** | ML | TT | 19.12.2019 |

*Drawing No* **LLD1851-LAN-DWG-204** *Revision* 00

ARUN DISTRICT COUNCIL BE/137/19/RES