



	Proposed - Planting Areas
	Proposed - Ornamental Shrub/ Grasses Planting
	Proposed - Herbaceous Planting
	Proposed - Ornamental Hedge
	Proposed - Mixed Species Climbers

1. *All Imported Topsoil: to be Multi-Purpose Topsoil to BS 3882: 2015. Topsoil to be tested and certified by a Soil Scientist;*
2. *Existing stripped topsoil (stored and re used): to be screened / cultivated to accord with BS 3882: 2015; tested and certified by a Soil Scientist.*

All proposed Ornamental Planting / Hedge Planting / Native Understory Shrub planting areas to be 300mm depth subsoil overlain with a of 300mm depth of topsoil tested and certified to achieve **BS 3882: 2015**. Topsoil to be tested and certified by a Soil Scientist.

All proposed planting areas to be overlain with 75mm depth Ornamental Bark Mulch. Planting areas to be mulched with fine graded ornamental bark mulch; 5 - 35mm nominal particle size; *BS4970:1987*.

1. Dimensions shall not be scaled. All dimensions to be checked on site.
2. Drawing is to be read in conjunction with all relevant Landscape Architect's drawings and specification.
3. For Hard and Soft Landscape General Arrangement refer to **LLD1851-LAN-DWG-100**.
4. For detailed soft landscape scheme proposals refer to **LLD-LAN-DWG-200 series - Detailed Planting Plan**; **LLD1851-LAN-SCH-001 - Detailed Plant Schedule and Specification**; **LLD1851-LAN-REP-001 - Long Term Management Plan**.
5. Refer to **LLD1851-LAN-SPE-001** for *Hard and Soft Landscape specification*.



Rev	Description	Date	Initials
01	Planning Issue	20.01.20	ML
00	Planning Issue	19.12.19	ML



<p><i>Client</i> ECE Planning <i>Project Title and Location</i> The Cottage Shripney Road, Bognor Regis, West Sussex</p>			
<p><i>Drawing Title</i> Detail Planting Plan 3 of 7 Ornamental Planting</p>			
<p><i>Scale</i> 1:50@A1</p>	<p><i>Drawn</i> ML</p>	<p><i>Approved</i> TT</p>	<p><i>Date</i> 19.12.2019</p>
<p><i>Drawing No</i> LLD1851-LAN-DWG-203</p>			<p><i>Revision</i> 01</p>