

Refrigerated 20ft Container (Zanotti Bas 235)



Dimensions

Type	Length	Width	Height
Zanotti Bas 235	20ft (6048mm)	8ft (2438mm)	8.5ft (2591mm)

Noise level

Type	At 3 metres from front.	At 10 metres from front.	Average noise level at 10 metres from sides and front. ISO
Zanotti Bas 235	64db.	54db	45db

Electrical Duty

Type	Weight kg	Comp HP	Volts	KW	Amps
Bas 235	179	5	440/3N/50hz	3.9	9.1

	Product Engineering Spacewise CENE Marsh Way Rainham Essex RM13 8EU	1 of 2
--	--	--------

Refrigeration Duty

Type	At - 15°C			At - 20°C			At - 25°C			Full duty
	watt	Kcal/h	M ³	watt	Kcal/h	M ³	Watt	Kcal/h	M ³	
Bas 235	4996	4296	81	4114	3538	61	3283	2823	44	8500

	BAS 235T
Nominal Power	3.7 Kw
Refrigerant	R409A
Voltage	440/3N/50Hz
Normal Power	3.9Kw – 9.1A
Defrost	Hot Gas
Air Flow Condenser.	2700m ³ /h
Air Flow Evaporator	3900m ³ /h
Air Throw.	9.5m

Del Temp	Ambient Temp	Power	Room Volume m ³	Power	Room Volume m ³	Power	Room Volume m ³	Power	Room Volume m ³
-15	20	3530	49	6259	108	10108	191	12921	267
-15	25	3345	45	5837	90	9451	175	12090	245
-15	30	3158	41	5413	81	8792	159	11260	223
-15	35	2972	37	4996	72	8135	143	10418	200
-15	40	2786	34	4588	64	7466	127	9566	178
-15	45	2600	30	4194	56	6788	111	8703	157
-20	20	2942	37	5336	79	8589	154	11041	217
-20	25	2775	33	4925	71	7999	140	10294	197
-20	30	2613	30	4515	62	7400	125	9532	178
-20	35	2453	27	4114	55	6797	111	8756	158
-20	40	2294	24	3723	47	6258	99	7973	139
-20	45	2134	21	3357	40	5668	86	7193	121
-25	20	2400	26	4456	61	7179	120	9245	170
-25	25	2247	23	4061	54	6649	108	8574	154
-25	30	2101	21	3666	46	6121	96	7890	137
-25	35	1959	18	3283	39	5597	85	7195	121
-25	40	1821	17	2927	32	5059	74	6497	105
-25	45	1684	15	2608	27	4539	63	5809	89