Notes

1. Cable draw pits shall be constructed by the main contractor. All sizes indicated refer to internal dimensions. Pits to have heavy duty, weather-proof covers

2. Cable duct specification as follows:
   - all buried ducts to be Ø150mm pvc unless stated.
   - all duct bends to have 'slow' bends.
   - all cable duct installations to include nylon draw wires.
   - duct entries in to draw pits are to incorporate bell mouths.

6. Minimum service depths (unless otherwise stated) below carriageways to be as follows:
   - BT = 450mm B.G.L
   - Electricity = 700mm B.G.L
   - Gas = 600mm B.G.L
   - Water = 900mm B.G.L

7. Minimum space between services under 2m footways to be as follows:
   - BT = 430mm from carriageway
   - Electricity :- hv = 1500mm from carriageway
     lv = 1500 / 1720mm from carriageway
   - Gas = 960mm from carriageway
   - Water = 690mm from carriageway

Legend

- PVC rigiduct complete with nylon draw cords
- 800 x 800 cable draw pit
- ANPR camera
- 6m column mounted PTZ camera

Rev	Date	Description	Cad	Chk
2	11/02/2020	PTZ cameras added and cabinet locations revised	AP	JB
1	04/02/2020	Duct layout updated and ANPR cameras added	AP	JB

Architect

MountfordPigott
Architecture Masterplanning Design

Client

LandLink Estates

Project

Saltbox

Drawing Title

Saltbox Phase 2
External Ducts and CCTV Layout

ScotchPartners
Building Services Engineering | Sustainability | Acoustics
Scriptor Court
157 Farringdon Road
London EC1R 3AD
020 3544 5400
www.scotchpartners.com

Copyright reserved. Work to figured dimensions only. Discrepancies to be reported before proceeding.

Issue	Contract		
Date	Nov 19	Scale @ A1	N.T.S
Drawn By	AP	Checked By	JB
Drawing No.	5163-SP-EX-120	Rev	2

ARUN DISTRICT COUNCIL BE/15/20/DOC