BERSTED PARK
CHICHESTER ROAD
NORTH BERSTED

SCHEDULE OF TREE WORKS

Prepared by
ACD
ARBORICULTURE

for

Berkeley
Designed for life

ACD

Ecology

Arboriculture

Landscape Architecture


Written By:	M Welby
Checked By:	
Date:	25/11/2013
Revision:	
Ref:	BERK18952stw

ARUN DISTRICT COUNCIL BE/21/14/T

APPENDIX 1: TREE SCHEDULE

No.	Name	Height	Size	Canopy Spread	Comments & recommendations
T1	Field Maple (Acer campestre)	10	Large	6	No obvious significant defects. Ivy on stem.
T2	Hawthorn (Crataegus monogyna)	5	Small	2	No obvious significant defects. Ivy on stem.
T3	Hawthorn (Crataegus monogyna)	5	Small	3	No obvious significant defects. Ivy on stem.
T4	Field Maple (Acer campestre)	4	Small	1	No obvious significant defects. Small with limited current landscape value.
T5	Common Oak (Quercus robur)	9	Medium	6	No obvious significant defects.
T6	Hawthorn (Crataegus monogyna)	4.5	Small	1	Declining. Scattered deadwood. **Recommendations: Remove tree within 6 months.**
T7	Ash (Fraxinus excelsior)	11	Large	6	No obvious significant defects. Ivy on stem. Scattered deadwood. Broken branches in crown. **Recommendations: Clean crown of poorly attached deadwood.**
T8	Hawthorn (Crataegus monogyna)	4	Small	1	No obvious significant defects. Spindly habit. Ivy on stem.
T9	Hawthorn (Crataegus monogyna)	4	Medium	1.5	Heavily ivy clad.
T10	Hawthorn (Crataegus monogyna)	5	Medium	2	No obvious significant defects.
T11	Ash (Fraxinus excelsior)	12	Large	7	No obvious significant defects. Ivy on stem. Multiple stems below 1.5m. Scattered deadwood.
T12	Hawthorn (Crataegus monogyna)	4	Small	1	No obvious significant defects. Tree of low quality and value.
T13	Ash (Fraxinus excelsior)	12	Large	7	Ivy on stem. Multiple stems below 1.5m. Scattered deadwood. Two stems, westerly one with Daldinia fruiting bodies at 1.5m (north). Extensive bacterial canker throughout crown. **Recommendations: Remove poorly attached deadwood. Remove westerly stem before it fails into stream.**
T14	Field Maple (Acer campestre)	4	Medium	4	No obvious significant defects. Ivy on stem.
T15	Common Oak (Quercus robur)	13	Large	6.5	No obvious significant defects. Scattered deadwood.
T16	Ash (Fraxinus excelsior)	14	Medium	1	Growing up through Oak. Very poor condition. **Recommendations: Remove tree within 6 months.**
T17	Ash (Fraxinus excelsior)	11	Medium	5	Scattered deadwood. Two stems weighted east. **Recommendations: Remove all poorly attached deadwood.**
T18	Hawthorn (Crataegus monogyna)	5	Small	3	No obvious significant defects. Ivy on stem.

APPENDIX 2: TREE LOCATIONS PLAN



ACD LANDSCAPE ARCHITECTS LTD
RODBOURNE RAIL BUSINESS CENTRE
GRANGE LANE
MALMESBURY
WILTS
SN16 0ES
TEL: (01666) 825646 FAX: (01666) 824654
email: mail@acdlandscape.co.uk
CONTACT: JOHN CONSTABLE

ACD ECOLOGY LTD
RODBOURNE RAIL BUSINESS CENTRE
GRANGE LANE
MALMESBURY
WILTS
SN16 0ES
TEL: (01666) 825646 FAX: (01666) 824654
email: mail@acdlandscape.co.uk
CONTACT: DUNCAN MURRAY

ACD ARBORICULTURE LTD
COURTYARD HOUSE
MILL LANE
GODALMING
SURREY
GU27 1EY
TEL: (01483) 425714
email:m.welby@acdarb.co.uk
CONTACT: MARK WELBY

ACD (LANDSCAPE ARCHITECTS) SOUTHAMPTON LTD
12 SOUTHGATE STREET
WINCHESTER
HAMPSHIRE
SO23 9EF
TEL: (01962) 855604 FAX:
email:a.wells@acdlandscape.co.uk
CONTACT: ANNETTE WELLS

ECOLOGY * ARBORICULTURE * ARBORICULTURAL SITE MONITORING AND SUPERVISION * LANDSCAPE & VISUAL IMPACT ASSESSMENT * LANDSCAPE DESIGN & PLANNING * LANDSCAPE MANAGEMENT * LANDSCAPE AUDIT * PROJECT MANAGEMENT * EXPERT WITNESS

ARUN DISTRICT COUNCIL BE/21/14/T