Planting Schedule

Trees

Species Name	Girth	Height	Density	Specification	No.
Sorbus torminalis		60-80cm	1Ctr	1+2 :Transplant :Multi-Stemmed :BR	17No
Viburnum opulus		60-80cm	2/m²	Bushy	4No
Corylus avellana		60-80cm	2/m²	Bushy :BR	4No
Acer campestre		80-100cm	3/m²	Transplant :BR	89No
Crataegus monogyna		80-100cm	3/m²	Transplant :BR	89No
Prunus spinosa		80-100cm	2/m²	Bushy :BR	3No
Malus sylvestris		100-125cm	3/m²	Feather :RB	89No
Crataegus monogyna		100-125cm	1Ctr	Bushy :1/3 brks :BR	81No
Ilex aquifolium		100-125cm	1Ctr	3 brks ;C	6No
Crataegus monogyna		100-125cm	0.5Ctr Double Staggered at 0.5m offset	Transplant :BR	56No
Betula nigra		175-200cm	1Ctr	Feather ;2x :BR	17No
Malus sylvestris	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB	4No
Betula albosinensis 'Fascination'	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB	5No
Acer rubrum 'October Glory'	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB	11No
Tilia cordata	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB	4No
Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem min. 200 :RB	2No
Carpinus betulus	12-14cm	350-425cm	Counted	Heavy Standard :Clear Stem 175-200 :RB	3No

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Abelia grandiflora 'Kaleidoscope'	30-40cm	3L	Bushy	4/m²	182No
Berberis media 'Red Jewel'	30-40cm	3L	Bushy :C	4/m²	155No
Buxus sempervirens	60-80cm	3L	Branched :C	0.5Ctr	164No
Carpinus betulus	60-80cm		Bushy	0.5Ctr Double Staggered at 0.5m offset	39No
Cistus x hybridus	30-40cm	3L	Bushy	4/m²	160No
Clethra alnifolia 'Paniculata'	20-30cm	3L		4/m²	39No
Cornus alba	40-60cm		Branched :BR	1Ctr	17No
Cornus kousa var. chinensis	150-175cm	10L	7 leaves	Counted	7No
Cornus sanguinea	30-40cm	3L	Bushy :BR	3/m²	89No
Corylus avellana	100-125cm		Branched :BR	3/m²	89No
Corylus avellana	60-80cm	3L	Branched :BR	0.5Ctr Double Staggered at 0.5m offset	12No
Cotoneaster 'Coral Beauty'	30-40cm	3L	Bushy	4/m²	64No
Crataegus monogyna	60-80cm		Bushy	0.5Ctr Double Staggered at 0.5m offset	238No
Euonymus europaeus	60-80cm		Bushy :BR	3/m²	89No
Euonymus fortunei 'Emerald Gaiety'	40-60cm	5L	Bushy :C	4/m²	98No
Euonymus japonicus 'Paloma Blanca'	40-60cm	5L	Bushy :C	4/m²	394No
Hamamelis intermedia 'Ruby Glow'		10L	7 leaves	Counted	3No
Hebe franciscana 'Blue Gem'	30-40cm	3L	Bushy	4/m²	122No
Hippophae rhamnoides	60-80cm		Branched :3 brks :BR	1Ctr	17No
Hydrangea paniculata 'Grandiflora'	20-30cm	3L		4/m²	94No
Hypericum moserianum	20-30cm	3L		4/m²	180No
Ilex aquifolium	30-40cm	2L	Bushy	0.5Ctr Double Staggered at 0.5m offset	12No
Leucothoe walteri 'Nana'	20-30cm	3L		4/m²	229No
Ligustrum ovalifolium	60-80cm		Bushy	0.5Ctr Double Staggered at 0.5m offset	1925No
Ligustrum ovalifolium	100-125cm		Bushy :3 brks :RB	1Ctr	12No
Ligustrum vulgare	100-125cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	34No
Magnolia 'Susan'		10L	7 leaves	Counted	7No
Mahonia media 'Winter Sun'	40-60cm	5L	Bushy :C	4/m²	72No
Nandina domestica 'Nana Purpurea'	30-40cm	3L	Bushy	4/m²	47No
Olearia haastii	30-40cm	3L	Bushy	4/m²	102No
Osmanthus burkwoodii	30-40cm	3L	Bushy	4/m²	107No
Philadelphus 'Belle Etoile'	30-40cm	3L	Bushy	4/m²	108No
Photinia fraseri 'Little red robin'	40-60cm	5L	Bushy :C	4/m²	168No
Pittosporum tenuifol. 'Golf Ball'	40-60cm	5L	Bushy	4/m²	207No
Potentilla fruticosa 'Red Ace'	30-40cm	3L	Bushy	4/m²	123No
Prunus spinosa	80-100cm		Bushy :BR	3/m²	89No
Rosa 'Bambino'	40-60cm	5L	Bushy :C	4/m²	71No
Salix caprea	60-80cm		Branched :BR	3/m²	89No
Salix cinerea	60-80cm		0/1 :5/6 brks :BR :Branched	1Ctr	26No
Salix purpurea	60-80cm		0/1 :5/6 brks :BR :Branched	1Ctr	17No
Salix triandra	60-80cm		0/1 :5/6 brks :BR :Branched	1Ctr	26No
Salvia officinalis 'Purpurascens'	40-60cm	5L	Bushy :C	4/m²	126No
Sambucus nigra	80-100cm		Bushy :BR	3/m²	89No
Sambucus nigra	80-100cm		Bushy :3 brks :RB	1Ctr	12No
Sarcococca hookeriana digyna	20-30cm	3L		4/m²	170No
Skimmia japonica 'Kew White'	20-30cm	3L		4/m²	214No
Syringa meyeri 'Palibin'		10L	7 leaves	Counted	11No
Viburnum davidii	30-40cm	3L	Bushy :C	4/m²	287No
Viburnum lantana	60-80cm		1+1 :Bushy :BR	1Ctr	17No
Viburnum opulus	60-80cm		Bushy :BR	3/m²	89No
Viburnum opulus	60-80cm		Bushy :BR	1Ctr	23No
Viburnum tinus 'Eve Price'	20-30cm	3L		4/m²	24No

Herbaceous

Species Name	Pot Size	Specification	Density	No.
Bergenia 'Silberlicht'	3L	Full Pot	7/m²	52No
Geranium 'Johnson's Blue'	3L	C	4/m²	141No
Thymus serpyllum	3L	C	4/m²	51No

SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 6
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties.
- Proposed low hedge planting to be planted in a single row at 300mm centres to be maintained at 60cm height
- Proposed ornamental hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.8m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed mixed native shrub planting to be planted in groups of 5-7no. of each species and as above
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Grassland areas to be retained. Patches to be seeded with EM5F Wild flower Mixture to be sown at a swing rate of 1.5g/m2; available from Emorsgate Seeds or similar and approved
- Proposed SUDS area, to be seeded with EM8 (Meadow mixture for wetlands) from Emorsgate or similar and approved.
- Cut lines

Planting Schedule on Sheet 2

Rev	Date	Details	Drawn
E	12/07/19	Client Comments	JO
D	11/07/19	Client Comments	JO
C	11/07/19	Client Comments	JO
B	09/07/19	Planting amended around drainage	JO
A	24/04/19	Drainage Layout - Planting Amended	JO

ACD ENVIRONMENTAL
HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane, Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026300

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk

Linden HOMES

scheme: Land West of New Barn Lane, North Bersted, 'Alternative Application'
client: Linden Homes
drawing: Soft Landscape Proposals
date: February 2019
scale: 1:200@A1
drawing no: LIN22349 11E Sheet 2
drawn: JO checked: DKM

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted: 2011. Copyright of this plan remains with ACD until all fees have been paid in full.