

JAKOUSTIC® REFLECTIVE

**Jacksons
Fencing**



The Jakoustic® reflective barrier reflects the noise away using heavy section planed timber boards with a special profile that has been carefully developed. Boards are constructed in such a way that eliminates gaps that sound can easily travel through. Up to 28 dB* in noise reduction.

- Unique tuning fork design posts
- Attractive timber structure with a planed finish throughout
- Anti climb design and scale design
- High privacy barrier
- Special fixings clamp the acoustic boards between posts
- Can accommodate changes in level or profile
- Complete with capping and counter rail
- Up to 28 dB reduction in noise*
- Category B3 rating
- 34mm thick "V" boards
- Matching pedestrian, swing and tracked sliding gates
- 25-year Jakcure® guarantee

* Jakoustic® barrier certified laboratory results:

Rating according to BS EN 1793-2:1998

Category = B3

Laboratory sound reduction 28 dB

Superficial mass 25kg/m²



- Heights available with timber tuning fork posts, for general applications away from hills and coasts.
- For barrier heights 2.1m - 3.0m the timber posts are reinforced with a steel spur post, coated black.

HEIGHT (MM)	POST CENTRES (MM)	SPUR POST (MM)	POST LENGTH (MM)
2000	2410	N/A	2830
2500	2410	2000	3400
3000	2410	2500	3900

*For taller heights, see Jakoustic® Commercial and Highway, which is constructed on galvanised steel I beam posts.

APPLICATIONS

- ✓ Commercial properties
- ✓ Construction sites
- ✓ Sports venues
- ✓ Residential properties

POST OPTIONS

- Timber tuning fork posts overlength set in concrete as standard

GATES

Matching gates available

FINISHES

- Jakcure® treated timber as standard