

Planting Schedule							
Species	Percentage	Common Name	Classification	Girth/Container Size	Planting Density	Number	
MEDIUM HEIGHT HEDGES							105 lin m
Carpinus betulus		Hombeam	Bareroot		5 per lin m	525	
Plant guards required			Feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.2m high hedge				
NATIVE MIX HEDGES							54m2
Crataegus monogyna	30%	Hawthorn	Feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.2m high hedge.Bare root. 5 per m2			81	
Prunus spinosa	30%	Blackthorn				81	
Acer campestre	15%	Field Maple				40	
Elder	15%	Sambucus nigra				40	
Hazel	10%	Coryllus avellana				27	
ENHANCED BOUNDARY							
New Native Hedge Planting							155m2
Crataegus monogyna	30%	Hawthorn	Existng scrub area to be cleared of undesirable species. New native hedge and wildflower to be planted. Hedge to be feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.5m high hedge. Bare root.			81	
Prunus spinosa	30%	Blackthorn				81	
Acer campestre	15%	Field Maple				40	
Elder	15%	Sambucus nigra				40	
Hazel	10%	Coryllus avellana				27	
Wildflower Mix							103m2
Shade tolerant mix							
GROUNDCOVER SPECIES							62m2
In swathes of min 20 plants							
Vinca Minor	35%	Periwinkle	Container	2L	4 per m²	87	
Luzula sylvatica	30%	Wood-rush	Container	2L	3 per m²	56	
Euonymus fortunei 'Darts Blanket'	35%	Darts Blanket	Container	3L	4 per m²	87	
LAWN TURF							1745m2
Turf							
WILDFLOWER MIX							175m2
Shade tolerant mix					5g per m2		
SHRUB MIX							249m2
Bergenia 'Overture'	10%	Elephant's Ears	Container	2L	5 per m2	125	
Cistus crispus 'Sunset'	10%	Rick Rose 'Sunset'	Container	3L	4 per m2	100	
Euonymous fortunei 'Emerald Gaiety'	15%	Euonymous	Container	3L	5 per m2	187	
Hebe albicans 'Red Edge'	15%	Hebe 'Red Edge'	Container	3L	7 per m2	261	
Pennisetum orientale	30%	Fountain Grass	Container	3L	5 per m2	374	
Liriope muscari	10%	Big Blue Lilyturf	Container	2L	7 per m2	174	
Viburnum davidii	10%	Viburnum	Container	3L	4 per m2	100	
Tree Schedule							
	Species	Common Name	Size	Number	Notes		
FEATURE TREE TYPE 1	Quercus rubra	Red Oak	40-45cm girth, RB	3	Semi mature, fastigiate, 2m clear stem, 7m high		
FEATURE TREE TYPE 2	Alnus glutinosa	Common Alder	20-25cm girth, RB	2	Semi mature, fastigiate, 2m clear stem, 3-5m high		
FRONT GARDEN TREES	Prunus serulata 'Sunset Boulevard'	Wild cherry	20-25cm girth, RB	15	Semi mature, fastigiate, 2m clear stem, 3-5m high		
CENTRAL SPACE TREES	Betula utilis 'Jaquemontii'	Himalyan Birch	4 x 4m CG multistem	8	Semi mature, multistem 4m x 4m high		
NATIVE TREES TYPE 1	Acer campestre	Field Common Maple	20-25cm girth, RB	5	Semi mature fastigiate 2m clear stem 5m high		
NATIVE TREES TYPE 2	Betula pendula	Silver Birch	20-25cm girth, RB	8	Semi mature fastigiate 2m clear stem 5m high		
NATIVE TREES TYPE 3	Quercus robur	Common Oak	20-25cm girth, RB	2	Semi mature, fastigiate, 2m clear stem, 5m high		
north NOTES: This drawing is the copyright of Hyland Edgar Driver. It must not be copied or reproduced without written consent. Only figured dimensions are to be taken from this drawing. All contractors must visit the site and be responsible for taking and checking all dimensions related to the works shown on this drawing.			REVISIONS		DATE	DRAWN BY	CHECKED BY
			P01: Issue For Planning - 220331 - JW		08.11.21	CH	IN
			-				SCALE @ A3
			-				AS SHOWN
			-				
			-				
			-				
			-				
			-				
			-				
PROJECT					Former Bartons Infant School Site, North Bersted		
DRAWING TITLE					PLANTING SCHEDULE		
DRAWING NUMBER					REVISION		
1444-HED-DR-02-009					P01		
CLIENT							LOVELL & WSCC
H E D Hyland Edgar Driver Landscape Architects & Urban Designers							
One Wessex Way Colden Common Winchester SO21 1WG							t. 01962 711 600