

Planting Schedule								
Species	Percentage	Common Name	Classification	Girth/Container Size	Planting Density	Number		
MEDIUM HEIGHT HEDGES							77 lin m	
Carpinus betulus		Hombeam	Bareroot		5 per lin m	385		
Plant guards required			Feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.2m high hedge					
NATIVE MIX HEDGES							42m2	
Crataegus monogyna	30%	Hawthorn	Feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.2m high hedge.Bare root. 5 per m2			63		
Prunus spinosa	30%	Blackthorn				63		
Acer campestre	15%	Field Maple				31		
Elder	15%	Sambucus nigra				31		
Hazel	10%	Coryllus avellana				22		
ENHANCED BOUNDARY								
New Native Hedge & Scrub Planting							349m2	
Crataegus monogyna	30%	Hawthorn	Existng scrub area to be cleared of undesirable species. New native hedge and wildflower to be planted. Hedge to be feathered to base, double staggered. 1.5m high, once planted reduce to a consistent 1.5m high hedge. Bare root. 5 per m2			244		
Prunus spinosa	30%	Blackthorn				244		
Acer campestre	15%	Field Maple				122		
Elder	15%	Sambucus nigra				122		
Hazel	10%	Coryllus avellana				81		
Wildflower Mix								
Shade tolerant mix								
GROUNDCOVER SPECIES							21m2	
In swathes of min 20 plants								
Vinca Minor	35%	Periwinkle	Container	2L	4 per m²	29		
Luzula sylvatica	30%	Wood-rush	Container	2L	4 per m²	25		
Euonymus fortunei 'Darts Blanket'	35%	Darts Blanket	Container	3L	4 per m²	29		
LAWN TURF							1580m2	
Turf								
WILDFLOWER MIX							175m2	
Shade tolerant mix					5g per m2			
SHRUB MIX							101m2	
Bergenia 'Overture'	10%	Elephant's Ears	Container	2L	5 per m2	51		
Cistus crispus 'Sunset'	10%	Rick Rose 'Sunset'	Container	3L	4 per m2	40		
Euonymous fortunei 'Emerald Gaiety'	15%	Euonymous	Container	3L	5 per m2	76		
Hebe albicans 'Red Edge'	15%	Hebe 'Red Edge'	Container	3L	7 per m2	106		
Pennisetum orientale	30%	Fountain Grass	Container	3L	5 per m2	152		
Liriope muscari	10%	Big Blue Lilyturf	Container	2L	7 per m2	71		
Viburnum davidii	10%	Viburnum	Container	3L	4 per m2	40		
Tree Schedule								
	Species	Common Name	Size	Number	Notes			
FEATURE TREE TYPE 1	Acer x freemanii	Autumn Blaze	40-45cm girth, RB	1	Semi mature, fastigiate, 2m clear stem, 7m high			
FEATURE TREE TYPE 2	Alnus glutinosa	Common Alder	20-25cm girth, RB	2	Semi mature, fastigiate, 2m clear stem, 3-5m high			
FRONT GARDEN TREES	Prunus serulata 'Sunset Boulevard'	Wild cherry	20-25cm girth, RB	8	Semi mature, fastigiate, 2m clear stem, 3-5m high			
CENTRAL SPACE TREES	Betula utilis 'jaquemontii'	Himalyan Birch	4 x 4m CG multistem	8	Semi mature, multistem 4m x 4m high			
NATIVE TREES TYPE 1	Acer campestre	Field Common Maple	20-25cm girth, RB	5	Semi mature fastigiate 2m clear stem 5m high			
NATIVE TREES TYPE 2	Betula pendula	Silver Birch	20-25cm girth, RB	8	Semi mature fastigiate 2m clear stem 5m high			
NATIVE TREES TYPE 3	Quercus robur	Common Oak	20-25cm girth, RB	4	Semi mature, fastigiate, 2m clear stem, 5m high			
north NOTES: This drawing is the copyright of Hyland Edgar Driver. It must not be copied or reproduced without written consent. Only figured dimensions are to be taken from this drawing. All contractors must visit the site and be responsible for taking and checking all dimensions related to the works shown on this drawing.			REVISIONS		DATE	DRAWN BY	CHECKED BY	
			P01: Issue For Planning - 220331 - JW		08.11.21	CH	IN	
			P02: Issue For Planning - 221128 - JW		DRAWING STATUS		SCALE @ A3	
			P03: Issue For Stage 3 - 230126 - SK		For Planning		AS SHOWN	
			P04: Update for Planning - 230517 - JW		PROJECT	Former Bartons Infant School Site, North Bersted		
			P05: Minor Corrections - 230719 - JW		DRAWING TITLE			
			-		PLANTING SCHEDULE			
			-		DRAWING NUMBER		REVISION	
			-		1444-HED-DR-02-009		P05	
CLIENT LOVELL & WSCC							Hyland Edgar Driver Landscape Architects & Urban Designers	
H E D								
One Wessex Way Colden Common Winchester SO21 1WG								
t. 01962 711 600								