KEY

- Existing tree
- Unimproved grass sward, overseeded with Germinal Seed mix WFG4 or similar approved. cut once per year in late autumn with arisings removed
- Proposed tree
- Proposed hedge
- Proposed shrubs
- Proposed amenity grass sward
- Buffer Mix

Planting schedule

Trees	**Size**	**Spec**	**Density**	**Quantities**
Acer campestre	14-16cm girth	Root balled	As shown	9
Alnus glutinosa	16-18cm girth	Root balled	As shown	4
Alnus glutinosa laciniata	16-18cm girth	Root balled	As shown	7
Amelanchier Ballerina	14-16cm girth	Container grown	As shown	4
Betula pendula	12-14cm girth	Container grown	As shown	4
Betula pubescens	12-14cm girth	Container grown	As shown	6
Betula utilis Grayswood Ghost	20-25cm girth	Multi stem 3 bole	As shown	13
Ginkgo biloba 'Blagon'	18-20cm girth	Root balled	As shown	3
Quercus robur	16-18cm girth	Root balled	As shown	5
Tilia cordata Rancho	20-25cm girth	Root balled	As shown	16
Hedges				
Fagus sylvatica	1.2-1.5m	Bare root	5 Per lin m - double staggered rows	1405
Lonicera pileata	50-60cm	5Lt	5 Per lin m - double staggered rows	220

Native hedge - Planted in groups of 3 to 10			%		
Corylus avellana	60-90cm	Bare root	40	5 Per lin m - double staggered rows	180
Cornus sanguinea	60-90cm	Bare root	10	5 Per lin m - double staggered rows	45
Crataegus monogyna	60-90cm	Bare root	20	5 Per lin m - double staggered rows	90
Ilex aquifolium.	60-90cm	Bare root	5	5 Per lin m - double staggered rows	22
Lonicera periclymenum	20-30cm	Bare root	5	5 Per lin m - double staggered rows	22
Pinus spinosa	60-90cm	Bare root	15	5 Per lin m - double staggered rows	68
Rosa canina	60-90cm	Bare root	5	5 Per lin m - double staggered rows	23

Shrubs and grasses				
Cornus alba 'sibirica	60-90cm	Bare root	2.5 Per Sq m	215
Cornus sanguinea Midwinter Fire	60-90cm	3 Lt	2.5 Per Sq m	188
Cornus sericea Flaviramea	60-90cm	Bare root	2.5 Per Sq m	122
Escallonia edbaingei Limelight	60-90cm	3 Lt	2 Per Sq m	64
Escallonia Gold Brian	30-40cm	3 Lt	3 Per Sq m	310
Euonymus Dart's Blanket	30-40cm	3 Lt	3 Per Sq m	321
Hebe Green Globe	30-40cm	3 Lt	4 Per Sq m	540
Lonicera Baggesen's Gold	30-40cm	3 Lt	3 Per Sq m	54
Lonicera May Green	30-40cm	3 Lt	4 Per Sq m	692
Miscanthus Morning Light	NA	3 Lt	3 Per Sq m	81
Pinus mugo Mini Mound	10-15cm	3 Lt	5 Per Sq m	245
Prunus otto Luyken	30-40cm	3 Lt	3 Per Sq m	317
Viburnum davidii	30-40cm	5 Lt	2 Per Sq m	138

Buffer planting mix (1.5 m grid)			%	
Acer campestre	90-1.2m	Bare root	10%	5
Corylus avellana	90-1.2m	Bare root	25%	14
Cornus sanguinea	60-90 cm	Bare root	10%	5
Crataegus monogyna	90-1.2m	Bare root	20%	12
Ilex aquifolium.	40-60cm	3Lt.	5%	3
Lonicera periclymenum	30-40cm	3Lt	2%	1
Pinus spinosa	40-60cm	Bare root	10%	5
Rosa canina	40-60cm	Bare root	3%	2
Sorbus aucuparia	90-1.2m	Bare root	5%	3
Taxus baccata	90-1.2m	5Lt	10%	5

450 Native Hedge
2 Acer campestre
1 Alnus glutinosa
2 Betula pubescens
3 Quercus robur
2 Betula pubescens
1 Quercus robur
1 Acer campestre
2 Acer campestre
1 Quercus robur
3 Betula pendula
centre line water course
Garden center
2 Acer campestre
3 Alnus glutinosa
72 Escallonia Gold Brian
3 Betula utilis Grayswood Ghost
63 Prunus otto Luyken
105 Cornus alba Sibirica
120 Lonicera May Green
26 Prunus otto Luyken
115 Fagus sylvatica
40 Lonicera May Green
3 Betula pendula
50 Cornus alba Sibirica
2 Acer campestre
43 Escallonia Gold Brian
2 Alnus glutinosa laciniata
30 Cornus alba Sibirica
66 Prunus otto Luyken)
1 Alnus glutinosa laciniata
20 Viburnum davidii
70 Cornus sanguinea Midwinter Fire
82 Cornus sericea Flaviramea
144 Lonicera May Green
1 Betula utilis Grayswood Ghost
132 Escallonia Gold Brian
93 Cornus sanguinea Midwinter Fire
3 Betula utilis Grayswood Ghost
6 Tilia cordata Rancho
240 Fagus sylvatica
40 Hebe Green Globe
2 Amelanchier Ballerina
20 Viburnum davidii
8 Tilia cordata Rancho
36 Prunus otto Luyken
600 Fagus sylvatica
188 Lonicera May Green
30 Escallonia Gold Brian
125 Lonicera pileata
200 Fagus sylvatica
24 Vibricoom davidii
2 Amelanchier Ballerina
44 Hebe Green Globe
33 Escallonia Gold Brian
25 Lonicera pileata
2 Tilia cordata Rancho
54 Lonicera Baggesen's Gold
81 Euonymus Dart's Blanket
36 Prunus otto Luyken
3 Alnus glutinosa laciniata
40 Cornus sericea Flaviramea
30 Cornus alba Sibirica
74 Viburnum davidii
200 Lonicera May Green
36 Escallonia ebbingei Limelight
2 Betula pubescens
190 Fagus sylvatica
3 Betula utilis Grayswood Ghost
140 Pinus mugo Mini Mound
72 Euonymus Dart's Blanket
160 Hebe Green Globe
54 Prunus otto Luyken
1 Alnus glutinosa laciniata
168 Euonymus Dart's Blanket
296 Hebe Green Globe
3 Betula utilis Grayswood Ghost
81 Miscanthus Morning Light
105 Pinus mugo Mini Mound
25 Cornus sanguinea Midwinter Fire
36 Prunus otto Luyken
3 Ginkgo biloba 'Blagon'
28 Escallonia ebbingei Limelight

Mark	Date	Details	By
P01	18.03.2019	Additional grass sward mix added	IM
-	04.03.2019	First Issued	IM

REVISIONS

Client:
Hanbury (PM) Limited

Project Title :
Phase 1A
Oldlands Farm, Bognor

Scale : 1:500 — for the original size of : A1

Drawn by : IM | Checked by : MG | Passed by : - | Date :12.03.2019

Drawing Status :
Planning

Drawing Originator :
DAVIESLANDSCAPE ARCHITECTS
Suite F1, Stroud House, Russell Street, Stroud, Gloucestershire, GL5 3AN
t. 01453 760380 e. info@d-la.co.uk w. www.d-la.co.uk

Drawing Title :
Planting Proposal

Job No.	Drawing							Revision
	Project	Origin	Volume	Level	Type	Discip	Number	
1930	1930	DLA	xx	xx	xx	L	11	P-01

DO NOT SCALE FROM THIS DRAWING

J:\SERVER DATA\PROJECT FILES\1930 Oldlands Farm Phase 1A Reserve Matters\Landscape\Drawings\Planning\DLA-1930-L-11 P01.dwg