



Model	Genesis 11	
Airend	C55*	
FAD @ 8 Bar	58.5	CFM
FAD @ 10 Bar	52.7	CFM
FAD @ 13 Bar (3)	42.4	CFM
Control System	Infologic	
Noise Level	65	dB(A)
Temperature Min/Max	2 to 46	°C
Cooling Air Flow	1800	m ³ /hr
Oil Capacity	4	litres
Air Outlet	3/4" F - TM FF	" BSP
L x W x H - TM & TM FF 270	1150 x 655 x 1687	mm
Weight - TM FF 270	366	Kg
Receiver Size - TM	270	litres

Electrical data Compressor		
Electrical Supply	400/3/50 V/Ph/Hz	
Fuse Rating	32	Amps
Cable Size (2)	4 x 6	mm ²
Motor	WEG	
Electrical Data Dryer (1)		
Electrical Supply	230/1/50 V/Ph/Hz	
Fuse Rating	13	Amps
Cable Size (2)	2.5	mm ²

(1) Dryer fitted to Genesis units requires a separate 230V / 1Ph supply

(2) Cable installed in free air and based on multicore cable with 70 °C PVC insulation, maximum

Cable sizes are for guidance only and should always be checked by an electrical engineer

Fuses should be TYPE D Breaker or HRC Cartridge Fuses

(3) No 13 Bar version at 5.5Kw power rating