



SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.

NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 6
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties
- Proposed low hedge planting to be planted in a single row at 300mm centres to be maintained at 60cm height
- Proposed ornamental hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.5m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed mixed native shrub planting to be planted in groups of 5-7no. of each species and as above
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Grassland areas to be retained. Patches to be seeded with EMSF Wild flower Mixture to be sown at a sowing rate of 1.5g/m²; available from Emorsgate Seeds or similar and approved
- Proposed SUDS area, to be seeded with EM6 (Meadow mixture for wetlands) from Emorsgate or similar and approved.

Cut lines

Planting Schedule on Sheet 2



Rev	Date	Details	Drawn
C	07/06/18	Layout change	DC
C	04/09/17	Layout change	LS
B	30/08/17	Client comments	AE
A	25/08/17	Client comments	AE



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026500

9 Brownlow Road, Cambridge, CB4 3NG
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk



scheme: Land West of New Barn Lane, North Bersted
client: Linden Homes
drawing: Landscape Proposals
date: July 2017
scale: 1:200@A1
drawing no: LIN21257 11D Sheet 2
drawn: LS checked: AE

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Planting Schedule

Trees	Species Name	Girth	Height	Density	Specification	No.
	Sorbus torminalis	60-80cm	1Ctr		1+2 : Transplant : Multi-Stemmed : BR	19No
	Acer campestre	80-100cm	3/m ²		Transplant : BR	120No
	Crataegus monogyna	80-100cm	3/m ²		Transplant : BR	120No
	Malus sylvestris	100-125cm	3/m ²		Feather : BR	120No
	Crataegus monogyna	100-125cm	1Ctr		Bushy : 1/3 brks : BR	81No
	Ilex aquifolium	100-125cm	1Ctr		3 brks : C	6No
	Crataegus monogyna	100-125cm	5Ctr Double Staggered at 0.5m offset		Transplant : BR	48No
	Betula nira	175-200cm	1Ctr		Feather : 2x : BR	19No
	Ilex aquifolium	10-12cm	250-300cm	Counted	Standard : Clear Stem 175-200 : RB	2No
	Malus sylvestris	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	5No
	Acer campestre	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	3No
	Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	2No
	Acer rubrum 'October Glory'	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	6No
	Carpinus betulus	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	5No
	Itila cordata	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	8No
	Betula albosinensis 'Fascination'	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem 175-200 : RB	15No
	Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard : Clear Stem min. 200 : RB	3No

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Abelia grandiflora 'Kaleidoscope'	30-40cm	3L	Bushy	4/m ²	173No
Berberis media 'Red Jewel'	30-40cm	3L	Bushy : C	4/m ²	167No
Buxus sempervirens	60-80cm	3L	Branched : C	0.5Ctr	209No
Carpinus betulus	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	59No
Cistus x hybridus	30-40cm	3L	Bushy	4/m ²	155No
Clethra alnifolia 'Paniculata'	20-30cm	3L	Branched : BR	1Ctr	19No
Cornus kousa var. chinensis	150-175cm	10L	7 leaves	Counted	5No
Cornus sanguinea	30-40cm	3L	Bushy : BR	3/m ²	120No
Corylus avellana	100-125cm	3L	Branched : BR	3/m ²	120No
Corylus avellana	60-80cm	3L	Branched : BR	0.5Ctr Double Staggered at 0.5m offset	19No
Cotoneaster 'Coral Beauty'	30-40cm	3L	Bushy	4/m ²	54No
Crataegus monogyna	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	239No
Euonymus europaeus	60-80cm	3L	Bushy : BR	3/m ²	120No
Euonymus fortunei 'Emerald Gaiety'	60-80cm	5L	Bushy : C	4/m ²	109No
Euonymus japonicus 'Paloma Blanca'	40-60cm	5L	Bushy : C	4/m ²	336No
Hamamelis intermedia 'Ruby Glow'	10L	7 leaves	Counted		3No
Hebe franciscana 'Blue Gem'	30-40cm	3L	Bushy	4/m ²	103No
Hippophae rhamnoides	60-80cm	3L	Branched : 3 brks : BR	1Ctr	19No
Hydrangea paniculata 'Grandiflora'	20-30cm	3L	Bushy	4/m ²	101No
Ilex aquifolium	30-40cm	2L	Bushy	0.5Ctr Double Staggered at 0.5m offset	10No
Leucothoe walteri 'Nana'	20-30cm	3L	Bushy	4/m ²	193No
Ligustrum ovalifolium	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	2431No
Ligustrum ovalifolium	100-125cm	3L	Bushy : 3 brks : RB	1Ctr	12No
Ligustrum vulgare	100-125cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	29No
Magnolia 'Susan'	10L	7 leaves	Counted		5No
Mahonia media 'Winter Sun'	40-60cm	5L	Bushy : C	4/m ²	85No
Nandina domestica 'Nana Purpurea'	30-40cm	3L	Bushy	4/m ²	56No
Olearia haastii	30-40cm	3L	Bushy	4/m ²	106No
Osmanthus burkwoodii	30-40cm	3L	Bushy	4/m ²	119No
Philadelphus 'Belle Etoile'	30-40cm	3L	Bushy	4/m ²	134No
Photinia fraseri 'Little red robin'	40-60cm	5L	Bushy : C	4/m ²	172No
Pittosporum tenuifolium 'Golf Ball'	40-60cm	3L	Bushy	4/m ²	196No
Potentilla fruticosa 'Red Ace'	30-40cm	3L	Bushy	4/m ²	118No
Prunus spinosa	60-100cm	5L	Bushy : BR	3/m ²	120No
Rosa 'Bambino'	40-60cm	5L	Bushy : C	4/m ²	88No
Salix caprea	60-80cm	3L	Branched : BR	3/m ²	120No
Salix cinerea	60-80cm	3L	0/1 : 5/6 brks : BR : Branched	1Ctr	28No
Salix purpurea	60-80cm	3L	0/1 : 5/6 brks : BR : Branched	1Ctr	19No
Salix triandra	60-80cm	3L	0/1 : 5/6 brks : BR : Branched	1Ctr	28No
Salvia officinalis 'Purpurascens'	40-60cm	5L	Bushy : C	4/m ²	88No
Sambucus nigra	60-100cm	3L	Bushy : BR	3/m ²	120No
Sambucus nigra	60-100cm	3L	Bushy : 3 brks : RB	1Ctr	12No
Sarcococca hookeriana digyna	20-30cm	3L	Bushy	4/m ²	169No
Skimmia japonica 'Kew White'	20-30cm	3L	7 leaves	Counted	182No
Syringa meyeri 'Palibin'	30-40cm	10L	7 leaves	Counted	26No
Viburnum davidii	30-40cm	3L	Bushy : C	4/m ²	19No
Viburnum lantana	60-80cm	3L	1+1 : Bushy : BR	1Ctr	19No
Viburnum opulus	60-80cm	3L	Bushy : BR	3/m ²	120No
Viburnum opulus	60-80cm	3L	Bushy : BR	1Ctr	25No
Viburnum tinus 'Eve Price'	60-80cm	3L	Bushy	4/m ²	56No

Herbaceous

Species Name	Pot Size	Specification	Density	No.
Bergenia 'Siberlicht'	3L	Full Pot	7/m ²	47No
Geranium 'Johnson's Blue'	3L	C	4/m ²	139No
Thymus serpyllum	3L	C	4/m ²	68No

11 Sheet 6
11 Sheet 5
11 Sheet 4
11 Sheet 3
11 Sheet 2

Existing Public Footpath 134