

Site Name: Oldlands Phase 4, Land between Charles Purley Way and Shripney Road, Bognor Regis, West Sussex





Job Number: R18-13443-2

Start Date: 17/12/2018

End Date: 17/12/2018

Borehole Number: **WS201**

Sheet 1 of 1

Samples and In Situ Testing						Legend	Depth	Stratum Description
Standpipe	Sample/ Test Type	Depth From (m)	Depth To (m)	Test Result				
	D	0.50				0.00	Topsoil.	
						0.20	Brown slightly gravelly slightly sandy silty CLAY. Gravel angular to subangular fine to coarse flint. Sand is fine. (Reworked/ River Terrace Deposits)	
						0.80	Orange brown and grey mottled slightly gravelly slightly sandy silty CLAY. Gravel is angular to subangular fine to medium flint. Sand is fine. (River Terrace Deposits)	
						2.20	Light brown slightly gravelly silty CLAY. Gravel is angular to rounded fine to coarse chalk and occasional flint. Sand is fine. (River Terrace Deposits)	
						3.20	Off white CHALK. (White Chalk Subgroup)	
						5.00	End of borehole at 5.00m	
	D	1.50						
								
								
								
								
								
	D	2.80						
	D	3.50						
D	4.50							

Remarks

Groundwater: Standing water depth at 1.00m on completion.

Stability: Borehole stable on completion.

Notes: Standpipe installed to 5.00m depth; 5.00m to 2.00m slotted pipe with gravel surround; 2.00m to ground level plain pipe with bentonite seal; completed with end cap and security cover concreted proud of ground surface.

Approximate Coordinates: E 494070, N 101922

Excavation Method: WLS

Borehole Diameter: Various

Made By: MR

Site Name: Oldlands Phase 4, Land between Charles Purley Way and Shripney Road, Bognor Regis, West Sussex

Job Number: R18-13443-2

Start Date: 17/12/2018

End Date: 17/12/2018

Borehole Number:
WS202

Sheet 1 of 1

Samples and In Situ Testing					Legend	Depth	Stratum Description
Standpipe	Sample/ Test Type	Depth From (m)	Depth To (m)	Test Result			
	D	0.50				0.00	Topsoil.
	D	1.50				0.20	Brown slightly gravelly slightly sandy silty CLAY. Gravel is angular to subangular fine to coarse flint and chalk. Sand is fine. (River Terrace Deposits)
							becoming mottled grey below 1.00m depth.
	D	2.50				2.00	Brown slightly gravelly sandy silty CLAY. Gravel is angular to subrounded fine to medium chalk and occasional flint. (River Terrace Deposits)
	D	3.60				3.50	Off white and cream CHALK with frequent light brown clay infill/ pockets. (White Chalk Subgroup)
	D	4.50				5.00	End of borehole at 5.00m

Remarks
Groundwater: Standing water depth at 1.10m on completion.

Stability: Borehole stable on completion.

Notes: Standpipe installed to 5.00m depth; 5.00m to 2.00m slotted pipe with gravel surround; 2.00m to ground level plain pipe with bentonite seal; completed with end cap and security cover concreted proud of ground surface.

Approximate Coordinates: E 494034, N 101680

Excavation Method: WLS

Borehole Diameter: Various

Made By: MR