

SPECIFICATION
All works generally, to comply with the written Soft Landscape Specification.


NOTE: DO NOT SCALE FROM DRAWING

Legend

- Existing trees to be retained and protected during construction
- Proposed tree planting within soft landscape. See detail on sheet 6
- Proposed specimen shrub planting to receive short angular staking on half standards with expandable tree ties.
- Proposed low hedge planting to be planted in a single row at 300mm centres to be maintained at 60cm height
- Proposed ornamental hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height
- Proposed mixed native hedge planting to be planted in a double staggered row 300mm apart and at 500mm centres in each row. To be maintained at 1m height and 1.5m height adjacent to site boundaries
- Proposed shrub planting to receive 75mm bark mulch after planting operations
- Proposed mixed native shrub planting to be planted in groups of 5-7no. of each species and as above
- Proposed grass areas to receive good quality amenity grass turves laid in line with good horticultural practices
- Grassland areas to be retained. Patches to be seeded with EMSF Wild flower Mixture to be sown at a swing rate of 1.5g/m²; available from Emorsgate Seeds or similar and approved
- Proposed SUDS area, to be seeded with EM8 (Meadow mixture for wetlands) from Emorsgate or similar and approved.

Cut lines

Planting Schedule on Sheet 2



A	10/07/18	Layout change	PF
Rev	Date	Details	Drawn



HEAD OFFICE
Rodbourne Rail Business Centre, Grange Lane,
Malmesbury, SN16 0ES
Tel: 01666 825646

Courtyard House, Mill Lane, Godalming, GU7 1EY
Tel: 01483 425714

Suite 6, Crescent House, Yonge Close, Eastleigh, SO50 9SX
Tel: 02382 026500

9 Brownlow Road, Cambridge, CB4 3NC
Tel: 07825 868654

email: mail@acdenv.co.uk
www.acdenvironmental.co.uk



scheme: Land West of New Barn
Lane, North Bersted
(90 units)

client: Linden Homes
drawing: Landscape Proposals
date: June 2018

scale: 1:200@A1

drawing no: LIN21257 11 Sheet 2

drawn: DC checked: AE

Copyright of ACD Environmental Ltd. All rights described in Chapter IV of the Copyright, Designs and Patents Act 1988 have been generally asserted. 2011. Copyright of this plan remains with ACD until all fees have been paid in full.

Planting Schedule

Trees	Species Name	Girth	Height	Density	Specification	No.
	Sorbus torminalis	60-80cm	1Ctr		1+2 Transplant Multi-Stemmed BR	19No
	Acer campestre	80-100cm	3/m ²		Transplant BR	107No
	Crataegus monogyna	80-100cm	3/m ²		Transplant BR	107No
	Malus sylvestris	100-125cm	3/m ²		Feather BR	107No
	Crataegus monogyna	100-125cm	1Ctr		Bushy 1/3 brks BR	81No
	Ilex aquifolium	100-125cm	1Ctr		3 brks C	6No
	Crataegus monogyna	100-125cm	5Ctr Double Staggered at 0.5m offset		Transplant BR	47No
	Betula nira	175-200cm	1Ctr		Feather 2x BR	19No
	Ilex aquifolium	10-12cm	250-300cm	Counted	Standard Clear Stem 175-200 RB	2No
	Malus sylvestris	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	5No
	Acer campestre	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	3No
	Betula pendula 'Youngii'	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	2No
	Acer rubrum 'October Glory'	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	4No
	Carpinus betulus	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	5No
	Lilja cordata	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	8No
	Betula albosinensis 'Fascination'	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem 175-200 RB	119No
	Betula pendula	12-14cm	350-425cm	Counted	Heavy Standard Clear Stem min. 200 RB	3No

Shrubs

Species Name	Height	Pot Size	Specification	Density	No.
Abelia grandiflora 'Kaleidoscope'	30-40cm	3L	Bushy	4/m ²	130No
Berberis media 'Red Jewel'	30-40cm	3L	Bushy C	4/m ²	117No
Buxus sempervirens	30-40cm	3L	Branched C	0.5Ctr	158No
Carpinus betulus	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	39No
Cistus x hybridus	30-40cm	3L	Bushy	4/m ²	145No
Clethra alnifolia 'Paniculata'	20-30cm	3L	Branched BR	1Ctr	61No
Cornus alba	40-60cm	3L	Bushy	4/m ²	19No
Cornus kousa var. chinensis	150-175cm	10L	7 leaves	Counted	5No
Cornus sanguinea	30-40cm	3L	Bushy BR	3/m ²	107No
Corylus avellana	100-125cm	3L	Branched BR	3/m ²	107No
Corylus avellana	60-80cm	3L	Branched BR	0.5Ctr Double Staggered at 0.5m offset	107No
Cotoneaster 'Coral Beauty'	30-40cm	3L	Bushy	4/m ²	25No
Crataegus monogyna	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	179No
Euonymus europaeus	60-80cm	3L	Bushy BR	3/m ²	107No
Euonymus fortunei 'Emerald Gaiety'	60-80cm	5L	Bushy C	4/m ²	94No
Euonymus japonicus 'Paloma Blanca'	40-60cm	5L	Bushy C	4/m ²	267No
Hamamelis intermedia 'Ruby Glow'	10L	7 leaves	Counted		3No
Hebe franciscana 'Blue Gem'	30-40cm	3L	Bushy	4/m ²	112No
Hippophae rhamnoides	60-80cm	3L	Branched 3 brks BR	1Ctr	19No
Hydrangea paniculata 'Grandiflora'	20-30cm	3L	Bushy	4/m ²	121No
Ilex aquifolium	30-40cm	2L	Bushy	0.5Ctr Double Staggered at 0.5m offset	10No
Leucothoe walteri 'Nana'	20-30cm	3L	Bushy	4/m ²	179No
Ligustrum ovalifolium	100-125cm	3L	Bushy 3 brks RB	1Ctr	12No
Ligustrum ovalifolium	60-80cm	3L	Bushy	0.5Ctr Double Staggered at 0.5m offset	1902No
Ligustrum vulgare	100-125cm	3L	7 leaves	0.5Ctr Double Staggered at 0.5m offset	28No
Magnolia 'Susan'	10L	7 leaves	Counted		8No
Mahonia media 'Winter Sun'	40-60cm	5L	Bushy C	4/m ²	72No
Nandina domestica 'Nana Purpurea'	30-40cm	3L	Bushy	4/m ²	41No
Olearia haastii	30-40cm	3L	Bushy	4/m ²	109No
Osmanthus burkwoodii	30-40cm	3L	Bushy	4/m ²	83No
Philadelphus 'Belle Etoile'	30-40cm	3L	Bushy	4/m ²	105No
Photinia fraseri 'Little red robin'	40-60cm	5L	Bushy C	4/m ²	152No
Pittosporum tenuifolium 'Golf Ball'	40-60cm	3L	Bushy	4/m ²	166No
Potentilla fruticosa 'Red Ace'	30-40cm	3L	Bushy	4/m ²	87No
Prunus spinosa	30-100cm	3L	Bushy BR	3/m ²	107No
Rosa 'Bambino'	40-60cm	5L	Bushy C	4/m ²	63No
Salix caprea	60-80cm	3L	Branched BR	3/m ²	107No
Salix cinerea	60-80cm	3L	0/1 5/6 brks BR Branched	1Ctr	28No
Salix purpurea	60-80cm	3L	0/1 5/6 brks BR Branched	1Ctr	19No
Salix triandra	60-80cm	3L	0/1 5/6 brks BR Branched	1Ctr	28No
Salvia officinalis 'Purpurascens'	40-60cm	5L	Bushy C	4/m ²	76No
Sambucus nigra	80-100cm	3L	Bushy BR	3/m ²	107No
Sambucus nigra	80-100cm	3L	Bushy 3 brks RB	1Ctr	12No
Sarcococca hookeriana digyna	20-30cm	3L	Bushy	4/m ²	181No
Skimmia japonica 'Kew White'	20-30cm	3L	7 leaves	4/m ²	129No
Syringa meyeri 'Palibin'	30-40cm	10L	Bushy C	Counted	246No
Viburnum davidii	30-40cm	3L	Bushy C	4/m ²	19No
Viburnum lantana	60-80cm	3L	1+1 Bushy BR	1Ctr	107No
Viburnum opulus	60-80cm	3L	Bushy BR	3/m ²	27No
Viburnum opulus	60-80cm	3L	Bushy BR	1Ctr	27No
Viburnum tinus 'Eve Price'	20-30cm	3L	Bushy	4/m ²	

Herbaceous

Species Name	Pot Size	Specification	Density	No.
Bergenia 'Siberlicht'	3L	Full Pot	7/m ²	71No
Geranium 'Johnson's Blue'	3L	C	4/m ²	150No
Thymus serpyllum	3L	C	4/m ²	35No

11 Sheet 5

11 Sheet 4

11 Sheet 3

11 Sheet 1

11 Sheet 2