



NOTES

Topsoil

Any topsoil imported to the site to be economy grade topsoil to BS 3882 with a minimum of 6% organic matter by dry weight. Topsoil to be 400mm deep over 400mm thoroughly broken up subsoil.

Planting

Barcham Trees or Hillier Trees would be suitable suppliers.

Landscaping contractors to be BALI approved.

All trees to be to National Plant Specification and BS5854:2014, Trees from nursery to independence in the landscape, Recommendations and handled and planted to Handling and Establishing Landscape Plants (CPSE, 1994).

Trees to be staked with two short stakes and cross-bar 600mm above ground level held with block and strap tie.

Mulching

Plant beds to be mulched with 100mm deep green waste compost, mulch grade, to PAS 100 or 100mm conifer bark mulch 100mm down with a maximum of 20% fines (below 5mm).


Management

All new planting to be watered as required to maintain it in a healthy condition during the critical first established season. In future years watering to be undertaken as required to maintain healthy and vigorous growth.

All dead or dying back trees to be replaced with trees to same specification in November following losses.

All areas to be maintained weed free for a minimum of five years with a maximum of four weeks weed growth at any one time.

Tree stakes to be removed in April after first growing season if possible or the following April. Ties to be checked every four weeks and secured as necessary. Side branches and basal shoots on trees to be removed each July to maintain a 2m trunk free of branches.



- ~~Cut back trees which are overhanging perimeter fence~~



01622 437196 lydia@hwandco.co.uk www.hwandco.co.uk

2 Keswick Drive, Maidstone, Kent ME16 0DQ Hill-Wood & Co (Kent) Ltd Company no. 10066666

PLANNING

Project

-

BARTON COUNTY INFANTS SCHOOL

Drawing title

-

Landscape planting plan

Rev	Description	Date
A	Minor amendment	07.17
B	ReRoot 2000 details added	07.17
-	-	-

Scale

Date

Drawing number

Rev

1:250@A2
1:500@A4

Jul 2017

0032/17/B/1B

1B