

GrufeKit Sedum Tiles



Your GrufeTile will be supplied with established plant coverage, growing on 60mm 100% recycled growing media. The 3 layers of the green roof tile are:

- **Vegetation:** A mix of 20-30 wildflower and meadow grass varieties and 8-12 varieties of sedum
- **Soil:** The media mix used is a special substrate prepared specifically for the GrufeTile
- **Carrier:** Made from recycled HDPE plastic, the carrier acts as a water reservoir, drainage layer

Carrier Dimensions (mm)	540 x 540 x 90 (sold per m ²)
Compressive strength	2.000kg/m ²
Water holding capacity	20l/m ²
Temperature range	-50 °C - +80 °C
Drainage surface	318cm ² /m ²
Outflow volume	40 l/m ²
Saturated weight	65kg/m ²
Guarantee	10 years