

ALL DELIVERIES & EXITS
FROM TO A27 DIRECTION

2.04 Meters width of site
Access Planning of Site

2.04 Meters width of
Access Planning of Site

SITE CONDUIT &
VEHICLE UNITS
SITE OBSERVATION
PARKING
SHIP YARD
AREA

Access/Storage area
4 VEHICLE TURNING AREA

Part of site
Storage Area

Yaron Rd
Bentham

6.6m

Dust Suppression Barnham

To mitigate the nuisance caused by dust, debris and mud during works carried out on the above development, the following items will be instigated:-

- a) The site roads will be kept clean.
- b) Access Road to the Public Highway will be kept clean, in partnership with Contractors carrying out works on the adjacent development on the access road.
- c) A Speed Limit of 10mph will be enforced for traffic when entering and within the development.
- d) Forklift movement around the site will be restricted to hardstanding areas only. In the event of the forklift going outside the designated areas then the machine is to be cleaned of any mud so that the migration of mud is removed.
- e) Material stacking areas are to be accessible by temporary or permanent roads. The delivery vehicles will stay on these surfaces, and they are to be checked to ensure they are clean prior to leaving the site.
- f) In the event wheel washing is required, then a jet wash and brush will be made available and any resultant debris is removed.
- g) Where surplus excavated material is stored on site, then it will be covered to reduce dust migration if required.
- h) Damping down of any area's that may cause dust during dry weather will be carried out if required.
- i) Material will be delivered to correct dimensions to reduce dust as a result of cutting.
- j) Where machine cutting is required, which would be a last resort, then a dust suppression unit must be applied to the machine.
- k) Noise levels will be kept to a minimum, and Noise Risk Assessments will be carried out where the noise level is likely to exceed 80 and 85dB.
- l) All Works Contractors and Suppliers will be instructed to adhere to the site rules.