

- KEY
- Disabled Parking Space
 - Electric Charging Space
 - HV Electric Main
 - Gas Main
 - Water Main
 - Site Boundary

ONLY SCALE FOR PLANNING PURPOSES

Copyright © 2020 Wesliden Agricultural Marketing Ltd.
All rights reserved. Any layout or design contained within this drawing remains the
intellectual property right of Wesliden Agricultural Marketing Ltd and shall not be released to
third parties without the written consent of Wesliden Agricultural Marketing Ltd.
No part of this drawing may be altered, copied, reproduced, scanned, or
photocopied without the written consent of Wesliden Agricultural Marketing Ltd.
Neither may this drawing or part of it be used for any purpose other than for which
it was issued without the written consent of Wesliden Agricultural Marketing Ltd.

NOTE:
Position of proposed Electricity
Cable routes indicative only.

Unit A	
Basement	110 m ²
Ground Floor	1,880 m ²
Mezzanine	1,540 m ²
Total	3,530 m ²
Unit B	
Basement	200 m ²
Ground Floor	1,095 m ²
Mezzanine	150 m ²
Total	1,445 m ²
Total Floor Area	4,975 m ²



The Stableyard, North Road, Bodle Street Green
Hailsham, East Sussex, BN27 4RG
Tel: 01323 833088 Mobile: 07836 588181
E-mail: office@weslidenam.com

GTR
Arundel Road
Fontwell Walberton
West Sussex, BN18 0SB

DRAWINGS

Proposed Industrial Unit
Arundel Road, Fontwell
Block Plan



REV	DESCRIPTION	DATE	BY
Rev. 1	Final Plan and Water Compounds and free canopy added	20-05-21	SAK
Rev. 2	Adjustment to Car Parking Cycle Parking North West Corner	20-05-21	SAK
Rev. 3	Adjustment to Car Parking Cycle Parking North West Corner	20-05-21	SAK
Rev. 4	Minor Electrical Supply route revised	24-05-21	SAK
Rev. 5	Paving revised	24-05-21	SAK
Rev. 6	Services roads added	04-06-21	SAK

SCALE	1 : 500 on A2	DRAWN	SAK
-------	---------------	-------	-----

Static water tank details for WSFR

One. Circular Water Tank manufactured from curved corrugated galvanised steel.
Model 15/4, 15' dia. (4.61m) 10' (3.04m) high. Nominal capacity 54,000 lts
One. 1mm thick Butyl liner for above.
One. 10 degree galvanised steel roof c/w hatch at eaves.
One. 4" dia BSP Stainless steel take off unit
One. 4" British BSRT as requested
One. Enclosure to bolt to the tank side, this covers and protects the incoming water supply pipe
Note colour to match building cladding as listed below
Main colour will be Anthracite Grey RAL 7016, together with Merlin Grey RAL roof