

Paul Basham Associates		Page 1
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOT 4 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:05 File 108.5009 - PLOT 4.SRCX	Designed by RD Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+40%)

Half Drain Time : 854 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	15.702	0.315	0.0	2.1	O K
30 min Summer	15.815	0.428	0.0	2.8	O K
60 min Summer	15.937	0.550	0.0	3.7	O K
120 min Summer	16.061	0.674	0.1	4.5	O K
180 min Summer	16.126	0.739	0.1	4.9	O K
240 min Summer	16.165	0.778	0.1	5.2	O K
360 min Summer	16.213	0.826	0.1	5.5	O K
480 min Summer	16.237	0.850	0.1	5.7	O K
600 min Summer	16.249	0.862	0.1	5.7	O K
720 min Summer	16.259	0.872	0.1	5.8	O K
960 min Summer	16.271	0.884	0.1	5.9	O K
1440 min Summer	16.279	0.892	0.1	5.9	O K
2160 min Summer	16.267	0.880	0.1	5.9	O K
2880 min Summer	16.243	0.856	0.1	5.7	O K
4320 min Summer	16.187	0.800	0.1	5.3	O K
5760 min Summer	16.134	0.747	0.1	5.0	O K
7200 min Summer	16.087	0.700	0.1	4.7	O K
8640 min Summer	16.046	0.659	0.1	4.4	O K
10080 min Summer	16.010	0.623	0.1	4.1	O K
15 min Winter	15.740	0.353	0.0	2.3	O K
30 min Winter	15.866	0.479	0.0	3.2	O K
60 min Winter	16.003	0.616	0.1	4.1	O K
120 min Winter	16.142	0.755	0.1	5.0	O K
180 min Winter	16.216	0.829	0.1	5.5	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	125.250	0.0	19
30 min Summer	85.368	0.0	34
60 min Summer	55.544	0.0	64
120 min Summer	34.816	0.0	122
180 min Summer	26.038	0.0	182
240 min Summer	21.042	0.0	242
360 min Summer	15.601	0.0	360
480 min Summer	12.593	0.0	480
600 min Summer	10.656	0.0	536
720 min Summer	9.290	0.0	592
960 min Summer	7.475	0.0	712
1440 min Summer	5.489	0.0	982
2160 min Summer	4.021	0.0	1388
2880 min Summer	3.220	0.0	1792
4320 min Summer	2.348	0.0	2596
5760 min Summer	1.878	0.0	3400
7200 min Summer	1.581	0.0	4176
8640 min Summer	1.373	0.0	4928
10080 min Summer	1.219	0.0	5648
15 min Winter	125.250	0.0	19
30 min Winter	85.368	0.0	33
60 min Winter	55.544	0.0	62
120 min Winter	34.816	0.0	120
180 min Winter	26.038	0.0	180

Paul Basham Associates		Page 2
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOT 4 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:05 File 108.5009 - PLOT 4.SRCX	Designed by RD Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+40%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
240 min Winter	16.260	0.873	0.1	5.8	O K
360 min Winter	16.317	0.930	0.1	6.2	O K
480 min Winter	16.346	0.959	0.1	6.4	O K
600 min Winter	16.360	0.973	0.1	6.5	O K
720 min Winter	16.366	0.979	0.1	6.5	O K
960 min Winter	16.377	0.990	0.1	6.6	O K
1440 min Winter	16.374	0.987	0.1	6.6	O K
2160 min Winter	16.341	0.954	0.1	6.3	O K
2880 min Winter	16.298	0.911	0.1	6.1	O K
4320 min Winter	16.211	0.824	0.1	5.5	O K
5760 min Winter	16.136	0.749	0.1	5.0	O K
7200 min Winter	16.072	0.685	0.1	4.6	O K
8640 min Winter	16.019	0.632	0.1	4.2	O K
10080 min Winter	15.974	0.587	0.1	3.9	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
240 min Winter	21.042	0.0	238
360 min Winter	15.601	0.0	350
480 min Winter	12.593	0.0	462
600 min Winter	10.656	0.0	566
720 min Winter	9.290	0.0	656
960 min Winter	7.475	0.0	742
1440 min Winter	5.489	0.0	1052
2160 min Winter	4.021	0.0	1492
2880 min Winter	3.220	0.0	1932
4320 min Winter	2.348	0.0	2764
5760 min Winter	1.878	0.0	3576
7200 min Winter	1.581	0.0	4328
8640 min Winter	1.373	0.0	5104
10080 min Winter	1.219	0.0	5856

Paul Basham Associates		Page 3
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOT 4 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:05	Designed by RD	
File 108.5009 - PLOT 4.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.600	Shortest Storm (mins)	15
Ratio R	0.322	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time Area Diagram

Total Area (ha) 0.009

Time (mins) Area
From: To: (ha)

0 4 0.009

Paul Basham Associates		Page 4
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOT 4 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:05 File 108.5009 - PLOT 4.SRCX	Designed by RD Checked by RW	
Innovyze Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 17.600

Cellular Storage Structure

Invert Level (m) 15.387 Safety Factor 4.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.11800

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	7.0	7.0	1.200	7.0	19.7	1.201	0.0	19.7