

Paul Basham Associates		Page 1
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOTS 35-39 REV A SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 15/09/2021	Designed by RD	
File 108.5009 - PLOT 35-39 REV A.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+40%)

Half Drain Time : 1361 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	15.596	0.049	0.1	6.5	O K
30 min Summer	15.614	0.067	0.1	8.9	O K
60 min Summer	15.633	0.086	0.1	11.5	O K
120 min Summer	15.654	0.107	0.1	14.2	O K
180 min Summer	15.665	0.118	0.1	15.7	O K
240 min Summer	15.672	0.125	0.1	16.6	O K
360 min Summer	15.682	0.135	0.1	18.0	O K
480 min Summer	15.688	0.141	0.2	18.8	O K
600 min Summer	15.692	0.145	0.2	19.3	O K
720 min Summer	15.695	0.148	0.2	19.6	O K
960 min Summer	15.697	0.150	0.2	20.0	O K
1440 min Summer	15.700	0.153	0.2	20.4	O K
2160 min Summer	15.702	0.155	0.2	20.6	O K
2880 min Summer	15.701	0.154	0.2	20.4	O K
4320 min Summer	15.696	0.149	0.2	19.8	O K
5760 min Summer	15.690	0.143	0.2	19.0	O K
7200 min Summer	15.684	0.137	0.1	18.2	O K
8640 min Summer	15.678	0.131	0.1	17.4	O K
10080 min Summer	15.673	0.126	0.1	16.7	O K
15 min Winter	15.602	0.055	0.1	7.3	O K
30 min Winter	15.622	0.075	0.1	9.9	O K
60 min Winter	15.644	0.097	0.1	12.9	O K
120 min Winter	15.666	0.119	0.1	15.9	O K
180 min Winter	15.679	0.132	0.1	17.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	125.250	0.0	23
30 min Summer	85.368	0.0	38
60 min Summer	55.544	0.0	68
120 min Summer	34.816	0.0	126
180 min Summer	26.038	0.0	186
240 min Summer	21.042	0.0	246
360 min Summer	15.601	0.0	364
480 min Summer	12.593	0.0	482
600 min Summer	10.656	0.0	602
720 min Summer	9.290	0.0	720
960 min Summer	7.475	0.0	858
1440 min Summer	5.489	0.0	1086
2160 min Summer	4.021	0.0	1480
2880 min Summer	3.220	0.0	1904
4320 min Summer	2.348	0.0	2724
5760 min Summer	1.878	0.0	3520
7200 min Summer	1.581	0.0	4320
8640 min Summer	1.373	0.0	5104
10080 min Summer	1.219	0.0	5856
15 min Winter	125.250	0.0	23
30 min Winter	85.368	0.0	37
60 min Winter	55.544	0.0	66
120 min Winter	34.816	0.0	124
180 min Winter	26.038	0.0	182

Paul Basham Associates		Page 2
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOTS 35-39 REV A SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 15/09/2021	Designed by RD	
File 108.5009 - PLOT 35-39 REV A.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+40%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
240 min Winter	15.687	0.140	0.2	18.7	O K
360 min Winter	15.699	0.152	0.2	20.2	O K
480 min Winter	15.706	0.159	0.2	21.1	O K
600 min Winter	15.711	0.164	0.2	21.8	O K
720 min Winter	15.714	0.167	0.2	22.2	O K
960 min Winter	15.717	0.170	0.2	22.6	O K
1440 min Winter	15.719	0.172	0.2	22.8	O K
2160 min Winter	15.718	0.171	0.2	22.8	O K
2880 min Winter	15.715	0.168	0.2	22.4	O K
4320 min Winter	15.706	0.159	0.2	21.1	O K
5760 min Winter	15.696	0.149	0.2	19.8	O K
7200 min Winter	15.687	0.140	0.2	18.6	O K
8640 min Winter	15.679	0.132	0.1	17.6	O K
10080 min Winter	15.672	0.125	0.1	16.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
240 min Winter	21.042	0.0	240
360 min Winter	15.601	0.0	356
480 min Winter	12.593	0.0	472
600 min Winter	10.656	0.0	584
720 min Winter	9.290	0.0	694
960 min Winter	7.475	0.0	906
1440 min Winter	5.489	0.0	1126
2160 min Winter	4.021	0.0	1584
2880 min Winter	3.220	0.0	2044
4320 min Winter	2.348	0.0	2900
5760 min Winter	1.878	0.0	3752
7200 min Winter	1.581	0.0	4544
8640 min Winter	1.373	0.0	5368
10080 min Winter	1.219	0.0	6152

Paul Basham Associates		Page 3
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOTS 35-39 REV A SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 15/09/2021	Designed by RD	
File 108.5009 - PLOT 35-39 REV A.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.600	Shortest Storm (mins)	15
Ratio R	0.322	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time Area Diagram

Total Area (ha) 0.028

Time (mins)	Area	Time (mins)	Area
From: To:	(ha)	From: To:	(ha)
0 4	0.014	4 8	0.014

Paul Basham Associates		Page 4
Lancaster Court Fareham Hampshire, PO15 5TU	1:100+40%CC PLOTS 35-39 REV A SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 15/09/2021	Designed by RD	
File 108.5009 - PLOT 35-39 REV A.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Model Details

Storage is Online Cover Level (m) 17.900

Cellular Storage Structure

Invert Level (m) 15.547 Safety Factor 4.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.30852

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	140.0	140.0	0.800	140.0	180.8	0.801	0.0	180.8