

Paul Basham Associates		Page 1
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 7 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:09 File 108.5009 - PLOT 7.SRCX	Designed by RD Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 10 year Return Period (+40%)

Half Drain Time : 433 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	15.674	0.124	0.0	1.4	O K
30 min Summer	15.714	0.164	0.0	1.9	O K
60 min Summer	15.756	0.206	0.1	2.3	O K
120 min Summer	15.797	0.247	0.1	2.8	O K
180 min Summer	15.818	0.268	0.1	3.1	O K
240 min Summer	15.829	0.279	0.1	3.2	O K
360 min Summer	15.841	0.291	0.1	3.3	O K
480 min Summer	15.849	0.299	0.1	3.4	O K
600 min Summer	15.855	0.305	0.1	3.5	O K
720 min Summer	15.858	0.308	0.1	3.5	O K
960 min Summer	15.861	0.311	0.1	3.5	O K
1440 min Summer	15.857	0.307	0.1	3.5	O K
2160 min Summer	15.844	0.294	0.1	3.3	O K
2880 min Summer	15.829	0.279	0.1	3.2	O K
4320 min Summer	15.801	0.251	0.1	2.9	O K
5760 min Summer	15.778	0.228	0.1	2.6	O K
7200 min Summer	15.760	0.210	0.1	2.4	O K
8640 min Summer	15.745	0.195	0.1	2.2	O K
10080 min Summer	15.732	0.182	0.1	2.1	O K
15 min Winter	15.689	0.139	0.0	1.6	O K
30 min Winter	15.734	0.184	0.1	2.1	O K
60 min Winter	15.781	0.231	0.1	2.6	O K
120 min Winter	15.828	0.278	0.1	3.2	O K
180 min Winter	15.851	0.301	0.1	3.4	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	76.566	0.0	19
30 min Summer	51.183	0.0	33
60 min Summer	32.926	0.0	62
120 min Summer	20.664	0.0	122
180 min Summer	15.602	0.0	180
240 min Summer	12.744	0.0	240
360 min Summer	9.573	0.0	298
480 min Summer	7.806	0.0	358
600 min Summer	6.660	0.0	422
720 min Summer	5.849	0.0	492
960 min Summer	4.762	0.0	626
1440 min Summer	3.561	0.0	906
2160 min Summer	2.660	0.0	1300
2880 min Summer	2.162	0.0	1700
4320 min Summer	1.613	0.0	2464
5760 min Summer	1.311	0.0	3224
7200 min Summer	1.116	0.0	3960
8640 min Summer	0.978	0.0	4672
10080 min Summer	0.875	0.0	5440
15 min Winter	76.566	0.0	19
30 min Winter	51.183	0.0	33
60 min Winter	32.926	0.0	62
120 min Winter	20.664	0.0	120
180 min Winter	15.602	0.0	176

Paul Basham Associates		Page 2
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 7 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:09 File 108.5009 - PLOT 7.SRCX	Designed by RD Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 10 year Return Period (+40%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
240 min Winter	15.864	0.314	0.1	3.6	O K
360 min Winter	15.877	0.327	0.1	3.7	O K
480 min Winter	15.885	0.335	0.1	3.8	O K
600 min Winter	15.889	0.339	0.1	3.9	O K
720 min Winter	15.891	0.341	0.1	3.9	O K
960 min Winter	15.889	0.339	0.1	3.9	O K
1440 min Winter	15.877	0.327	0.1	3.7	O K
2160 min Winter	15.853	0.303	0.1	3.4	O K
2880 min Winter	15.829	0.279	0.1	3.2	O K
4320 min Winter	15.791	0.241	0.1	2.7	O K
5760 min Winter	15.762	0.212	0.1	2.4	O K
7200 min Winter	15.739	0.189	0.1	2.2	O K
8640 min Winter	15.721	0.171	0.1	2.0	O K
10080 min Winter	15.707	0.157	0.0	1.8	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
240 min Winter	12.744	0.0	232
360 min Winter	9.573	0.0	330
480 min Winter	7.806	0.0	372
600 min Winter	6.660	0.0	448
720 min Winter	5.849	0.0	526
960 min Winter	4.762	0.0	674
1440 min Winter	3.561	0.0	966
2160 min Winter	2.660	0.0	1384
2880 min Winter	2.162	0.0	1788
4320 min Winter	1.613	0.0	2552
5760 min Winter	1.311	0.0	3336
7200 min Winter	1.116	0.0	4040
8640 min Winter	0.978	0.0	4840
10080 min Winter	0.875	0.0	5544

Paul Basham Associates		Page 3
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 7 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:09	Designed by RD	
File 108.5009 - PLOT 7.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	10	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.600	Shortest Storm (mins)	15
Ratio R	0.322	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time Area Diagram

Total Area (ha) 0.010

Time (mins) Area
From: To: (ha)

0 4 0.010

Paul Basham Associates		Page 4
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 7 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:09 File 108.5009 - PLOT 7.SRCX	Designed by RD Checked by RW	
Innovyze Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 17.100

Cellular Storage Structure

Invert Level (m) 15.550 Safety Factor 4.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.30852

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	12.0	12.0	0.800	12.0	23.1	0.801	0.0	23.1