

Paul Basham Associates		Page 1
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 26 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:38	Designed by CLP	
File 108.5009 - PLOT 26.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Summary of Results for 10 year Return Period (+40%)

Half Drain Time : 399 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m ³)	Status
15 min Summer	16.530	0.170	0.0	1.7	O K
30 min Summer	16.584	0.224	0.1	2.2	O K
60 min Summer	16.642	0.282	0.1	2.8	O K
120 min Summer	16.697	0.337	0.1	3.4	O K
180 min Summer	16.723	0.363	0.1	3.6	O K
240 min Summer	16.737	0.377	0.1	3.8	O K
360 min Summer	16.754	0.394	0.1	3.9	O K
480 min Summer	16.765	0.405	0.1	4.0	O K
600 min Summer	16.772	0.412	0.1	4.1	O K
720 min Summer	16.776	0.416	0.1	4.1	O K
960 min Summer	16.778	0.418	0.1	4.2	O K
1440 min Summer	16.771	0.411	0.1	4.1	O K
2160 min Summer	16.751	0.391	0.1	3.9	O K
2880 min Summer	16.729	0.369	0.1	3.7	O K
4320 min Summer	16.690	0.330	0.1	3.3	O K
5760 min Summer	16.660	0.300	0.1	3.0	O K
7200 min Summer	16.635	0.275	0.1	2.7	O K
8640 min Summer	16.614	0.254	0.1	2.5	O K
10080 min Summer	16.597	0.237	0.1	2.4	O K
15 min Winter	16.550	0.190	0.1	1.9	O K
30 min Winter	16.612	0.252	0.1	2.5	O K
60 min Winter	16.676	0.316	0.1	3.2	O K
120 min Winter	16.739	0.379	0.1	3.8	O K
180 min Winter	16.769	0.409	0.1	4.1	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m ³)	Time-Peak (mins)
15 min Summer	76.566	0.0	19
30 min Summer	51.183	0.0	33
60 min Summer	32.926	0.0	62
120 min Summer	20.664	0.0	122
180 min Summer	15.602	0.0	180
240 min Summer	12.744	0.0	238
360 min Summer	9.573	0.0	288
480 min Summer	7.806	0.0	350
600 min Summer	6.660	0.0	418
720 min Summer	5.849	0.0	486
960 min Summer	4.762	0.0	624
1440 min Summer	3.561	0.0	896
2160 min Summer	2.660	0.0	1296
2880 min Summer	2.162	0.0	1676
4320 min Summer	1.613	0.0	2424
5760 min Summer	1.311	0.0	3176
7200 min Summer	1.116	0.0	3896
8640 min Summer	0.978	0.0	4672
10080 min Summer	0.875	0.0	5352
15 min Winter	76.566	0.0	19
30 min Winter	51.183	0.0	33
60 min Winter	32.926	0.0	62
120 min Winter	20.664	0.0	120
180 min Winter	15.602	0.0	176

Paul Basham Associates		Page 2
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 26 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:38 File 108.5009 - PLOT 26.SRCX	Designed by CLP Checked by RW	
Innovyze Source Control 2020.1.3		

Summary of Results for 10 year Return Period (+40%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Volume (m³)	Status
240 min Winter	16.786	0.426	0.1	4.3	O K
360 min Winter	16.802	0.442	0.1	4.4	O K
480 min Winter	16.812	0.452	0.1	4.5	O K
600 min Winter	16.817	0.457	0.1	4.6	O K
720 min Winter	16.818	0.458	0.1	4.6	O K
960 min Winter	16.814	0.454	0.1	4.5	O K
1440 min Winter	16.795	0.435	0.1	4.3	O K
2160 min Winter	16.760	0.400	0.1	4.0	O K
2880 min Winter	16.728	0.368	0.1	3.7	O K
4320 min Winter	16.675	0.315	0.1	3.1	O K
5760 min Winter	16.635	0.275	0.1	2.7	O K
7200 min Winter	16.605	0.245	0.1	2.4	O K
8640 min Winter	16.582	0.222	0.1	2.2	O K
10080 min Winter	16.563	0.203	0.1	2.0	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Time-Peak (mins)
240 min Winter	12.744	0.0	230
360 min Winter	9.573	0.0	296
480 min Winter	7.806	0.0	368
600 min Winter	6.660	0.0	446
720 min Winter	5.849	0.0	520
960 min Winter	4.762	0.0	672
1440 min Winter	3.561	0.0	954
2160 min Winter	2.660	0.0	1364
2880 min Winter	2.162	0.0	1760
4320 min Winter	1.613	0.0	2548
5760 min Winter	1.311	0.0	3288
7200 min Winter	1.116	0.0	4040
8640 min Winter	0.978	0.0	4760
10080 min Winter	0.875	0.0	5544

Paul Basham Associates		Page 3
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 26 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:38	Designed by CLP	
File 108.5009 - PLOT 26.SRCX	Checked by RW	
Innovyze	Source Control 2020.1.3	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	10	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.600	Shortest Storm (mins)	15
Ratio R	0.322	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+40

Time Area Diagram

Total Area (ha) 0.012

Time (mins)	Area
From:	To: (ha)

0	4 0.012
---	---------

Paul Basham Associates		Page 4
Lancaster Court Fareham Hampshire, PO15 5TU	1:10+40%CC PLOT 26 SIDE INFILTRATION ONLY INFILTRATION CRATES	
Date 28/10/2021 09:38 File 108.5009 - PLOT 26.SRCX	Designed by CLP Checked by RW	
Innovyze Source Control 2020.1.3		

Model Details

Storage is Online Cover Level (m) 17.700

Cellular Storage Structure

Invert Level (m) 16.360 Safety Factor 4.0
Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95
Infiltration Coefficient Side (m/hr) 0.30852

Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)	Depth (m)	Area (m ²)	Inf. Area (m ²)
0.000	10.5	10.5	0.800	10.5	20.9	0.801	0.0	20.9