

Planting Area No. 08

14 no. Lonicera nitida 'May Green'; 3L; 3p/m

28 no. Lonicera nitida 'May Green'; 3L; 3p/m

Planting Area No. 09

15 no. Sarcococca hookeriana var. humilis; 2L; 4p/m

1 no. Cornus mas; 15L

18 no. Vinca major 'Variegata'; 2L; 4p/m

2 no. Skimmia japonica; 7L

1 no. Philadelphus 'Belle Etoile'; 10Ltr

12 no. Viburnum davidii 'Compactum'; 3L; 3p/m

1 no. Skimmia japonica; 7L

1 no. Cornus mas; 15L

Planting Area No. 10

Proposed Ornamental Tree Planting
2 no. Amelanchier arborea 'Robin Hill';
14 - 16 cm Girth Size; 4.25 - 6.0 m height;
Standard Extra Heavy

9 no. Rosmarinus 'Miss Jessop's Upright'; 3L; 3p/m

1 no. Weigela 'Florida Variegata'; 7L

18 no. Vinca major 'Variegata'; 2L; 4p/m

3 no. Abelia x grandiflora; 7L

1 no. Cotinus coggygia 'Royal Purple'; 15L

Planting Area No. 11

15 no. Lonicera nitida 'May Green'; 3L; 3p/m

20 no. Sarcococca hookeriana var.humilis;
2L; 4p/m

Proposed Ornamental Tree Planting
1 no. Sorbus aria 'Lutescens'
14 - 16 cm Girth Size; 4.25 - 6.0 m height;
Standard Extra Heavy

40 no. Escallonia 'Apple Blossom'; 3L; 3p/m

1 no. Spirea cinerea 'Grefsheim'; 10L

21 no. Lonicera pileata; 3L; 3p/m

1 no. Spirea cinerea 'Grefsheim'; 10L

15 no. Sarcococca hookeriana var. humilis; 2L; 4p/m

1 no. Ribes sanguineum 'Pulborough Scarlet'; 10L

21 no. Vinca major 'Variegata'; 2L; 4p/m

2 no. Photinia x fraseri 'Little Red Robin'; 5L

1 no. Philadelphus 'Belle Etoile'; 10Ltr

12 no. Viburnum davidii 'Compactum'; 3L; 3p/m

1 no. Skimmia japonica; 7L

1 no. Spirea cinerea 'Grefsheim'; 10L

Planting Area No. 12

Proposed Ornamental Tree Planting
1 no. Gleditsia triacanthus 'Sunburst'
14 - 16 cm Girth Size; 4.25 - 6.0 m height;
Standard Extra Heavy

1 no. Ribes sanguineum 'Pulborough Scarlet'; 10L

12 no. Viburnum davidii 'Compactum'; 3L; 3p/m

2 no. Sarcococca hookeriana var.humilis; 2L; 4p/m

1 no. Cornus alba 'Ivory Halo'; 10L

2 no. Potentilla fruticosa 'Hopley's Orange'; 7L

17 no. Geranium macrorrhizum 'Bevan's Variety'; 2L; 4p/m

5 no. Sanguisorba officinalis 'Red Thunder'; 2L

4 no. Monarda 'Squaw'; 2L

Planting Area No. 14

3 no. Sarcococca hookeriana var.humilis; 2L; 4p/m

15 no. Hebe 'Autumn Glory'; 3L; 3p/m

12 no. Ceanothus thyrsiflorus repens; 3L; 3p/m

14 no. Spiraea japonica 'Firelight'; 3L; 4p/m

3 no. Sarcococca hookeriana var.humilis; 2L; 4p/m

1 no. Miscanthus sinensis 'Kleine Silberspinne'; 5L

2 no. Miscanthus sinensis 'Kleine Silberspinne'; 5L

12 no. Caryopteris x clandonensis 'Heavenly Blue'; 3L; 3p/m

3 no. Skimmia japonica; 7L


Proposed Ornamental Tree Planting
1 no. Gleditsia triacanthus 'Sunburst'
14 - 16 cm Girth Size; 4.25 - 6.0 m height;
Standard Extra Heavy

3 no. Miscanthus sinensis 'Kleine Silberspinne'; 5L
2 no. Cistus x purpureus; 15L


9 no. Caryopteris x clandonensis 'Heavenly Blue'; 3L; 3p/m

3 no. Skimmia japonica; 7L


Legend




Proposed Native Specimen Tree Planting
(14 - 16 cm girth size; Standard Extra Heavy;
4.25 - 6.0m height).




Proposed Ornamental Specimen Tree Planting
(14 - 16 cm girth size; Standard Extra Heavy;
4.25 - 6.0m height)




Specimen Planting
Specimen Planting Areas to be a minimum of
300 mm depth of subsoil overlain with a
minimum of 450 mm depth of Multi-Purpose
Topsoil to BS:3882; 2015.



Shrub / Groundcover Planting Areas
Shrub / Groundcover Planting Areas to be a
minimum of 300 mm depth of subsoil overlain
with a minimum of 450 mm depth of Multi-
Purpose Topsoil to BS:3882; 2015.



Herbaceous / Bulb Accent Planting
Herbaceous and Bulb Planting Areas to be a
minimum of 300 mm depth of subsoil overlain
with a minimum of 450 mm depth of Multi-
Purpose Topsoil to BS:3882; 2015.



Proposed Native Single Species Hedgerow
Native hedge planting stock; 60 - 80 cm height.
Hedge planting to be single rows; planting at
400 mm centres.
Hedge planting areas to be minimum 300 mm
depth subsoil overlain with a minimum of 450
mm depth of Multi-purpose Topsoil to BS 3882;
2015; mixed with excavated site topsoils.

Proposed - Grass Seeded / Turfed Areas

Proposed grass seeded areas to be minimum 300 mm depth subsoil overlain with a minimum of 150 mm depth of Multi-Purpose Topsoil to BS 3882; 2015. Existing and imported topsoil to be tested and certified by a Soil Scientist. Amenity Grass seeded areas to be seeded with 'A19 (All Purpose Landscaping)'. Lawned Areas to be seeded with 'A2 (Quality Lawn)' supplied by Germinall Seeds Amenity, or equal and approved.

Planting Areas / Mulching

All proposed shrub planting areas to be overlain with 75mm depth Ornamental Bark Mulch. Planting areas to be mulched with fine graded ornamental bark mulch; 5 - 35mm nominal particle size; BS4970:1987.

Tree Planting

All proposed tree planting to be in accordance with BS8545:2014 - 'Trees: from nursery to independence in the landscape - recommendations'.

Tree Pits

- Sizes:
 - 14 - 16cm Girth: 4.25 - 6.0m height (Standard Extra Heavy) :
 - Tree Pit Size: min. 150 mm radially greater than radius of root system / root ball / container.
 - Planting depth; to depth of root system / root ball / container.
 - Backfilling Material
 - Backfill to be consolidated in 150mm depth layers around root system.
 - Composition: Previously prepared mixture of topsoil excavated from pit and additional topsoil as required, together with:
 - Ameliorant / Conditioner: 20 % by volume, together with 20 % volume Tree Planting Compost (8 mm peat free organic compost) supplied by Bourne Amenity, Newenden, Cranbrook, Kent, TN18 5QG. Tel. 01797 252296; Fax: 01797 253115. Email: enquiries@bourne.co.uk, or equal and approved, and 2500 grams of Seamure Soil Builder per tree planting pit;
 - To be supplied by Alginate Products, Stone Hill, Egerton, Ashford, Kent, TN27 9DU. Tel. 01233 756241. Fax: 01233 756419 or equal and approved.
- Upon completion of planting:
 - tree to be watered (saturated to field capacity) and staked.

All staked trees:

- Ties: Adjustable ties.
- Tying: Secure tree firmly but not rigidly with a single tie centrally on brace for long double staking.
- Advanced Nursery Stock (Standard Extra Heavy): Trees to be long double staked; 2 no. 2400 x 75 mm diameter timber stakes driven vertically into the ground to finish 300mm below base of pit; 2 no. per tree.
- Stakes to be cut level at 1000mm height and braced with timber crossbar.

Detailed Planting Plans / Specification

Refer to:
LLD 833 / 05 Soft Landscape Layout and LLD833 Detailed Planting Schedule and Specification

Rev	Description	Date	Initials
01	Planning Issue	24/06/15	KM
00	Planning Issue	19/06/15	KM
--	--	--	--

Lizard Landscape Design

Lizard Landscape Design
19 Broadwater Street East
Worthing
West Sussex
BN14 9AA
Tel. 01903 216033
Fax. 01903 214777
Email: lizardlandscape@btconnect.com



Project title

Land to the North of Yapton Road,
Barnham, West Sussex

Drawing title

Detailed Planting Plans
Residential Planting Proposals

Scale
1:100@A1

Drawn
KM

Date
19.06.15

Drawing No

LLD833 / 07

CAD Filename

LLD833/CADDrawings

Revision

01

Land north of Yapton Road
Residential Areas - Detailed Planting Plans

