Highground

Barn

Proposed native tree planting (min 5m from the stream. The exact location and quantity will need to be verified in the field

Infill gap with native shrub planting

2m

Barnham

Court

Chichester and

Arundel Canal

course of

FALLING GROUND

Lane (Track

Fatting Ground

Proposed hedgerow. Min 2.5 m wayleave between new planting and ditch for maintenance. (Tree planting grouped towards areas where there are larger gaps in existing hedgerow)

Proposed native tree planting (the exact location and quantity will need to be verified in the field.)

Proposed hedgerow along the southeast boundary:

Hedge mix

20%	Acer campestre	(Field Maple)	60-80 cm high transplants
20%	Corylus avellana	(Hazel)	60-80 cm high transplants
20%	Crataegus monogyna	(Hawthorn)	40-60 cm high transplants
20%	Prunus spinosa	(Blackthorn)	40-60 cm high transplants
10%	Rosa canina	(Dog rose)	60-80 cm high transplants
10%	Viburnum opulus	(Guelder Rose)	60-80 cm high transplants

Indicative plan

Southeast boundary only - Planted as 3 staggered rows set 500mm apart, plants along each row at 500mm centres.

To be planted as 60-80cm/40-60cm high transplants.
To be planted randomly in single species groups of 3,5 & 7 plants

All hedgerows to be grown up to a maximum height of 3m. The existing hedgerows are to be managed at a winter cut height of 3m maximum.

All plants to be protected with Tubex Easy wrap or equivalent.

GENERAL NOTES:

1. ALL DIMENSIONS AND LEVELS SHALL BE CHECKED ON SITE PRIOR TO CONSTRUCTION WORK COMMENCING.
2. ALL LANDSCAPE DRAWINGS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ENGINEER'S AND ARCHITECT'S DRAWINGS AND SPECIFICATIONS.
3. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE LANDSCAPE SPECIFICATION.
4. ANY DISCREPANCY CONCERNING THE DRAWINGS SHOULD BE REFERRED TO THE CA IMMEDIATELY.
5. ALL DIMENSIONS IN MILLIMETERS UNLESS NOTED OTHERWISE.
6. ALL LEVELS IN METERS.
7. DO NOT SCALE OFF THIS DRAWING.
8. EXISTING SERVICE ALIGNMENTS SHALL BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO CONSTRUCTION WORK COMMENCING.

Legend

- Site boundary
- Existing vegetation, consisting of poorly maintained hedgerows and trees and scrub
- Proposed hedgerow (locally indigenous species) managed to a winter cut height of 3m
- Proposed hedgerow with randomly spaced trees
- Proposed area to be seeded with species rich grassland mix
- Wildlife Protection Zone (WPZ) Min 6m wide. To be left to revegetate naturally

Notes:

- Drawing to be printed in colour

2768_03
Landscape Masterplan

N

THE Landmark PRACTICE
Hope Chapel House
Hope Chapel Hill
Hotwells
Bristol BS8 4ND
United Kingdom
Tel: +44 (0)117 923 0455
enquiries@thelandmarkpractice.com
www.thelandmarkpractice.com

CLIENT
BL_SOLAR_7_LTD

PROJECT
BARNHAM_COURT

TITLE
LANDSCAPE_MITIGATION_PLAN

Status:	Drawn:	Checked:
FOR_PLANNING	JL	MR
Scale:	Date:	Approved:
1:2500@A3	21/07/15	NR

Drawing Number: 2768_200_MITIGATION_PLAN Rev: A

Reproduced with the permission of the controller of her Majesty's Stationary Office.© Crown Copyright - Licence No. AR100017235
ARUN DISTRICT COUNCIL BN/29/15/PL